

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Abraham Whistler Operator Well No.: 8127

LOCATION: Elevation: 1400' Quadrangle: Hundred, W.VA, PA
District: Battelle County: Monongalia
Latitude: _____ Feet South of 39 Deg. 40 Min. 03.00 Sec.
Longitude: _____ Feet West of -80 Deg. 23 Min. 52.97 Sec.

Well Type: OIL GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 06/26/2023 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:


Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 1st day of August, 2023, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|----------------------------------|-------|---------|--------------------------|-------------------------------|
| Expandable Cement w/ Gas Blocker | 3287' | 1660' | 5/8" Sucker Rods - 3282' | 0' |
| Thixotropic Cement w/ Green Dye | 1660' | 1024' | 2 3/8" Tubing - 3287' | 0' |
| Expandable Cement | 1024' | Surface | 5 1/2" Casing - 1650' | 1562' (Multiple perforations) |
| | | | 7" Casing - 1432' | Unknown |
| | | | 16" Conductor Pipe - 0' | 20' |
| | | | | |
| | | | | |

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 24th day of August, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 25th day of September, 2023



My commission expires: June 8, 2027
Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

KAREN C. & ROBERT D. COPELAND
Lease or Property Owner
13448 MASON DIXON HWY. BURTON, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

HUNDRED W.VA, PA
Well Location

BATTELLE
District

MONONGALIA
County

8127
Well No.

ABRAHAM W. WHISTLER
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KARLIE D. SMALLWOOD being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 1st day of August, 2023 and that the well was plugged in the following manner:

| Sand or Zone Record Formation | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|---|--------------------------|---|---------------|----------------|
| Removed all 5/8" sucker rods from the surface to 3282'. Removed all 2 3/8" tubing from the surface to 3287'. Due to extreme bonding the existing 5 1/2" casing was perforated with 4 shots at each of the following depths: 3183', 3083', 2983', 2883', 2783', 2683', 2583', 2483', 2383', 2283', 2183', 2083', 1983', 1883', 1783' and 1683'. Cemented the bottom hole from 3287' to 1660' with 150 sacks of Expandable Cement with a Gas Blocker additive. Cut 5 1/2" casing at 1650' and removed 1650' of 5 1/2" casing from the surface to 1650'. Left 1562' of 5 1/2" casing in the hole from 1650' to 3212'. A diligent effort was made to remove additional 5 1/2" casing but all efforts were unsuccessful. Removed 1432' of 7" casing from the surface to 1432'. A diligent effort was made to remove additional 7" casing but all efforts were unsuccessful. Left an unknown amount of 7" casing in the hole from 1432' to an unknown depth. Cleaned a 9 7/8" hole from the surface to the top of the remaining 7" casing at 1432'. Cleaned a 6 1/4" hole from 1432' to the top of the bottom hole plug at 1660'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1224.5' - 1231.0'). Left 20' of 16" conductor pipe in the hole from the surface to 20'. <u>Cemented the hole from 1660' to the surface as follows:</u> From 1650' to 1024' with 325 sacks of Thixotropic Cement with Green Dye. Tagged top of Thixotropic Cement plug at 1024'. Cemented the hole from 1024' to the surface with 530 sacks of Expandable Cement. Cement did circulate at the surface. A total of 1005 sacks of cement were used to fill the hole from 3287' to the surface. | 5/8" Sucker Rods | 3282' | 0' | |
| | 2 3/8" Tubing | 3287' | 0' | |
| | 5 1/2" Casing | 1650' | 1562' | |
| | 7" Casing | 1432' | Unknown | |
| | 16" Conductor | 0' | 20' | |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | <u>1224.5' - 1231.0'</u> | <u>77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u> | | |

... and that the work of plugging and filling said well was completed on the 24th day of August, 2023

And further deponents saith not.


Matthew A. Yearsley

Matthew A. Yearsley

Karlie D. Smallwood

Karlie D. Smallwood

Sworn to and subscribed before me this 24th day of October, 2023



[Signature]
Notary Public

My commission expires:

August 17, 2025

Permit No. 47-061-00608

Well No. 8127

Latitude: 39° 40' 03.00"N

Longitude: -80° 23' 52.97"W