

FILE NO. _____
 DRAWING NO. _____
 SCALE 1" = 300'
 MINIMUM DEGREE OF ACCURACY 1 IN 5000
 PROVEN SOURCE OF ELEVATION COMPANY SURVEY
TIED INTO THE U.S.G.S. NETWORK

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF ENERGY.
 (SIGNED) Paul D. Harbert
 R.P.E. _____ L.L.S. 862

PLACE SEAL HERE

STATE OF WEST VIRGINIA
 DEPARTMENT OF ENERGY
 OIL AND GAS DIVISION

DATE AUGUST 10, 19 89
 OPERATOR'S WELL NO. M3-251
 API WELL NO. 47-61-0950-P

WELL TYPE: OIL ___ GAS ___ LIQUID INJECTION ___ WASTE DISPOSAL ___
 (IF "GAS,") PRODUCTION ___ STORAGE ___ DEEP ___ SHALLOW X ABANDONED X
 LOCATION: ELEVATION 1246.44 WATERSHED JAKES RUN
 DISTRICT CLAY 3 COUNTY MONONGALIA
 QUADRANGLE BLACKSVILLE W.V. - PA. 7.5 + 15' NC

SURFACE OWNER GEORGE W. JOHNSON ACREAGE 32.22
 OIL & GAS ROYALTY OWNER _____ LEASE ACREAGE _____
 LEASE NO. _____

PROPOSED WORK: DRILL ___ CONVERT ___ DRILL DEEPER ___ REDRILL ___ FRACTURE OR STIMULATE ___ PLUG OFF OLD FORMATION ___ PERFORATE NEW FORMATION ___ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) _____


PLUG AND ABANDON ___ CLEAN OUT AND REPLUG X
 TARGET FORMATION NONE ESTIMATED DEPTH _____
 WELL OPERATOR CONSOLIDATION COAL COMPANY DESIGNATED AGENT ROGER E. DUCKWORTH
 ADDRESS P.O. BOX 1314 MORGANTOWN W.V. 26505 ADDRESS P.O. BOX 1314 MORGANTOWN W.V. 26505

194

NOV 30 1989

COUNTY NAME

PERMIT



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Co.
 Coal Operator or Owner
 P.O. Box 1314, Morgantown, W.Va.
 Address

Consolidation Coal Co.
 Coal Operator or Owner
 P.O. Box 1314, Morgantown, W.va.
 Address

George W. Johnson
 Lease or Property Owner
 Rt. 2 Fairview, W.Va.
 Address

Consolidation Coal Co.
 Name of Well Operator
 P.O. Box 1314, Morgantown, W.v.a
 Complete Address

December 27 19 89
 WELL AND LOCATION

Clay District

Monongalia County

WELL NO. M3-251

Johnson Farm


STATE INSPECTOR SUPERVISING PLUGGING Don Ellis

AFFIDAVIT

STATE OF WEST VIRGINIA,
 County of Monongalia ss:
Larry L. Yost and Dennis L. Yost

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Co., well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 27th day of November, 19 89, and that the well was plugged and filled in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing	
			CSG PULLED	CSG LEFT IN
	Pulled 560 ft. of 10" casing; Cleaned wellbore 1341 ft Ran coal protection string as follows; 969 ft. of 4 1/2" casing; 345 ft. of 2 3/8" tubing; Latch down at 960 ft.; Float valve at 969 ft.; Swedge at 970 ft. Circulated cement to surface as follows; 660 sacks of Poz Mix; 420 sacks of expanding type of cement. Let set, bailed dry, set monument.	10"	560ft. TOP	800 ft. BOTTOM
Coal Seams		Description of Monument		
(Name) Pittsburgh -775 ft		6 ft. of 4 1/2" casing with plaque stating Consol M3-251. 47-61-0950-P		



and that the work of plugging and filling said well was completed on the 15th day of December, 19 89.

And further deponents saith not.

Sworn to and subscribed before me this 2nd day of January, 19 90.
Larry L. Yost
Dennis L. Yost
Gelli P. Wilson
 Notary Public

My commission expires:
March 15, 1993

AUG 26 1991
 Permit No. 47-61-0950-P