

LATITUDE 39° 42' 30"

9,000

2,950

LONGITUDE 80° 15' 00"

0.565
1.70 W

TOPO. LOC.
WADESTOWN QUAD.
7 1/2' SERIES

HELEN L. EDDY
CONT. 97.56 ACRES

1200' RADIUS

J. TUTTLE

F. CLOVIS

M. ORD


3.445
1.70 W

NORTH

FILE NO. F2-1-184
DRAWING NO. F2-2-248
SCALE 1" = 500'
MINIMUM DEGREE OF
ACCURACY 1/2500'
PROVEN SOURCE OF
ELEVATION USGS B.M.

I THE UNDERSIGNED, HEREBY CERTIFY
THAT THIS PLAT IS CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF AND
SHOWS ALL THE INFORMATION REQUIRED
BY LAW AND THE REGULATIONS ISSUED
AND PRESCRIBED BY THE DEPARTMENT OF
MINES.

(SIGNED) John F. Ewell, Jr.
R.P.E. 11133 L.L.S.



(+) DENOTES LOCATION OF
WELL ON UNITED STATES
TOPOGRAPHIC MAPS


DATE AUGUST 18, 19 92
OPERATOR'S WELL NO F2-21
API WELL NO.

FORM IV-6
(8-78)

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

47-061-1084-P
STATE COUNTY PERMIT

WELL TYPE: OIL X GAS _____ LIQUID INJECTION _____ WASTE DISPOSAL _____
(IF "GAS", PRODUCTION _____ STORAGE _____ DEEP _____ SHALLOW X _____
LOCATION: ELEVATION 1190 WATERSHED RIGHT BRANCH OF MIRACLE RUN
DISTRICT BATTELLE COUNTY MONONGALIA
QUADRANGLE WADESTOWN
SURFACE OWNER HELEN EDDY ACREAGE 100
OIL & GAS ROYALTY OWNER FORMERLY SOUTH PENN OIL CO. LEASE ACREAGE 100
LEASE NO. _____
PROPOSED WORK: DRILL _____ CONVERT _____ DRILL DEEPER _____ REDRILL X FRACTURE OR
STIMULATE _____ PLUG OFF OLD FORMATION _____ PERFORATE NEW
FORMATION _____ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) _____
PLUG AND ABANDON X CLEAN OUT AND REPLUG _____
TARGET FORMATION GORDEN ESTIMATED DEPTH 3188
WELL OPERATOR EASTERN ASSOC. COAL DESIGNATED AGENT TERRY O. HENDERSHOT
ADDRESS ROUTE 1 BOX 144 ADDRESS ROUTE 1 BOX 144
FAIRVIEW WV. 26570 FAIRVIEW WV. 26570



STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: EDDY, HELEN Operator Well No.: ELI COLLINS 4
F2-21

LOCATION: Elevation: 1190.00 Quadrangle: WADESTOWN
District: BATTELLE County: MONONGALIA
Latitude: 2950 Feet South of 39 Deg. 42 Min. 30 Sec.
Longitude 9000 Feet West of 80 Deg. 15 Min. 0 Sec.

Well Type: OIL X GAS _____

Company: Eastern Associated Coal Corp. Coal Operator Eastern Associated Coal Corp
Route 1 - Box 144 or Owner Route 1 - Box 144
Fairview, WV 26570 Fairview, WV 26570

Agent: Terry O. Hendershot Coal Operator _____
Permit Issued: 10/28/92 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Creig Park and Jim Gump being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randal Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 20th day of November, 1992, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out to depth of	1448'			
Run Loggs Gamma Ray, Neutron and 3 Arm Caliper.				
Pulled old 8" pipe from	860' to 918'	Old 8" left from	918' to 1405'	
Run 403' of 3" and 1042' of 4 1/2" pipe.		Celled hole with	10 sks gell.	
Run 800 sks Portland and 300 sks Chem. Comp.		Cement and got	circulation.	
Pumped, latch down, plug to 999'.				
Bailed water out inside 4 1/2" and checked plug -- OK.				
Pittsburgh Coal 903' to 911'.				

Description of monument: 4 1/2" x 2" swedge, metal plate with A.P.I. # and date plugged. 6/17/93
and that the work of plugging and filling said well was completed on the 10th day of December, 1992.

And furthur deponents saith not.

Sworn and subscribe before me this 15th day of Dec, 1992
My commission expires: 4-15-97

Creig Park
Jim Gump
Randal Mick
Notary Public
1993

Oil and Gas Inspector: Randal Mick