

(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS

FILE NO. _____
 DRAWING NO. _____
 SCALE 1" = 600'
 MINIMUM DEGREE OF ACCURACY 1 IN 5000
 PROVEN SOURCE OF ELEVATION COMPANY SURVEY TIED INTO U.S.G.S. NETWORK

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF ENERGY.
 (SIGNED) Paul D. Harless
 R.P.E. _____ L.L.S. 862

PLACE SEAL HERE

STATE OF WEST VIRGINIA
DEPARTMENT OF ENERGY
OIL AND GAS DIVISION

DATE 3-2, 1994
 OPERATOR'S WELL NO. 4176
 API WELL NO. 47-61-1163-P

WELL TYPE: OIL ___ GAS ___ LIQUID INJECTION ___ WASTE DISPOSAL ___
 (IF "GAS,") PRODUCTION ___ STORAGE ___ DEEP ___ SHALLOW X ABANDONED X
 STATE COUNTY PERMIT

LOCATION: ELEVATION 1170.69 WATER SHED RANGE RUN
 DISTRICT BATTELLE COUNTY MONONGALIA

QUADRANGLE WADESTOWN

SURFACE OWNER CHARLES H. & FRED A. L. PHILLIPS ACREAGE 128.75
 OIL & GAS ROYALTY OWNER _____ LEASE ACREAGE _____

LEASE NO. _____

PROPOSED WORK: DRILL ___ CONVERT ___ DRILL DEEPER ___ REDRILL ___ FRACTURE OR STIMULATE ___ PLUG OFF OLD FORMATION ___ PERFORATE NEW FORMATION ___ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) _____

PLUG AND ABANDON X CLEAN OUT AND REPLUG _____

TARGET FORMATION NONE ESTIMATED DEPTH _____

WELL OPERATOR CONSOLIDATION COAL CO DESIGNATED AGENT ROGER E. DUCKWORTH
 ADDRESS P.O. BOX 1314 MORGANTOWN WY. 26505 ADDRESS P.O. BOX 1314 MORGANTOWN WY. 26505

JUN 17 1994

was: 70963

FORM WW-8

COUNTY NAME
 PERMIT

FORM WR-38
(Affidavit of Plugging)

STATE OF WEST VIRGINIA
DEPARTMENT OF ENERGY
OIL AND GAS WELLS DIVISION

RECEIVED
WV Division of
Environmental Protection

JAN 18 1996

Permitting
Office of Oil & Gas

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Company
Coal Operator or Owner
P.O. Box 1314, Morgantown, WV 26505-1314
Address

Coal Operator or Owner
Address
Charles Phillips
Lease or Property Owner
Rt. 1, Box 211, Wadestown, WV 26589
Address

Consolidation Coal Company
Name of Well Operator
P.O. Box 1314, Morgantown, WV 26505-1314
Complete Address
Sept. 13, 19 94

WELL AND LOCATION
Battelle District
Monongalia County
WELL NO. 4176

Charles Phillips Fa

STATE INSPECTOR SUPERVISING PLUGGING

Randal Micks

AFFIDAVIT

STATE OF WEST VIRGINIA,

ss:

County of Harrison

Kevin Wright


and Glen Andrew Lang

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Co, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23rd day of August 19 94, and that the well was plugged and filled in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing	
			CSG PULLED	CS LEFT
Cleaned 9 7/8" hole from surface to 1190'. Cleaned 7 7/8" hole from 1190' to 1405'. Cleaned 9 7/8" hole thru Pittsburgh Coal from 998' to 1006'. Ran coal protection string as follows: 209.96' of 2" tubing followed by 1178.95' of 4 1/2" casing. Cemented hole from 1388.89' back to surface. Latch down plug at 1158.07'. Float valve at 1178.93'. Swedge at 1179.93'. Circulated cement to surface as follows: Pumped 845 sacks of poz mix followed by 370 sacks of thixotropic cement. Used 1,000 gallons of mud flush. Displaced cement to 1158.07' with water. let set and bailed dry.				
TOTAL DEPTH: 1,405 feet				
Coal Seams	Description of Monument			
(Name) Pittsburgh Coal	998 feet to 1006 feet	5 feet of 4 1/2" casing with plaque stating: Consolidation Coal Co. Well 4176		
(Name)		Permit #47-61-1163-P		
(Name)				
(Name)				

and that the work of plugging and filling said well was completed on the 6th of September, 19 94.

And further deponent does not



Sworn to

at Charleston this

13th

day of

Sept.

1994

Kevin G. Wright
Glen Andrew Lang
Charlotte Keater
Notary Public