

A = N 40° 00' E 198.00
 B = N 12° 00' W 165.00

(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS

FILE NO. _____
 DRAWING NO. _____
 SCALE 1" = 600'
 MINIMUM DEGREE OF ACCURACY 1 IN 5000
 PROVEN SOURCE OF ELEVATION COMPANY SURVEY TIED INTO U.S.G.S. NETWORK

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF ENERGY.
 (SIGNED) Paul D. Hubert
 R.P.E. _____ L.L.S. 862

PLACE SEAL HERE

STATE OF WEST VIRGINIA
 DEPARTMENT OF ENERGY
 OIL AND GAS DIVISION



DATE 1-17, 19 92
 OPERATOR'S WELL NO. 4148
 API WELL NO. _____

WELL TYPE: OIL ___ GAS ___ LIQUID INJECTION ___ WASTE DISPOSAL ___
 (IF "GAS,") PRODUCTION ___ STORAGE ___ DEEP ___ SHALLOW X ABANDONED X

LOCATION: ELEVATION 1469.92 WATERSHED RANGE RUN
 DISTRICT BATTELLE COUNTY MONONGALIA

QUADRANGLE WADESTOWN, WV, PA
 SURFACE OWNER GEORGE BREIDING ACREAGE 101.60

OIL & GAS ROYALTY OWNER _____ LEASE ACREAGE _____
 LEASE NO. _____

PROPOSED WORK: DRILL ___ CONVERT ___ DRILL DEEPER ___ REDRILL ___ FRACTURE OR STIMULATE ___ PLUG OFF OLD FORMATION ___ PERFORATE NEW FORMATION ___ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) _____

PLUG AND ABANDON ___ CLEAN OUT AND REPLUG X
 TARGET FORMATION NONE ESTIMATED DEPTH _____
 WELL OPERATOR CONSOLIDATION COAL CO. DESIGNATED AGENT ROGER E. DUCKWORTH
 ADDRESS P.O. BOX 1314 MORGANTOWN WV 26505 ADDRESS P.O. BOX 1314 MORGANTOWN WV 26505

FORM WW-6 HALLS INC. 058065

NORTH
 8,300' LONGITUDE
 80°20'00"

AFFIDAVIT OF PLUGGING AND FILLING WELL

WV Division of
Environmental Protection

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Company
Coal Operator or Owner
P. O. Box 1314, Morgantown, WV 26507-1314
Address

Consolidation Coal Company
Name of Well Operator
P.O. Box 1314, Morgantown, WV 26507-1314
Complete Address

December 01 19 95

WELL AND LOCATION

Coal Operator or Owner
Address

Battelle District

George Breiding
Lease or Property Owner
540 Elmina Street, Morgantown, WV 26505
Address

Monongalia County

WELL NO. 4148

George Breiding Farm

STATE INSPECTOR SUPERVISING PLUGGING

Randal Micko

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of Harrison

ss:

G. Andrew Lang

and

Kevin Wright


being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11th day of October, 19 95, and that the well was plugged and filled in the following manner:

| Sand or Zone Record Formation | Filling Material | Plugs Used Size & Kind | Casing | |
|---|------------------|--|---------------|----------------|
| | | | CSG PULLED | CSG LEFT IN |
| Cleaned 9 7/8" hole from surface to 1426'. Reduced hole to 7 7/8" and cleaned 7 7/8" hole from 1426' to 1776'. Cleaned 9 7/8" hole thru Pittsburgh coal from 1302' to 1309'. Pulled 8 5/8" casing from 1184' to 1426'. Left 8 5/8" casing in hole from 1426' to 1746'. Ran coal protection string as follows: 284.40' of 2 3/8" tubing followed by 1478.29' of 4 1/2" casing. Cemented hole from 1762.69' back to surface using 745 sacks of poz mix and 190 sacks of thixotropic cement. Latch down plug at 1457.86'. Float valve at 1478.29'. Swedge at 1479.29'. Cement did circulate. Used 1000 gallons of mud flush. Displaced cement to 1457.86' with water let set and bailed dry. | | | | |
| TOTAL DEPTH: 1,776 feet | | | | |
| Coal Seams | | Description of Monument | | |
| (Name) Pittsburgh | 1302' to 1309' | 5' of 4 1/2" casing with plaque stating: Consolidation Coal Co. Well #4148 | | |
| (Name) | | Permit #47-61-1211-P | | |

Handwritten initials and date: 10/21/95

and that the work of plugging and filling said well was completed on the 24th day of October, 19 95.

And further deponents ~~swear~~ subscribed before me.



Sworn

and subscribed before me this 01st day of December, 19 95.

Kevin S. Wright
Glen Andrew Lang
Charlotte Heister
Notary Public

OCT 03 1995