

LATITUDE 39° 40' 00"

5600'

1950'

LONGITUDE 80° 17' 30"

TOPG. LOC.
WADESTOWN QUAD.
7 1/2' SERIES

0.375
1.06 W

Kyle Howard

G. YOST

WELL F2-461

H. TENNENT

1200' RADIUS


NORTH

FILE NO. F2-1-232
DRAWING NO. F2-2-288
SCALE 1"=400'
MINIMUM DEGREE OF
ACCURACY 1/2500'
PROVEN SOURCE OF
ELEVATION USGS B.M.

I THE UNDERSIGNED, HEREBY CERTIFY,
THAT THIS PLAT IS CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF AND
SHOWS ALL THE INFORMATION REQUIRED
BY LAW AND THE REGULATIONS ISSUED
AND PRESCRIBED BY THE DEPARTMENT OF
MINES.

(SIGNED)

John F. Ewell Jr.
R.P.E. 11133 L.L.S.



(+) DENOTES LOCATION OF
WELL ON UNITED STATES
TOPOGRAPHIC MAPS

DATE NOV. 25, 2000
OPERATOR'S WELL NO. F2-461
API WELL NO.

FORM IV-6
(8-78)

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

47-061-1400P
STATE COUNTY PERMIT

was 061 70896

WELL TYPE: OIL X GAS ___ LIQUID INJECTION ___ WASTE DISPOSAL ___
(IF "GAS", PRODUCTION ___ STORAGE ___ DEEP ___ SHALLOW X)
LOCATION: ELEVATION 1340 WATERSHED RIGHT BRANCH MIRACLE RUN
DISTRICT BATTELLE COUNTY MONONGALIA
QUADRANGLE WADESTOWN
SURFACE OWNER GENE YOST ACREAGE 20
OIL & GAS ROYALTY OWNER PENNZOIL CO. LEASE ACREAGE

PROPOSED WORK: DRILL ___ CONVERT ___ DRILL DEEPER ___ REDRILL X FRACTURE OR
STIMULATE ___ PLUG OFF OLD FORMATION ___ PERFORATE NEW
FORMATION ___ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) ___

PLUG AND ABANDON: CLEAN OUT AND REPLUG X
TARGET FORMATION GORDON SAND ESTIMATED DEPTH 2600
WELL OPERATOR EASTERN ASSOC. COAL DESIGNATED AGENT TERRY D. HENDERSHOT
ADDRESS 1044 MIRACLE RUN ROAD ADDRESS 1044 MIRACLE RUN ROAD
FAIRVIEW WV. 26570 FAIRVIEW WV. 26570

DEC 22 2000

MONO 1400 P

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Gene Yost Operator Well No.: F2-461

LOCATION: Elevation: 1430' Quadrangle: Wadestown
District: Battelle County: Monongalia
Latitude: 1950' Feet South of 39 Deg. 40 Min. 00 Sec.
Longitude: 5600' Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL X GAS _____

Company: Eastern Associated Coal Corp. Coal Operator Eastern Associated Coal Corp.
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, W. Va. 26570 Fairview, W. Va. 26570

Agent: Terry O. Hendershot Coal Operator _____
or Owner _____

Permit Issued Date: December 26, 2000

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Micky Hayhurst and Danny Corter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 03 day of January, 2001, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out to depth of 2100'				
Logged well Gamma Ray Neutron & 3 Arm Caliper				
Run 1 1/2" pipe to depth of 2100', Run 10 sks gell & 200 sks Portland				
Run 4 1/2" pipe to 1326' Run 20 sks gell. Run 428 sks Portland & 150 sks Elk expandable cement				
Pumped latch down plugged to depth of 1306'				
Bailed water out inside 4 1/2" pipe checked O. K.				
<input checked="" type="checkbox"/> Pittsburgh Coal 1168' to 1176'				

Description of monument: 4 1/2" pipe Metal Plate A.P.I. # & Date Plugged and that the work of plugging and filling said well was completed on the 12 day of February, 2001.

And further deponents saith not. Michael Hayhurst
Danny O. Corter

Sworn and subscribe before me this 26th day of February
My commission expires: January 13, 2003

Allen K. Moore
Notary Public
Oil and Gas Inspector: Randall Mick



MONO 1400 P