


STATE OF WEST VIRGINIA  
 DEPARTMENT OF ENVIRONMENTAL PROTECTION  
 OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Thomas Marshall Operator Well No.: F2-450

LOCATION: Elevation: 1,133 Quadrangle: Wadestown  
 District: Battelle County: Monongalia  
 Latitude: 2,800 Feet South of 39 Deg. 40 Min. 00 Sec.  
 Longitude: 6,000 Feet West of 80 Deg. 17 Min. 30 Sec.



Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal Corp Coal Operator: Eastern Associated Coal Corp  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator: \_\_\_\_\_  
 or Owner \_\_\_\_\_

Permit Issued Date: July 3, 2001

AFFIDAVIT

STATE OF WEST VIRGINIA,  
 County of Monongalia ss:

Jeffery Hostuttler and Kenneth M. Gump being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 3rd day of July, 2001, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out to 3,059 ft.			
	Ran 3,060 feet of 1 1/2" tubing and 100 sacks for bottom plug. Pulled 1 1/2" tubing.			
	Logged well—Gamma Ray, Neutron and 3-arm caliper.			
	Cut 5" pipe at 1,685 feet and then pulled 5" pipe. Ran 1,818 feet of 1 1/2" tubing and pumped cement plug with 67 sacks of cement. Cut 7" pipe at 1,050, 1,000, & 950 and then pulled 1,119 feet of 7" pipe.			
	Ripped 8" pipe 891 feet to 921 feet.			
	Ran 1,121 feet of 4 1/2" casing and cemented with 300 sacks.			
	Swabbed water out and checked plug at 960 feet. — OK			
	Pittsburgh Coal: 902 - 909			


Description of monument: 4 1/2" Pipe with metal plate, API#, Date plugged and that the work of plugging and filling said well was completed on the 3<sup>rd</sup> day of August 2001.

And further deponents saith not. Jeffery Hostuttler  
Kenneth M. Gump

Sworn and subscribe before me this 28<sup>th</sup> day of AUGUST 2001.  
 My commission expires: July 7, 2007

[Signature]  
 Notary Public

Oil and Gas Inspector: [Signature]



MOND 1412-P