

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Huskie Lumber Company Operator Well No.: SC-2 (Access)

LOCATION: Elevation: 1409' Quadrangle: WADESTOWN, PA 7.5"

District: BATTELLE County: MONONGALIA

Latitude: _____ Feet South of 39 Deg. 40 Min. 00 Sec.

Longitude: _____ Feet West of 80 Deg. 20 Min. 30 Sec.

Well Type: OIL _____ GAS X

Company WEST VIRGINIA LAND RESOURCES, INC. Coal Operator WEST VIRGINIA LAND RESOURCES, INC.
46226 NATIONAL ROAD WEST or Owner 1 BRIDGE STREET MONONGAH, WV 26554
ST. CLAIRSVILLE, OH 43950

Agent David Roddy Coal Operator _____
or Owner _____

Permit Issued Date 3/16/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 9th day of May, 2022 and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement	896'	Surface		
7" Casing	974.6'	Surface	None	974.6'
9 5/8" Casing	42'	Surface	None	42'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 10th day of May, 2022.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 13th day of Jun, 2022

My commission expires: 09/15/22
Thomas J. Sullivan
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATED, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
46226 NATIONAL ROAD WEST ST. CLAIRSVILLE, OH 43950
Address

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
FREDERICK A. SIX
Lease or Property Owner
P.O BOX 55 Wana, WV 26590
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WADESTOWN, PA 7.5"
Well Location
BATTELLE
District
MONONGALIA
County
SC-2A
Well No.
HUSKIE LUMBER COMPANY
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of MONONGALIA ss:


Kevin S. Wright and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 9th day of May, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Logged access hole from surface to bottom of 7" casing at 934'. Attempted to remove 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Set cast iron bridge plug at 896'. Cemented hole from 896' to the surface 145 sacks of Expandable Cement. Cement did circulate at the surface. Access hole continues on a curve from 896' until intersection with the production hole at coal seam. The bottom of the access hole is plugged back from the SC-2 production hole plugging. See SC-2 Affidavit for details. Left 974.6' of 7" casing from surface to 974.6'. Left 42' of 9 5/8" from surface to 42'.		7" Steel Casing	0'	974.6'
		9 5/8" Steel Casing	0'	42'
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	(1237.8' - 1243.7')			

... and that the work of plugging and filling said well was completed on the 10th day of May 22, 2022

And further deponents saith not.

Kevin S. Wright
Kevin S. Wright
Matthew A. Yearsley
Matthew A. Yearsley



Sworn to and signed before me this 17th day of Jun 2022

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-061-01551
Well No. SC-2A
Latitude: 39° 40' 00"N
Longitude: 80° 20' 30"W