

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: S. Wilson 46.3 ac., current owner - William Gum Operator Well No.: FZ- 549

LOCATION: Elevation: 1,354' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 8.077 Feet South of 39 Deg. 42 Min. 30 Sec.
Longitude: 2.446 Feet West of 80 Deg. 12 Min. 30 Sec.
Well Type: OIL _____ GAS X

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator: _____
or Owner _____

Permit Issued Date: July, 08, 2008

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Eric Dale Chisholm and Kenneth Thomas Crump first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Triston Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 13th day of January, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
			Cleaned out to 1,250' with an 10" bit.	Cleaned out to 1,338' with a 8" bit.
			Logged the hole with Century Geophysical. Coal seam at 1,028' to 1,036' based on log information.	
			Ran 1-1/2" tubing and pumped the bottom plug with 85 sacks of E1K expanding cement.	
			Tagged bottom plug at 1,138'. Ran 1,138' of 4-1/2" casing with latchdown plug at 1,118'.	
			Pumped the top plug with 800 sacks of E1K expanding cement and 250 sacks of cement.	
			Swabbed water off latchdown plug at 1,118'.	


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 10th day of March, 2009.

And further deponents saith not. Eric Dale Chisholm
Kenneth Thomas Crump

Sworn and subscribe before me this 10th day of March, 2009.

My commission expires: July 7, 2017
Edward Y. Hoy
Notary Public

Affidavit review by the office of Oil and Gas: _____
Title: _____



RECEIVED
Office of Oil & Gas

JUN 12 2012

WV Department of
Environmental Protection