

Rev (5-01)
WR-38
DATE: 11-3-10

API # 47-6101601P

61-01601P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Perkey, Arlyn Operator Well No.: F2- S51

LOCATION: Elevation: 1,668' Quadrangle: Blacksville
 District: Clay County: Monongalia
 Latitude: 12,291' Feet South of 39 Deg. 40 Min. 00 Sec.
 Longitude: 6,157' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL GAS

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner: 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner: _____

Permit Issued Date: September 4, 2009

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Gary C Thomas and Eric Dale Chisholm being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 14th day of December, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out with $3/2$ 1/4" bit to 480'. Cleaned out with $3/2$ 5/8" bit to 1,572'.				
Logged the hole with Timco Inc. There is 10" pipe from 480' to 1252', which was shot at and above the coal seam. The bottom of the Pittsburgh coal seam is 1243'.				
Ran tubing and pumped the bottom plug with expanding cement. The top of the bottom plug is 1,348' deep.				
Ran 1348' of 4-1/2" tubing and pumped the top plug with expanding cement. A total of 512 sacks of expanding cement were used. Swabbed water off hole. Latch down plug at 1321'.				


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 31st day of December, 2009.

And further deponents saith not. Gary C Thomas
Eric Dale Chisholm

Sworn and subscribe before me this 2nd day of November, 2010
My commission expires: July 7, 2011

Notary Public
[Signature]

Oil and Gas Inspector: [Signature]



RECEIVED
Office of Oil & Gas
JUN 12 2012
Department of
Environmental Protection