

Rev (5-01)
WR-38
DATE: 07-16-10

API # 47-6101603P

61-01603P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Tennant, Rodney Operator Well No.: F2-S2

LOCATION: Elevation: 1,399' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 10.859' Feet South of 39 Deg. 40 Min. 00 Sec.
Longitude: 7.216' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: Oil GAS

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner: 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner

Permit Issued Date: September 11, 2009

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Gary C Thomas and [Signature] being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 16th day of November, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with 12" bit to 154'. Then ran 207' of 8" inch casing. Then Cleaned out with 7 3/4" bit to 1350'.			
	Logged the hole with Timco Inc. Coal seam is at 1014' based on log information. There is 8" casing from the surface to 200' deep. There is 10" casing from 612' to 1230', which was shot at and above the coal seam by Timco. There is also 8" casing from 1230' to 1350'.			
	Ran 1142' of 4-1/2" casing. B.J. Hughes pumped the bottom plug with 50 sacks of expanding cement. Then B.J. Hughes pumped 512 sacks of cement in the top plug.			
	Swabbed water off hole. Latch down plug at 1118'.			


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 11th day of December 2009.

And further deponents saith not. [Signature]

Sworn and subscribe before me this 16th day of July, 2010

My commission expires: July 7, 2017
Notary Public

[Signature]
#3110



RECEIVED
Office of Oil & Gas

JUN 12 2012

WV Department of Environmental Protection
Oil and Gas Inspector: