

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Payton, Clarence Operator Well No.: F2- S37

LOCATION: Elevation: 1,379' Quadrangle: Grant Town  
 District: Clay County: Monongalia  
 Latitude: 1,465' Feet South of 39 Deg. 37 Min. 30 Sec.  
 Longitude: 9,725' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Matthew L. Bonnell Coal Operator \_\_\_\_\_  
 or Owner \_\_\_\_\_

Permit Issued Date: December 6, 2012

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

x Jeff Sine and x Eric Dale Chister being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 23<sup>rd</sup> day of January, 2013, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with a 12 1/4" to 934'. Then cleaned out with a 6 1/4" bit to 1,865'.			
	Ran logs with Century Wireline Services. Based on the logs the Pittsburgh coal seam is 931" to 938". Based on the caliper logs, there was 8" casing from 934' down to 1,740'. We milled up the 8" casing down to 950'. We then shot the casing every 50 feet from 1,000 to 1,700'.			
	There is a bottom hole cement plug from 1,865' up to 1,140'. Then they set an expanding cement plug from 1,140' to 810'. Then from 810' to surface it was filled with cement.			
	There were 1,055 sacks of Portland and 175 sacks of expanding cement used to plug the well.			

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 22<sup>nd</sup> day of February, 2013.

And further deponents saith not. x Jeff Sine  
x Eric Dale Chister


Sworn and subscribe before me this 25<sup>th</sup> day of March, 2013  
My commission expires: July 1, 2017

[Signature]  
Notary Public  
Oil and Gas Inspector: [Signature]

RECEIVED  
Office of Oil and Gas  
Oil and Gas Inspector:

NOV 24 2014

WV Department of  
Environmental Protection



11/28/2014