

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Solomon M. Shriver Operator Well No.: 8232

LOCATION: Elevation: 1118.5' Quadrangle: Hundred W.VA, PA
District: Battelle County: Monongalia
Latitude: 39.6627 Feet South of 39 Deg. 39 Min. 45.72 Sec.
Longitude: -80.3653 Feet West of 80 Deg. 21 Min. 55.08 Sec.

Well Type: OIL _____ GAS x

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 5/22/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 29 day of November, 2023, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic with Green Dye and Gas Blocker	1214'	749'	16" Conductor	20'
Expandable Cement	749'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 13 day of December, 2023.

And further deponents saith not. Matthew A. Yearsley

John Campbell

Sworn and subscribe before me this 28th day of December, 2023



My commission expires: June 8, 2027

Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
GEORGE D. SIX
Lease or Property Owner
11023 MASON DIXON HWY, BURTON WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WADESTOWN W.VA, PA
Well Location
BATTELLE
District
MONONGALIA
County
8232
Well No.
SOLOMON M. SHRIVER
Farm

STATE INSPECTOR SUPERVISING PLUGGING Gayne Knitowski

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29th day of November, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from surface to 238'. Reduced to 9 7/8" hole at 238'. Cleaned a 9 7/8" hole from 238' to 1214'. Cleaned a 9 7/8" hole through Pittsburgh Coal Seam (949.5' to 956'). Left 20' of 16" conductor from 20' to surface.		16" Conductor	0'	20'
Cemented Hole from 1214' to surface as follows: Cemented bottom hole plug from 1214' to 749' with 225 sacks of Thixotropic Cement with Green Dye and Gas Blocker. Cemented from 749' to surface with 360 sacks of Expandable Cement. Cement did circulate at the surface. A total of 585 sacks were used to fill the hole from 1214' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>949.5' - 956'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 13th of December, 2023

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley


John Campbell
John Campbell

Sworn to and subscribed before me this 28th day of December, 2023

Christopher Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-061-01936-00-00
Well No. 8232
Latitude: 39° 39' 45.72"N
Longitude: -80° 21' 55.08"W