

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.P. Kennedy Operator Well No.: 8137

LOCATION: Elevation: 1440' Quadrangle: Hundred, W.VA, PA  
District: Battelle County: Monongalia  
Latitude: 39.67129 Feet South of 39 Deg. 40 Min. 16.6432 Sec.  
Longitude: -80.39765 Feet West of -80 Deg. 23 Min. 51.5519 Sec.

RECEIVED  
Office of Oil and Gas  
JAN 08 2025  
WV Department of  
Environmental Protection

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc Coal Operator West Virginia Land Resources, Inc  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 07/09/2024 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of October, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Theotropic with Green Gye and Gas Blocker	1500'	1046'	8 5/8" Casing - 0'	Unknown
Expandable Cement	1046'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7' casing with Company Name, Well #, API #, and Date Completed and that the work of plugging and filling said well was completed on the 6th day of November, 2024.

And further deponents saith not. Matthew A. Yearsley  
John Campbell



Sworn and subscribe before me this 11th day of December, 2024

My commission expires: August 13, 2029 Kerri A. McCormick  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
PAT O. EVERETT KENNEDY  
Lease or Property Owner  
7500 BELLE PLAIN DR., DAYTON, OH 45424  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
HUNDRED, W.VA, PA  
Well Location  
BATTELLE  
District  
MONONGALIA  
County  
8137  
Well No.  
J.P. KENNEDY  
Farm

RECEIVED  
Office of Oil and Gas

JAN 08 2025

WV Department of  
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING GAYNE KNITOWSKI

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4<sup>th</sup> day of October, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from surface to 210'. Reduced to 9 7/8" bit and cleaned 9 7/8" hole from 210' to 1383'. Cleaned 9 7/8" hole through the Pittsburgh Coal Seam (1244.5' - 1251'). Top of 8 5/8" casing found at 1383'. Reduced to 7 7/8" bit and cleaned 7 7/8" hole inside of 8 5/8" casing from 1383' to 1500'. Place a cut in 8 5/8" casing at 1451' and 1401'. A diligent effort was made to remove the 8 5/8" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left an unknown amount of 8 5/8" casing below 1383'.		8 5/8" Casing 16" Conductor Casing	0' 0'	Unknown 20'
Cemented hole from 1500' to surface as follows:				
Cemented hole from 1500' to 1046' with 280 sacks of Thixotropic Cement with Green Dye and Gas Blocker. Cemented hole from 1046' to surface with 615 sacks of Expandable Cement. Cement did circulate at the surface. A total of 895 sacks of cement were used to fill the hole from 1500' to the surface.				
Coal Seams		Description of Monument		
Pittsburgh	1244.5' - 1251'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 6<sup>th</sup> day of November, 2024

And further deponents saith not



Matthew A. Yearsley

Matthew A. Yearsley

John Campbell

John Campbell

Sworn to and subscribed before me this 11<sup>th</sup> day of December

Kerri A. McCormick  
Notary Public

My commission expires: August 13, 2029

Permit No. 47-061-01958  
Well No. 8137  
Latitude: 39° 40' 16.64"N  
Longitude: -80° 23' 51.55"W