

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Abraham W. Whistler Operator Well No.: 8132

LOCATION: Elevation: 1,338.14' Quadrangle: Hundred
District: Battelle County: Monongalia
Latitude: 39.669263 Feet South of 39 Deg. 40 Min. 9.4 Sec.
Longitude: -80.397879 Feet West of 80 Deg. 23 Min. 52.4 Sec.

RECEIVED
Office of Oil and Gas

APR 14 2025

WV Department of
Environmental Protection

Well Type: OIL X GAS

Company West Virginia Land Resources Coal Operator West Virginia Land Resources
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator
Permit Issued Date 1/13/2025 or Owner

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 27th day of January, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Throatropes w/ Green Dye & Gas Blocker	1404'	1057'	6 5/8" Casing - None	1,048'
EZ Seal Grout	720'	Surface	14" Drisco Pipe - None	20'
			16" Casing - None	20'

Description of monument: 77" of 7' casing with company name, well #, API#, and date completed and that the work of plugging and filling said well was completed on the 11th day of February, 2025.


And further deponents saith not. Matthew A. Yearsley

John Campbell

Sworn and subscribe before me this 4th day of April, 2025

My commission expires: August 13, 2029

Kerri A. McCormick
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
KAREN C. & ROBERT D. COPELAND
Lease or Property Owner
13448 Mason Dixon Hwy Burton, WV 26562
Address

WEST VIRGINIA LAND RESOURCES
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Hundred
Well Location
Battelle
District
Monongalia
County
8132
Well No.
Abraham W. Whistler
Farm

RECEIVED
Office of Oil and Gas
APR 14 2025
WV Department of
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING Gayne Knitowski

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 27th day of January, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned the hole with a 12 1/4" bit from surface to 278'. Reduced to a 9 7/8" bit at 278'. Cleaned hole with 9 7/8 bit from 278' to 1404'. Tagged plug at 1404'. Cleaned 9 7/8" hole through Pittsburgh Coal Seam from 1,150' to 1,157'.		6 5/8" Casing	0	1,048'
		14" Drisco Pipe	0	20'
		16" Conductor	0	20'
Cemented hole from 1404' to 1057' as follows: From 1404' to 1000' with 310 sacks of Thixotropic Cement with Green Dye and Gas Blocker. Tagged top of cement at 1000' and drilled cement back down to 1,057'. Left 20' of 16" conductor at surface. The uncemented portion of this well was converted into a coal degasification hole and will be cemented to surface at a later date. Installed 1,048' of 6 5/8" casing (300' of slotted & 748' solid casing) with two 7" grout baskets at 720' and 750'. Grouted annulus of 6 5/8" casing with 150 sacks of EZ Seal grout from 720' to surface. Grout did circulate at surface. A joint of 14" Drisco pipe was installed from surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	1,150' - 1,157'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 11th day of February, 2025



Sworn to and subscribed before me this 4th day of April

My commission expires:

August 13, 2029

Matthew A. Yearsley
Matthew A. Yearsley

John Campbell
John Campbell

Kerri McCormick
Notary Public

Permit No. 47-061-01975
Well No. 8132
Latitude: 39° 40' 9.4"N
Longitude: -80° 23' 52.4"W