

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

RECEIVED
Office of Oil and Gas

APR 22 2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

WV Department of
Environmental Protection

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Whistler 1 Operator Well No.: 8133

LOCATION: Elevation: 1286.08' Quadrangle: Hundred WV
District: Battelle County: Monongalia
Latitude: 39.6680 Feet South of 39 Deg. 40 Min. 05.06 Sec.
Longitude: -80.3941 Feet West of -80 Deg. 23 Min. 38.85 Sec.

Well Type: OIL _____ GAS X

Company	<u>West Virgina Land Resources INC</u>	Coal Operator	<u>West Virgina Land Resources INC</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>2/10/25</u>	or Owner	_____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 14 day of March, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED		LEFT
Thixotropic	1360'	918'	8 5/8" Casing	None	Unknown
Expanding	918'	Surface	16" Conductor Casing	None	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 10 day of April, 2025.

And further deponents saith not. Matthew A. Yearsley
John Campbell



Sworn and subscribe before me this 16th day of April, 2025

My commission expires: August 13, 2029 Kerri A. McCormick
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Gayne Knitowski Digitally signed by Gayne Knitowski Date: 2025.04.17 09:12:53 -0400 Title: Inspector

04/25/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
RICHARD COPELAND
Lease or Property Owner
13448 Mason Dixon Hwy Burton, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Hundred WV
Well Location
Battelle
District
Monongalia
County
8133
Well No.
WHISTLER 1
Farm

RECEIVED
Office of Oil and Gas

APR 22 2025

WV Department of
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING Gayne Knitowski

AFFIDAVIT

Gayne

Knitowski

Digitally signed by
Gayne Knitowski
Date: 2025.04.17
09:13:25 -04'00'


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of March, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from surface to 236'. Reduced hole to 9 7/8" at 236'. Cleaned 9 7/8" hole from 236' to 1119'. Cleaned a 9 7/8" through the Pittsburgh Coal Seam from 1078' to 1085'. Reduced to 7 7/8" at 1119'. Cleaned a 7 7/8" hole from 1119' to an approved depth of 1360'. Attempted to remove 8 5/8" casing by pulling 150% of string weight. All attempts were unsuccessful. Left an unknown amount of 8 5/8" casing from 1119' to unknown. Cut remaining 8 5/8" casing at 1285',1235',1185',1135'.	8 5/8" Casing 16" Conductor Casing	0' 0'	Unknown 20'	
Cemented hole from 1360' to surface as follows: Cemented hole from 1360' to 918' with 180 sacks of Thixotropic Cement with green dye and gas blocker. Cemented from 918' to surface with 500 sacks of Expandable Cement. Cement did circulate at surface. Left 20' of 16" conductor at surface. A total of 680 sacks of cement were used to fill the hole form 1360' to surface.				
Coal Seams		Description of Monument		
Pittsburgh	1078'-1085'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 10th day of April, 2025

And further deponents saith not.



Sworn to and subscribed before me this 10th day of April

Matthew A. Yearsley
Matthew A. Yearsley

John Campbell
John Campbell

Kerri A. McCormick
Notary Public

My commission expires: August 13, 2029

Permit No. 47-061-01977
Well No. 8133
Latitude: 39° 40' 05.06"N
Longitude: -80° 23' 38.85"W

04/25/2025