

AFFIDAVIT OF PLUGGING AND FILLING WELL

08/29/2025



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
KANDY L & RANDY L EARL
Lease or Property Owner
249 Blacks Run Rd., Core, WV 26529
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED W.VA, PA
Well Location
BATTELLE
District
MONONGALIA
County
8162
Well No.
MASON S. HENDERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Gayne Knitowski
AFFIDAVIT

Gayne
Knitowski
Digitally signed by
Gayne Knitowski
Date: 2025.07.29
09:04:27 -04'00'


STATE OF WEST VIRGINIA,
County of WETZEL ss:

MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21st day of June, 2025 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from surface to 294'. Reduced to 9 7/8" bit and cleaned a 9 7/8" hole from 294' to 1247'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (997' – 1004'). Left 20' of 16" Conductor Casing in the hole from surface to 20'. Cemented hole from 1247' to surface as follows: Cemented hole from 1247' to 797' using 240 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 797' to surface using 450 sacks of Expandable Cement. Cement did circulate at the surface. A total of 690 sacks of Cement were used to fill the hole from 1247' to surface.		16" Conductor Casing	0'	20'
Coal Seams		Description of Monument		
Pittsburgh	997' – 1004'	77" of 7" casing w/ company name, well #, API # and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 8th day of July, 2025

And further deponents saith



Matthew A. Yearsley
Matthew A. Yearsley

John Campbell
John Campbell

Sworn to and subscribed before me this 28th day of July 2025

Kerri McCormick
Notary Public

My commission expires August 13, 2029

Permit No. 47-061-01979
Well No. 8162
Latitude: 39° 40' 04.90"N
Longitude: 80° 23' 19.97"W

RECEIVED
Office of Oil and Gas
08/29/2025
AUG 06 2025