



west virginia department of environmental protection

Office of Oil and Gas
601 57th Street, S.E.
Charleston, WV 25304
(304) 926-0450
fax: (304) 926-0452

Harold D. Ward, Cabinet Secretary
www.dep.wv.gov

Thursday, October 1, 2026
PERMIT MODIFICATION APPROVAL
Horizontal 6A / New Drill

NORTHEAST NATURAL ENERGY LLC
707 VIRGINIA STREET EAST
STE 1200
CHARLESTON, WV 25301

Re: Permit Modification Approval for Laurita 5H
47-061-02032-00-00

Extended Lateral

NORTHEAST NATURAL ENERGY LLC

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

If there are any questions, please feel free to contact me at (304) 926- 0450.

A handwritten signature in black ink, reading "H. Jason Harmon".

H. Jason Harmon
Chief

Operator's Well Number: Laurita 5H
Farm Name: NORTHEAST NATURAL ENERGY LLC
U.S. WELL NUMBER: 47-061-02032-00-00
Horizontal 6A New Drill
Date Modification Issued: 10/1/2026

Promoting a healthy environment.

10/02/2026

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
WELL WORK PERMIT APPLICATION

1) Well Operator: Northeast Natural Energy	494498281	Monongalia	Grant	Rivesville
	Operator ID	County	District	Quadrangle

2) Operator's Well Number: 5H Well Pad Name: Laurita

3) Farm Name/Surface Owner: Northeast Natural Energy LLC Public Road Access: Hagans Rd 37

4) Elevation, current ground: 1176' Elevation, proposed post-construction: 1173.5'

5) Well Type (a) Gas ☒ Oil ☐ Underground Storage ☐
Other ☐
(b) If Gas Shallow ☒ Deep ☐
Horizontal ☒

6) Existing Pad: Yes or No No

7) Proposed Target Formation(s), Depth(s), Anticipated Thickness and Expected Pressure(s):
Marcellus, 7,856', 100', 5,110 psi

8) Proposed Total Vertical Depth: 7,937'

9) Formation at Total Vertical Depth: Marcellus

10) Proposed Total Measured Depth: 27,495'

11) Proposed Horizontal Leg Length: 18,947'

12) Approximate Fresh Water Strata Depths: 70', 587'

13) Method to Determine Fresh Water Depths: Drillers log from offset wells (including 47-049-02585)

14) Approximate Saltwater Depths: 1,964'

15) Approximate Coal Seam Depths: 500' and 587'

16) Approximate Depth to Possible Void (coal mine, karst, other): No voids expected

17) Does Proposed well location contain coal seams directly overlying or adjacent to an active mine? Yes ☐ No ☒

(a) If Yes, provide Mine Info: Name: _____
Depth: _____
Seam: _____
Owner: _____

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
WELL WORK PERMIT APPLICATION

1) Well Operator: <u>Northeast Natural Energy LLC</u>	Operator ID: <u>494498281</u>	County: <u>Monongalia</u>	District: <u>Grant</u>	Quadrangle: <u>Rivesville</u>
---	-------------------------------	---------------------------	------------------------	-------------------------------

2) Operator's Well Number: 5H Well Pad Name: Laurita

3) Farm Name/Surface Owner: Northeast Natural Energy LLC Public Road Access: Hagans Rd 37

4) Elevation, current ground: 1176' Elevation, proposed post-construction: 1173.5'

5) Well Type (a) Gas ☒ Oil ☐ Underground Storage ☐
Other ☐
(b) If Gas Shallow ☒ Deep ☐
Horizontal ☒

6) Existing Pad: Yes or No No

7) Proposed Target Formation(s), Depth(s), Anticipated Thickness and Expected Pressure(s):
Marcellus, 7,856', 100', 5,110 psi

8) Proposed Total Vertical Depth: 7,937'

9) Formation at Total Vertical Depth: Marcellus

10) Proposed Total Measured Depth: 27,495'

11) Proposed Horizontal Leg Length: 18,947'

12) Approximate Fresh Water Strata Depths: 70', 587'

13) Method to Determine Fresh Water Depths: Drillers log from offset wells (including 47-049-02585)

14) Approximate Saltwater Depths: 1,964'

15) Approximate Coal Seam Depths: 500' and 587'

16) Approximate Depth to Possible Void (coal mine, karst, other): No voids expected

17) Does Proposed well location contain coal seams directly overlying or adjacent to an active mine? Yes ☐ No ☒

(a) If Yes, provide Mine Info: Name: _____
Depth: _____
Seam: _____
Owner: _____

18)

CASING AND TUBING PROGRAM

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill-up (Cu. Ft.)/CTS
Conductor	24	New	N/A	N/A	100	100	CTS
Fresh Water	13-3/8	New	J-55	54.5	760	730	CTS
Coal	-	-	-	-	-	-	-
Intermediate	9-5/8	New	J-55	36.0	2,110	2,080	CTS
Production	5-1/2	New	HP P-110	23.0	27,495	27,445	6,042
Tubing	2-7/8	New	P-110	6.5	N/A	8,500	N/A
Liners	-	-	-	-	-	-	-

TYPE	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	Cement Yield (cu. ft./k)
Conductor	24	32	N/A	N/A	N/A	Class A or L	1.19
Fresh Water	13-3/8	17-1/2	0.380	2,730	1,600	Class A or L	1.14
Coal	-	-	-	-	-	-	-
Intermediate	9-5/8	12-3/8	0.395	3,520	2,800	Class A or L	1.19
Production	5-1/2	8-3/4	0.415	17,920	12,500	50:50 Poz	1.16
Tubing	2-7/8	N/A	0.217	13,870	N/A	N/A	N/A
Liners	-	-	-	-	-	-	-

PACKERS

Kind:				RECEIVED Office of Oil and Gas SEP 11 2026
Sizes:				WW Department of Environmental Protection
Depths Set:				

Robert J. Hitt
9-1-26

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:

Utilize auger rig to set cellar & conductor. The conductor will be set with cement to surface. Mobilize drilling rig and drill surface section on air. Run surface (freshwater & coal string) casing to desired depth. The surface casing will not penetrate sea level. Surface casing will be cemented to surface. Drill intermediate section on air. Run intermediate casing to desired depth. Intermediate casing will be cemented to surface. Drill on air the production section to the start of the curve (KOP). The well will be loaded with synthetic oil base drilling mud (SOBM). Finish drilling the production section utilizing MWD surveys and geosteering practices to maintain the wellbore in the Marcellus shale and prevent anti-collision. Production casing will be ran to TD and cement top will be inside the intermediate casing.

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

A cement bond log will determine the top of production casing cement. The production casing will be pressure tested. The hydraulic fracturing equipment will then open the toe sleeves and begin pumping the first stage. The plug-and-perf method will be used for the remaining stages. The max anticipated pressure during frac is 12,500 psi and a max rate of 100 bpm. Once frac has finished, a drill out rig will drill all the plugs out of the well. Flowback will then be rigged up and flowback of the well will begin until it is ready to be turned in line via casing flow. At a later time during the life of the well, production tubing will be installed based on the wells performance.

21) Total Area to be disturbed, including roads, stockpile area, pits, etc., (acres): 29.34

RECEIVED
Office of Oil and Gas

22) Area to be disturbed for well pad only, less access road (acres): 11.85

SEP 11 2026

23) Describe centralizer placement for each casing string:

Surface: shoe track & every 3rd joint to surface
Intermediate: shoe track & every 3rd joint to surface
Production: Rigid bow centralizers at shoe track & every joint in the lateral to KOP. Bow springs from KOP to surface every third joint.

WV Department of
Environmental Protection

24) Describe all cement additives associated with each cement type:

Surface: Class A or L Cement + Max 3% bwoc Calcium Chloride Fresh Water blend.
Intermediate: Class A or L Cement + Max 3% bwoc Calcium Chloride + Fresh Water.
Production: 50:50 Poz (Fly Ash & Class A or L) plus additives such as defoamer, retarder, & fluid loss to meet well specific requirements

25) Proposed borehole conditioning procedures:

Surface & intermediate on air will utilize high volumetric flow rates of air to ensure the wellbore is clean prior to TOH.
Production section will utilize synthetic oil based drilling mud to properly clean the wellbore. At TD, pump rate and rotation will be maximized and tripping will begin once the wellbore has been circulated cleaned.
Production casing will be circulated prior to cementing to ensure a prepared wellbore for cement.

*Note: Attach additional sheets as needed.



NORTHEAST NATURAL ENERGY, LLC

Area: Monongalia County, WV
Field: Monongalia
Facility: Laurita Pad
Slot: 5H

Well: Laurita 5H
UWI/Legal: Laurita 5H PWB
Wellbore: Laurita 5H PWP Ex-01
Wellpath: Laurita 5H PWP Ex-01



Well Profile Data

Design Comment	MD (ft)	Inc (")	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	0.00	0.000	80.837	0.00	0.00	0.00	0.00	0.00
SRFC Casing (Est.)	805.00	0.000	80.837	805.00	0.00	0.00	0.00	0.00
INT Casing (Est.)	2150.00	0.000	80.837	2150.00	0.00	0.00	0.00	0.00
KOP	2250.00	0.000	80.837	2250.00	0.00	0.00	0.00	0.00
End of Build	2655.09	12.153	80.837	2652.06	6.82	42.25	3.00	-19.26
KOP	7330.20	12.153	80.837	7222.40	163.55	1013.89	0.00	-462.19
End of 3D Arc	7766.61	35.000	0.000	7627.05	300.28	1060.69	8.00	-378.90
LP	8547.16	90.135	324.087	7981.64	900.88	806.06	8.00	256.89
BHL	27494.16	90.135	324.087	7937.00	16246.18	-10307.39	0.00	19203.84

Bottom Hole Location

MD (ft)	Inc (")	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
27494.16	90.135	324.087	7937.00	16246.18	-10307.39	1786467.64	415483.04	39°38'20.1159"N	80°08'47.0028"W

Scale 1 inch = 3000
Easting (ft)
-13500 -12000 -10500 -9000 -7500 -6000 -4500 -3000 -1500 0 1500 3000 4500

Laurita 5H BHL Rev-1
BHL : 7937.00ft TVD, 16246.18ft N, 10307.39ft W



HDGM2025v1.0 (1900.0 to 2026.0) Dip: 66.03° Field: 51542.5 nT
Magnetic North is 9.41 degrees West of True North (at 2025-07-02)
Grid North is 0.39 degrees West of True North
To correct azimuth from True to Grid add 0.39 degrees
To correct azimuth from Magnetic to Grid subtract 9.02 degrees

Plot reference wellpath is Laurita 5H PWP Ex-01	Grid System: NAD83 / Lambert West Virginia SP, Northern Zone (4701), US feet
True vertical depths are referenced to Rig on Slot #09 (RT)	North Reference: Grid North
Reference wellpath measured depths are referenced to Rig on Slot #09 (RT)	Scale: True distance
Rig on Slot #09 (RT) to Mean Sea Level: 0 feet	Coordinates are in feet referenced to Slot
Mean Sea Level to Ground level (At Slot 5H): 0 feet	Depths are in feet
Offset wellpath MDs are referenced to each path's default MD datum	Created by: Revision on 2026-05-18, Database: WVA_MPL_EASTERNUS_Cuts

Location Information

Facility Name	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
Laurita Pad	1786767.100	396290.500	39°35'40.7910N	80°06'33.9400W
Slot	Local N (ft)	Local E (ft)	Local N (US ft)	Local E (US ft)
5H	-52.64	7.30	1786774.400	396237.800
Rig on Slot #09 (RT) to Ground level (At Slot 5H):	0ft			
Mean Sea Level to Ground level (At Slot 5H):	0ft			
Rig on Slot #09 (RT) to Mean Sea Level:	0ft			

Survey Program

Survey Name	Survey No.	Survey Date	Survey Type	Survey Status	Survey Description	Survey Notes
1	180	1/18	SRFC	Yes	SRFC Casing (Est.)	Laurita 5H PWB
2	180	1/18	INT	Yes	INT Casing (Est.)	Laurita 5H PWB
3	180	1/18	KOP	Yes	KOP	Laurita 5H PWB


Targets

Name	MD (ft)	TVD (ft)	Local N (ft)	Local E (ft)	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
Laurita 5H BHL Rev-1	27494.16	7937.00	16246.18	-10307.39	1786467.64	415483.04	39°38'20.1159N	80°08'47.0028W
Laurita 5H LP Rev-2	N/A	7982.00	799.84	909.18	1787682.53	399987.75	39°35'47.8422N	80°06'23.2044W
Laurita 5H LP Rev-2 (0.18.2026)	N/A	8000.00	15160.51	-14047.66	1787277.60	414397.44	39°38'9.1179N	80°06'34.1098W

Formation Tops

Formation	MD (ft)	TVD (ft)	Dip (°)	Dip Azimuth (°)	Formation Name
Genesee	7517.22	7456.00	0.000	0.000	Genesee
Tully	7814.81	7655.00	0.000	0.000	Tully
Hamilton	7936.25	7741.00	0.000	0.000	Hamilton
Upper Marcellus	8062.01	7816.00	0.000	0.000	Upper Marcellus
Cherry Valley	8134.95	7852.00	0.000	0.000	Cherry Valley
Lower Marcellus	8143.87	7856.00	0.000	0.000	Lower Marcellus
Onondaga	N/A	7996.00	0.000	0.000	Onondaga

LP : 7981.64ft TVD, 900.88ft N, 806.06ft E
Laurita 5H LP Rev-2
End of 3D Arc : 7627.05ft TVD, 300.28ft N, 1060.69ft E
SRFC Casing (Est.) : 805.00ft TVD, 0.00ft N, 0.00ft E
INT Casing (Est.) : 2150.00ft TVD, 0.00ft N, 0.00ft E
KOP : 2250.00ft TVD, 0.00ft N, 0.00ft E
End of Build : 2652.06ft TVD, 6.82ft N, 42.25ft E
KOP : 7222.40ft TVD, 163.55ft N, 1013.89ft E



RECEIVED
Office of Oil and Gas

SEP 11 2026

WV Department of
Environmental Protection


10/02/2026

10/02/2026

Laurita 5H Area of Review

API Number	Well Name	Well Number	Operator	Latitude (NAD 83)	Longitude (NAD 83)	TMP	TVD	Producing Formation	Notes
061-00387	A Arnett	3693	Diversified Production, LLC	39.595356	-80.104681	7-17-57	2401	Gantz	
061-02028	NA	NA	NNE RESOURCES LLC	39.595212	-80.109253	7-17-36	NA	NA	Plugged

WELL NAME: LAURITA 5H
RIVESVILLE, WV



TOTAL DISTANCE BORED
FROM LP TO BH = 18,947'

BLACKSVILLE
GRANT TOWN

OSAGE
RIVESVILLE

10/02/2026



	PROPERTY OWNER INDEX
7-17-36	NORTHEAST NATURAL ENERGY LLC
7-17-38	PATRICIA KELLY
7-17-37	ALFRED JUNIOR GLOVER
7-17-39	LEONARD DALE & RHONDA FOX
7-17-56	LEONARD DALE & RHONDA FOX
7-17-57	GORDON WAYNE & SHEILA M LAWSON
7-17-36.1	MERIT DEVELOPMENT INC
7-17-35	JIMMY L & RENITA D SHISLER
7-10-21.1	WILLIAM CARTER & REBECCA ROSE HARRIS
7-10-21	WILLIAM CARTER & REBECCA ROSE HARRIS
7-10-20	TIMOTHY P ZAHARKO
7-10-5	GREGORY C SMITH
7-10-6	JACK L RADCLIFF (DD-ROY P RADCLIFF)
7-10-8	TAMMY LYNN & KRIS B CAMPBELL
4-23-25	BEVERLY A MICHAEL
4-23-26	HUGH J & SANDRA J BLAKE
4-23-21	CNX LAND LLC
4-23-20	CNX LAND LLC
4-23-16	MARK A UPHOLD & AMBER N KUCISH
4-23-16.2	MARK A UPHOLD & AMBER N KUCISH
4-23-7.1	RICHARD A & KATHY L ORINICK
4-23-8	RICHARD A & KATHY L ORINICK
4-23-9	FREDA LAURA & PAUL DAVID HIMES
4-23-2	FREDA LAURA & PAUL DAVID HIMES
4-23-2.1	WADE FAMILY IRREVOCABLE TRUST
4-23-1.4	SCOTT A & KITTY J HENDRICKS
4-23-1	DONALD A MIRANOV
4-23-1.1	JAMES HALL
4-23-1.2	HAGANS CEMETERY
4-23-1.3	JAMES HALL
4-24-54	BENJAMIN CAMPBELL
4-21-55	BENJAMIN RENEX SMITH JR & KATHLEEN RENEE SMITH
4-21-53.4	NANCY K & FRANKLIN J RASPA
4-21-53	MARY A EDDY
4-21-53.8	AARON & JESSICA BARNETT
4-21-37	SCOTT A & KITTY J HENDRICKS
4-21-38.2	PETER A & RENEE M BIRURAKIS
4-21-39.2	BENJAMIN RICHARD KENYON
4-21-39.3	BENJAMIN RICHARD KENYON
4-21-39	KEVIN & CARRIE L SMITH

	LEASE INDEX		
A	WV-061-00219-001	N	WV-061-006543-001
B	WV-061-107054-003	O	WV-061-800171-002
C	WV-061-106431-001	P	WV-061-007149-010
D	WV-061-086111-001	Q	WV-061-007268-001
E	WV-061-086278-001	R	WV-061-007032-003
F	WV-061-086278-001	S	WV-061-006151-001
G	WV-061-106398-012	T	WV-061-006939-001
H	WV-061-106524-004	U	WV-061-00219-001
I	WV-061-00219-001	V	WV-061-00219-001
J	WV-061-086236-001	W	WV-061-006721-001
K	WV-061-107225-001	X	WV-061-004008-001
L	WV-061-006611-001	Y	WV-061-005294-019
M	WV-061-000220-001-PA		

10/02/2026

FILE #: <u>NNE25</u>	DATE: <u>JUNE 24, 2026</u>
DRAWING #: <u>4145</u>	OPERATOR'S WELL #: <u>LAURITA 5H</u>
SCALE: <u>N/A</u>	API WELL #: <u>47</u> <u>061</u> <u>02032</u> STATE COUNTY PERMIT

**INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE
Chapter 22, Article 6A, Section 5(a)(5)
IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)**

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that –

(1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;

(2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Lease Name or Number	Grantor, Lessor, etc.	Grantee, Lessee, etc.	Royalty	Book/Page
See attached				

RECEIVED
Office of Oil and Gas

SEP 11 2026

WV Department of
Environmental Protection

**Acknowledgement of Possible Permitting/Approval
In Addition to the Office of Oil and Gas**

The permit applicant for the proposed well work addressed in this application hereby acknowledges the possibility of the need for permits and/or approvals from local, state, or federal entities in addition to the DEP, Office of Oil and Gas, including but not limited to the following:

- WV Division of Water and Waste Management
- WV Division of Natural Resources WV Division of Highways
- U.S. Army Corps of Engineers
- U.S. Fish and Wildlife Service
- County Floodplain Coordinator

The applicant further acknowledges that any Office of Oil and Gas permit in no way overrides, replaces, or nullifies the need for other permits/approvals that may be necessary and further affirms that all needed permits/approvals should be acquired from the appropriate authority before the affected activity is initiated.

Well Operator: Northeast Natural Energy LLC
By: Hollie Medley
Its: Regulatory Manager

WW-6A1		Operators Well No. Laurita 5H				
Tract	Lease Number	Grantor, Lessor, etc.	Grantee, Lessee, etc.	Royalty	Book	Page
A	WV-061-00219-001	ET Blue Grass, LLC	Northeast Natural Energy LLC	Affidavit of Asset Contribution	186	257
B	WV-061-107054-003	The James L. Laurita Family Limited Partnership	Marion Natural Energy LLC	12.5% or Greater	1894	366
B	WV-061-107054-001	The Karen E. Richter Trust dated July 2, 2009	Marion Natural Energy LLC	12.5% or Greater	1906	657
B	WV-061-107054-002	Shuman Inc.	Marion Natural Energy LLC	12.5% or Greater	1890	25
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
C	WV-061-106431-001	Fortune Development LLC	Marion Natural Energy LLC	12.5% or Greater	1820	214
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
D	WV-061-086111-001	Lynn Ann Nicholas	NNE Land LLC	12.5% or Greater	1803	824
		NNE Land LLC	Marion Natural Energy LLC	Assignment	162	769
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
E	WV-061-086278-001	William Carter Harris and Rebecca Rose Harris, JTROS	Marion Natural Energy LLC	12.5% or Greater	1808	330
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
F	WV-061-086278-001	William Carter Harris and Rebecca Rose Harris, JTROS	Marion Natural Energy LLC	12.5% or Greater	1808	330
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
G	WV-061-106398-012	Kathryn Combs	Marion Natural Energy LLC	12.5% or Greater	1825	309
G	WV-061-006398-014	Charles M. Combs	Northeast Natural Energy LLC	12.5% or Greater	185	441
G	WV-061-106398-006	Susan G. Arnold	Marion Natural Energy LLC	12.5% or Greater	1820	66
G	WV-061-006398-002	Thomas Scott Glasscock	Marion Natural Energy LLC	12.5% or Greater	1814	527
G	WV-061-106398-001	Jack A. Glasscock	Marion Natural Energy LLC	12.5% or Greater	1820	63
G	WV-061-106398-007	Sandria Glasscock	Marion Natural Energy LLC	12.5% or Greater	1821	235
G	WV-061-106398-005	Jeffrey Arnett Glasscock	Marion Natural Energy LLC	12.5% or Greater	1820	63
G	WV-061-106398-008	Traci Leigh Glasscock, a/k/a Traci Leigh Lester	Marion Natural Energy LLC	12.5% or Greater	1821	238
G	WV-061-106398-004	James E. Glasscock	Marion Natural Energy LLC	12.5% or Greater	1820	6
G	WV-061-106398-003	Andrew S. Glasscock	Marion Natural Energy LLC	12.5% or Greater	1820	57
G	WV-061-106398-013	Jennifer Glasscock	Northeast Natural Energy LLC	12.5% or Greater	184	279
G	WV-061-106398-009	Heather Glasscock White	Marion Natural Energy LLC	12.5% or Greater	1821	241
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
H	WV-061-106524-004	Joseph Gibson	Marion Natural Energy LLC	12.5% or Greater	1831	830
H	WV-061-106524-003	Timothy Gibson	Marion Natural Energy LLC	12.5% or Greater	1831	828
H	WV-061-106524-001	William Gibson	Marion Natural Energy LLC	12.5% or Greater	1831	824
H	WV-061-106114-002	Betty Jane Hill	Marion Natural Energy LLC	12.5% or Greater	1843	85
H	WV-061-106524-002	Charles Lewis Dunlap	Marion Natural Energy LLC	12.5% or Greater	1831	826
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
I	WV-061-00219-001	John J. Musgrave et al	E.G. Price and T.S. Neptune	12.5% or Greater	84	257
		E.G. Price and T.S. Neptune	Fayette County Gas Company	Deed Book	84	270
		Fayette County Gas Company	Hope Natural Gas Company	Deed Book	117	241
		Hope Natural Gas Company	Consolidated Gas Supply Corporation	Deed Book	680	35
		Consolidated Gas Supply Corporation	Consolidated Gas Transmission Corporation	Assignment Book	16	198
		Consolidated Gas Transmission Corporation	CNG Transmission Corporation	WV SOS Name Change		
		CNG Transmission Corporation	Eastern States Oil & Gas, Inc.	Assignment Book	43	313
		Eastern States Oil & Gas, Inc.	Equitable Production - Eastern States, Inc.	WV SOS Name Change		
		Equitable Production - Eastern States, Inc.	Equitable Production Company	Merger via WVSOS		
		Equitable Production Company	EQT Production Company	WV SOS Name Change		
		EQT Production Company	Northeast Natural Energy LLC	Affidavit of Asset Contribution	186	257
J	WV-061-086236-001	Jack L. Radcliff	NNE Land LLC	12.5% or Greater	1804	143
		NNE Land LLC	Marion Natural Energy LLC	Assignment	162	769
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
K	WV-061-107225-001	Emory Peak Minerals II LLC	Marion Natural Energy LLC	12.5% or Greater	1887	17
**Note: All agreements to Marion Natural Energy LLC are subject to a Confirmatory Deed & Assignment with Northeast Natural Energy LLC filed at 1407/236-241 in Marion County.						
L	WV-061-006611-001	Generation-Skipping Trust under LWT of Pauline M. Taylor, FBO Linda Suzann Miller	Northeast Natural Energy, LLC	12.5% or Greater	1861	608
L	WV-061-006611-002	Generation-Skipping Trust under LWT of Pauline M. Taylor, FBO Larry Charles Taylor	Northeast Natural Energy, LLC	12.5% or Greater	1861	448
L	WV-061-006400-001	Waco Oil and Gas Co., Inc	Northeast Natural Energy, LLC	12.5% or Greater	1820	129
L	WV-061-006400-002	Mike Ross Inc.	Northeast Natural Energy, LLC	12.5% or Greater	1821	367
L	WV-061-006611-003	Beverly A. Michael	Northeast Natural Energy, LLC	12.5% or Greater	183	791
M	WV-061-000220-001-PA	XTO Energy Inc. - Participating	Northeast Natural Energy, LLC	Affidavit of Asset Contribution	188	81
N	WV-061-006543-001	Edwin A. Deagle III	Northeast Natural Energy, LLC	12.5% or Greater	1829	355
N	WV-061-006543-002	The Deagle Family Revocable Living Trust dated May 7, 2019	Northeast Natural Energy, LLC	12.5% or Greater	1883	154
O	WV-061-800171-002	NNE Properties II	Northeast Natural Energy, LLC	12.5% or Greater	1805	638
P	WV-061-007149-010	Victoria R. Hawkins	Northeast Natural Energy, LLC	12.5% or Greater	1893	713
P	WV-061-007149-044	Sheila Ezerski	Northeast Natural Energy, LLC	12.5% or Greater	1896	130
P	WV-061-007149-025	Jesse Ray Hawkins	Northeast Natural Energy, LLC	12.5% or Greater	1893	699
P	WV-061-007149-024	John Lewis Hawkins	Northeast Natural Energy, LLC	12.5% or Greater	1893	697
P	WV-049-007149-030	Carrie Elizabeth Parrack	Northeast Natural Energy, LLC	12.5% or Greater	1896	100
P	WV-061-007149-008	William Gene Stewart	Northeast Natural Energy, LLC	12.5% or Greater	1892	559
P	WV-061-007149-009	Barbara Louise Stillwagon	Northeast Natural Energy, LLC	12.5% or Greater	1892	561

P	WV-061-007149-035	Rickey L. Nicholson	Northeast Natural Energy, LLC	12.5% or Greater	1896	134
P	WV-061-007149-056	Daniel Lee Stewart	Northeast Natural Energy, LLC	12.5% or Greater	1916	204
P	WV-061-007149-007	Diane Lynn Buck	Northeast Natural Energy, LLC	12.5% or Greater	1892	557
P	WV-061-007149-005	Robert Franklin Stewart	Northeast Natural Energy, LLC	12.5% or Greater	1892	553
P	WV-061-007149-002	Rebecca K. Davis	Northeast Natural Energy, LLC	12.5% or Greater	1883	270
P	WV-061-007149-001	Lonnie Ray Hawkins	Northeast Natural Energy, LLC	12.5% or Greater	1883	268
P	WV-061-007149-003	Anita Jaggie	Northeast Natural Energy, LLC	12.5% or Greater	1884	202
P	WV-061-007149-004	Charlotte Higinbotham	Northeast Natural Energy, LLC	12.5% or Greater	1885	849
P	WV-061-007149-043	Beverly J. Klingaman	Northeast Natural Energy, LLC	12.5% or Greater	1896	128
P	WV-061-007149-026	Jo Ellen Sims	Northeast Natural Energy, LLC	12.5% or Greater	1893	775
P	WV-061-007149-033	Russel Scott Hawkins	Northeast Natural Energy, LLC	12.5% or Greater	1896	106
P	WV-061-007149-048	Carol A. Pyles	Northeast Natural Energy, LLC	12.5% or Greater	1912	468
P	WV-061-007149-049	Patrick Hawkins	Northeast Natural Energy, LLC	12.5% or Greater	1912	470
P	WV-061-007149-022	Kimberly A. Vincent	Northeast Natural Energy, LLC	12.5% or Greater	1893	691
P	WV-061-007149-020	Samantha Jo Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1893	693
P	WV-061-007149-021	Karrie Lynn Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1893	695
P	WV-061-007149-019	Sheila M. Larew	Northeast Natural Energy, LLC	12.5% or Greater	1893	689
P	WV-061-007149-012	Glenna Joyce Marshall	Northeast Natural Energy, LLC	12.5% or Greater	1893	681
P	WV-061-007149-018	Melina Gail Trenum	Northeast Natural Energy, LLC	12.5% or Greater	1893	687
P	WV-061-007149-059	Kelly Cobb Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1919	725
P	WV-061-007149-027	Kimberly Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1893	777
P	WV-061-007149-034	Debbie Jean Hall	Northeast Natural Energy, LLC	12.5% or Greater	1896	132
P	WV-061-007149-032	Tammie Hall	Northeast Natural Energy, LLC	12.5% or Greater	1896	104
P	WV-061-007149-006	George Forest Sybolt Jr.	Northeast Natural Energy, LLC	12.5% or Greater	1892	555
P	WV-061-007149-055	Dave Hall	Northeast Natural Energy, LLC	12.5% or Greater	1914	465
P	WV-061-007149-016	Tracie B. Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1893	683
P	WV-061-007149-023	Edwin D. Smith	Northeast Natural Energy, LLC	12.5% or Greater	1893	773
P	WV-061-007149-017	William Darrell Smith	Northeast Natural Energy, LLC	12.5% or Greater	1893	685
P	WV-061-007149-031	Shawn Dale Felton	Northeast Natural Energy, LLC	12.5% or Greater	1896	102
P	WV-061-007149-054	David A. Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1914	463
P	WV-061-007149-045	Linda G. Woods	Northeast Natural Energy, LLC	12.5% or Greater	1900	1
P	WV-061-007149-047	William E. Whitehead	Northeast Natural Energy, LLC	12.5% or Greater	1912	466
P	WV-061-007149-046	Richard Lee Everly	Northeast Natural Energy, LLC	12.5% or Greater	1899	99
P	WV-061-007149-028	David Jeffery Everly Sr.	Northeast Natural Energy, LLC	12.5% or Greater	1896	96
P	WV-061-007149-070	Roger Allen Hawkins	Northeast Natural Energy, LLC	12.5% or Greater	1929	605
P	WV-061-008144-001	Norma Jean Godzak	Northeast Natural Energy, LLC	12.5% or Greater	1928	503
P	WV-061-007149-052	A. Darlene Stenberg	Northeast Natural Energy, LLC	12.5% or Greater	1912	580
P	WV-061-007149-081	Kristine C. Dewitt	Northeast Natural Energy, LLC	12.5% or Greater	190	184
P	WV-061-007149-080	Jason Michael Dewitt	Northeast Natural Energy, LLC	12.5% or Greater	190	168
P	WV-061-007149-079	Sascha Jade Dewitt	Northeast Natural Energy, LLC	12.5% or Greater	190	188
P	WV-061-007149-084	Richard Harold Tasker	Northeast Natural Energy, LLC	12.5% or Greater	190	107
P	WV-061-007149-091	Brenda W. Murphy	Northeast Natural Energy, LLC	12.5% or Greater	190	135
P	WV-061-007149-060	Jeffrey T. Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1926	780
P	WV-061-007149-011	Donna J. Quinn	Northeast Natural Energy, LLC	12.5% or Greater	1893	715
P	WV-061-007149-086	Mary Lou Hallas	Northeast Natural Energy, LLC	12.5% or Greater	190	79
P	WV-061-007149-067	Zeda A. Johnson	Northeast Natural Energy, LLC	12.5% or Greater	1930	267
P	WV-061-007149-064	Angie K. Schultz	Northeast Natural Energy, LLC	12.5% or Greater	1929	688
P	WV-061-007149-068	Charles P. Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1930	426
P	WV-061-007149-063	Ellen M. Burns	Northeast Natural Energy, LLC	12.5% or Greater	1929	684
P	WV-061-007149-062	Caroline L. Keller Collins	Northeast Natural Energy, LLC	12.5% or Greater	1929	682
P	WV-061-007149-065	Rhonda L. Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1929	690
P	WV-061-007149-053	Rochelle Darlene Vanhouten	Northeast Natural Energy, LLC	12.5% or Greater	1916	202
P	WV-061-007149-069	Donald Edward Sybolt	Northeast Natural Energy, LLC	12.5% or Greater	1929	686
P	WV-061-007149-089	Christie L. Young	Northeast Natural Energy, LLC	12.5% or Greater	190	131
Q	WV-061-007268-001	Richard A. Orinick and Kathy L. Orinick, JTROS	Northeast Natural Energy, LLC	12.5% or Greater	1888	569
R	WV-061-007032-003	Betty Wiley	Northeast Natural Energy, LLC	12.5% or Greater	1878	642
R	WV-061-007032-004	Robert C. Lemley	Northeast Natural Energy, LLC	12.5% or Greater	1884	200
R	WV-061-007032-002	Rosemary C. Gyko	Northeast Natural Energy, LLC	12.5% or Greater	1878	644
R	WV-061-007032-001	Cam R. Lemley	Northeast Natural Energy, LLC	12.5% or Greater	1878	640
R	WV-061-007032-006	Keith Lemley	Northeast Natural Energy, LLC	12.5% or Greater	183	787
R	WV-061-007032-005	Michael Lemley	Northeast Natural Energy, LLC	12.5% or Greater	1888	650
S	WV-061-006151-001	Malinda Ann Stewart	Northeast Natural Energy, LLC	12.5% or Greater	1806	633
S	WV-061-006151-002	Country Roads Minerals LLC	Northeast Natural Energy, LLC	12.5% or Greater	1795	73
S	WV-061-006151-002	LaCore Agriculture LLC	Northeast Natural Energy, LLC	12.5% or Greater	1795	73
S	WV-061-006867-001	AMP V LP	Northeast Natural Energy, LLC	12.5% or Greater	1876	188
T	WV-061-006939-001	Karen F. Thompson	Northeast Natural Energy, LLC	12.5% or Greater	1874	490
	WV-061-006939-002	Mac Resources LLC	Northeast Natural Energy, LLC	12.5% or Greater	1884	187
U	WV-061-00219-001	Country Roads Minerals LLC	EQT Production Company	12.5% or Greater	1882	405
		EQT Production Company	Northeast Natural Energy, LLC	Affidavit of Asset Contribution	186	257
U	WV-061-00219-001	LaCore Agriculture LLC	EQT Production Company	12.5% or Greater	1882	408
		EQT Production Company	Northeast Natural Energy, LLC	Affidavit of Asset Contribution	186	257
V	WV-061-00219-001	Country Roads Minerals LLC	EQT Production Company	12.5% or Greater	1882	417
		EQT Production Company	Northeast Natural Energy, LLC	Affidavit of Asset Contribution	186	257
V	WV-061-00219-001	LaCore Agriculture LLC	EQT Production Company	12.5% or Greater	1882	417
		EQT Production Company	Northeast Natural Energy, LLC	Affidavit of Asset Contribution	186	257
W	WV-061-006721-001	Aaron Barnett and Jessica Barnett, JTROS	Northeast Natural Energy, LLC	12.5% or Greater	1859	163
X	WV-061-004008-001	David J. Eddy and Elizabeth A. Eddy	David F. Morris	12.5% or Greater	95	355
		David F. Morris	Hagens Oil and Gas Company	Deed Book	95	357
		Hagens Oil and Gas Company	JH McDermott, Noah Moore and Jesse Moore	Deed Book	147	463
		JH McDermott, Noah Moore and Jesse Moore	Marshall Oil and Gas Company	Deed Book	159	364
		Marshall Oil and Gas Company	Marshall Oil Company	Deed Book	172	142

		Marshall Oil Company	Dunn-Mar Oil and Gas Company	Deed Book	204	211
		Dunn-Mar Oil and Gas Company	Alco Oil Company	Deed Book	837	658
		Alco Oil Company	Greenridge Oil Company	Assignment Book	12	651
		Greenridge Oil Company	Mark Eddy and Harry Eddy	Assignment Book	19	602
		Mark Eddy and Harry Eddy d/b/a Eddy Brothers	Northeast Natural Energy, LLC	Assignment Book	123	363
Y	WV-061-005294-019	Jackie S. Clifton	Northeast Natural Energy, LLC	12.5% or Greater	1884	183
Y	WV-061-005294-020	Debra S. Cardella	Northeast Natural Energy, LLC	12.5% or Greater	1884	185
Y	WV-061-005294-001	Dawn Barger	Northeast Natural Energy, LLC	12.5% or Greater	1630	229
Y	WV-061-005294-007	Alfred Van Dunn	Northeast Natural Energy, LLC	12.5% or Greater	1633	485
Y	WV-061-005294-021	Arthur D. Dunn	Northeast Natural Energy, LLC	12.5% or Greater	1886	132
Y	WV-061-005294-017	Floyd E. Dunn, deceased	Northeast Natural Energy, LLC	12.5% or Greater	178	101
Y	WV-061-005294-006	Jack C. Dunn	Northeast Natural Energy, LLC	12.5% or Greater	1633	479
Y	WV-061-005294-005	Larry D. Dunn	Northeast Natural Energy, LLC	12.5% or Greater	1633	477
Y	WV-061-005294-014	Max G. Dunn	Northeast Natural Energy, LLC	12.5% or Greater	1864	543
Y	WV-061-005294-018	Wayne H. Dunn	Northeast Natural Energy, LLC	12.5% or Greater	1883	276
Y	WV-061-005294-017	Daniel Leon Gruver, deceased	Northeast Natural Energy, LLC	12.5% or Greater	178	105
Y	WV-061-005294-002	Master Mineral Holdings III, LP	Northeast Natural Energy, LLC	12.5% or Greater	1631	561
Y	WV-061-005294-003	Master Mineral Holdings III, LP	Northeast Natural Energy, LLC	12.5% or Greater	1631	563
Y	WV-061-005294-015	Donna Lee Sanderson	Northeast Natural Energy, LLC	12.5% or Greater	1866	224
Y	WV-061-005294-013	Leanna S. White	Northeast Natural Energy, LLC	12.5% or Greater	1861	622

NNE PROPERTIES LLC
707 VIRGINIA ST E STE 1200
CHARLESTON WV 25301-2719

Marion County
Julie Kincaid, Clerk
Instrument 202500022790
12/18/2025 @ 01:08:17 PM
DEED
Book 1407 @ Page 236-241
Pages Recorded 6
Recording Cost \$ 33.00

CONFIRMATORY DEED & ASSIGNMENT

THIS CONFIRMATORY DEED & ASSIGNMENT, is made the 20th day of November, 2025, by and between Marion Natural Energy LLC, a Delaware limited liability company, party of the first part, and Northeast Natural Energy LLC, a Delaware limited liability company, party of the second part.

WHEREAS, the party of the first part has merged with and into the party of the second part, as evidenced by the Certificate of Merger attached hereto as Exhibit A; and

WHEREAS, the party of the first part owned real property interests in Marion County, West Virginia, and pursuant to W. Va. Code § 31B-9-904 intends to evidence title to such real property interests in the party of the second part as the surviving corporation by executing and acknowledging for record this confirmatory deed.

NOW, THEREFORE, WITNESSETH, that for and in consideration of the merger of the party of the first part with and into the party of the second part, with the party of the second part being the surviving corporation, and other good and valuable consideration, the receipt of which is hereby acknowledged, the said party of the first part does hereby grant, assign, convey, release and remise unto the party of the second part all its right, title and interest in and to all real property owned by the party of the first part as of the date of the merger.

This deed and assignment is made subject to all valid reservations, exceptions, easements, rights-of-way, covenants, conditions, licenses and other servitudes contained or referred to in prior deeds or other instruments of record affecting or pertaining to the property hereby conveyed.


27420418.1

10/02/2026

The undersigned party of the first part hereby declares that this conveyance is not subject to the excise tax on the privilege of transferring real property because it is a deed made pursuant to a merger.

IN WITNESS WHEREOF, the party of the first party has caused its name to be signed hereto by its duly authorized.


MARION NATURAL ENERGY LLC,
a Delaware limited liability company

By: 
Its: Christopher D. Mullen
Vice President


STATE OF WEST VIRGINIA,
COUNTY OF KANAWHA, TO-WIT:

On this 20th day of November, 2025, before me, the undersigned Notary Public, personally appeared Christopher D. Mullen, the Vice President of Marion Natural Energy LLC, a Delaware limited liability company, and acknowledged this instrument to be the free and voluntary act and deed of the said limited liability company and on oath stated that he was authorized to execute this instrument and in fact executed the instrument for and on behalf of the said limited liability company.

My commission expires: 9-29-27


Notary Public

(NOTARIAL SEAL)



Prepared by and after monthly please return to:
Northeast Natural Energy LLC
707 Virginia St. E. Suite 1200
Charleston, WV 25301

27420418.1

10/02/2026

Exhibit A

Certificate of Merger

[see attached]

27420418.1

EXHIBIT A

10/02/2026

Delaware

The First State

Page 1

I, CHARUNI PATIBANDA-SANCHEZ, SECRETARY OF STATE OF THE
STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND
CORRECT COPY OF THE CERTIFICATE OF MERGER, WHICH MERGES:

"MARION NATURAL ENERGY LLC", A DELAWARE LIMITED LIABILITY
COMPANY,

WITH AND INTO "NORTHEAST NATURAL ENERGY LLC" UNDER THE NAME
OF "NORTHEAST NATURAL ENERGY LLC", A LIMITED LIABILITY COMPANY
ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE,
AS RECEIVED AND FILED IN THIS OFFICE ON THE TWENTY-NINTH DAY OF
OCTOBER, A.D. 2025, AT 1:22 O'CLOCK P.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF
THE AFORESAID CERTIFICATE OF MERGER IS THE THIRTY-FIRST DAY OF
OCTOBER, A.D. 2025.



4713590 8100M
SR# 20254407364

You may verify this certificate online at corp.delaware.gov/authver.shtml

C. B. Sanchez

Charuni Patibanda-Sanchez, Secretary of State

Authentication: 205186907
Date: 10-30-25

10/02/2026

**STATE OF DELAWARE
CERTIFICATE OF MERGER OF
DOMESTIC LIMITED LIABILITY COMPANIES**

Pursuant to Title 6, Section 18-209 of the Delaware Limited Liability Act, the undersigned limited liability company executed the following Certificate of Merger:

FIRST: The name of the surviving limited liability company is
Northeast Natural Energy LLC,
and the name of the limited liability company being merged into this surviving limited liability company is Marion Natural Energy LLC.

SECOND: The Agreement of Merger has been approved, adopted, certified, executed and acknowledged by each of the constituent limited liability companies.


THIRD: The name of the surviving limited liability company is
Northeast Natural Energy LLC.

FOURTH: The merger is to become effective on October 31, 2025.

FIFTH: The Agreement of Merger is on file at 707 Virginia Street East
Suite 1200, Charleston, West Virginia 25301,
the place of business of the surviving limited liability company.

SIXTH: A copy of the Agreement of Merger will be furnished by the surviving limited liability company on request, without cost, to any member of the constituent limited liability companies.

IN WITNESS WHEREOF, said surviving limited liability company has caused this certificate to be signed by an authorized person, the 27th day of
October, A.D., 2025.

By: 
Authorized Person

Name: Samuel P. Sommerville
Print or Type

Title: Vice President

State of Delaware
Secretary of State
Division of Corporations
Delivered 01:22 PM 10/29/2025
FILED 01:22 PM 10/29/2025
SR 20254407364 - File Number 4713590

10/02/2026



LLC/PLC Termination Cancellation Filing

For filing with the West Virginia Secretary of State
a Business for West Virginia Partner
tel: (304) 558-8000

Organization Name	MARION NATURAL ENERGY LLC
Organization Type	Limited Liability Company
Charter Type	Foreign
Class	For Profit
Home State	DE
WV Effective Date	12/06/2023
Contact Name	Samuel P. Sommerville
Contact Address	707 Virginia Street East, Suite 1200 , Charleston, WV 25301
Contact Phone	(304)414-7072
Contact Email Address	SSOMMERVILLE@NNE-LLC.COM
Filing Date	11/06/2025
SOS Termination Date	11/06/2025

I certify the information provided is true. I further certify that I am a member or manager or individual holding a power-of-attorney and am duly authorized to file this report on behalf of this limited liability company, as required by West Virginia Code §31B-2-211. I agree that the electronic entry of my name below represents my signature and authorization for this filing.

Samuel P. Sommerville
Authorized By

MEMBER
Capacity

Marion County
Julie Kincaid, Clerk
Instrument 202500022790
12/18/2025 @ 01:08:17 PM
DEED
Book 1407 @ Page 236-241
Pages Recorded 6
Recording Cost \$ 33.00

RETAIN A COPY FOR YOUR RECORDS

10/02/2026



**Monongalia County
Site Safety Plan**

**Laurita Well Pad
2026**

Robert J. Hitt
6-29-26

10/02/2026

Laurita Well Pad

Grant District
Monongalia County

ACCESS ROAD ENTRANCE

622 Hagans Road
Rivesville, WV 26588


39.59208 Lat, -80.11374 Long (WV-83)

DRIVING DIRECTIONS

- Beginning at Exit 155 on Interstate 79.
- Travel east on State Route 19/24 (Chaplin Road) for 0.57 miles to the intersection of said State Route 19/24 and US Rt. 19.
- Turn left onto US Rt. 19 and travel north for 1.67 miles to the intersection of said US Rt. 19 and WV Rt. 7 (Mason Dixon Highway).
- Turn left onto WV Rt. 7 and travel west for 4.04 miles to the intersection of said WV Rt. 7 and State Route 41 (Little Indian Creek Road)
- Turn left onto said State Route 41 and travel south for 5 miles to the intersection of said State Route 41 and US Rt. 19.
- Turn right onto said US Rt. 19 and travel south for 2.95 miles to the intersection of said US Rt. 19 and State Route 37 (Hagans Road).
- Turn right onto said State Route 37 and travel north for 1.46 miles to the access road on the right located @ N 39.5921932, W 80.1139216.

*See Attached Maps

10/02/2026



Introduction

Northeast Natural Energy LLC ("NNE") is an oil and gas exploration and production company with company headquarters located at the following address:

707 Virginia Street East, Suite 1200
Charleston, WV 25301

And a Field Operations Office located at the following address:

48 Donley Street, Suite 601
Morgantown, WV 26501

NNE is committed to protecting the people, property, and resources of the company and of the communities in which it works by establishing a safe and healthy work environment that is free from recognized hazards and complies with all local, state and federal regulations.

This Plan will be reviewed annually and may be subject to revision and/or update whenever any of the following occur:

- Following an incident.
- A new chemical or process is utilized onsite.
- Existing processes are modified significantly.
- Regulations are revised significantly.
- The current Plan fails in an emergency situation.
- Changes in emergency response equipment.
- Changes in internal and external emergency resources.

TABLE OF CONTENTS

- 1 – Contacts, Schedules and Meetings
- 2 – Maps and Diagrams
- 3 – Well Work
- 4 – SDS & Chemical Inventory
- 5 – BOP and Well Control
- 6 – Hydrogen Sulfide (H₂S)
- 7 – Flaring
- 8 – Collision Avoidance Safeguards, Practices and Standards

1

Contacts, Schedules and Meetings

A. NORTHEAST NATURAL ENERGY LLC CONTACTS:

24 hour emergency number 1-866-207-1846

EH&S

- Andy Travis- EH&S Manager 304.951.0909

Construction/Reclamation

- Mike Shreve – Construction Coordinator 304.918.3050
- Dave McDougal – Civil Engineering Manager 304.941.5033

Drilling/Completion

- Matt Bakewell– Drilling Engineer 304-907-9493
- Criss VanGilder - Director – Drilling & Completions 405.757.8725
- Matt Biddle- Completions Engineer 412.889.1442

Production

- John Landis – Production & Facilities Manager 304.216.6854
- Eric Zwolinski- Production Engineer 304.542.9431

B. EMERGENCY CONTACTS:

In case of an emergency call **911**

1. OPERATOR CONTACTS

- 24-hour emergency number 1-866-207-1846

2. CONTRACTORS

Drilling Operations

- TBD – Drilling Contractor 865.805.8683
- Nextier – Cement/Pumping 281.784.4700
- Wild Well Control – Well Control

Completions Operations

- Pro Frac – Pressure Pumping 254.776.3722
- Evolution – Pressure Pumping 346.977.4878
- Nine Energy – Wireline 724.222.8900

10/02/2026

3. **WV DEP/ OFFICE OF OIL AND GAS**

Pollution and Emergency Spills 1-800-642-3074

- H. Jason Harmon – Acting Chief 304.926.0450
- Robert Hitt – Inspector 681.344.4747

4. **WV DEP/ AIR QUALITY**

- Lucas Freeze - Inspector 304.312.1503
- James F. Jarrett – Inspector 304.549.2461

5. **LOCAL EMERGENCY RESPONSE UNITS**

MONONGALIA COUNTY OFFICE OF EMERGENCY MANAGEMENT

- 24 Hour Emergency Number 304.599.6382
- Jimmy Smith – Director 304.598.0301
- Harold Sperringer – Deputy Director
- Mike Fortney - Assistant Director

FIRE DEPARTMENTS

- River Road VFD 304.983.2000

AMBULANCE / EMS

- MON EMS 304.599.0650

LIFE FLIGHT AMBULANCE SERVICE (HELICOPTER)

- HealthNet Aeromedical Base 1.800.255.2146

STATE POLICE

- Morgantown Detachment 304.285.3200

COUNTY POLICE

- Monongalia Sheriff 304.291.7290

HOSPITAL

- Ruby Memorial (trauma 1) 304.598.4000
- Monongalia General (trauma 4) 304.598.1200

C. PRE-JOB MEETINGS

Prior to beginning work, an onsite meeting will be held to coordinate operations and review the site safety plan. This meeting shall include the NNE and/or contracted site supervisor(s) ("Company Man"), any staff or contracted safety personnel, and key contractors to the planned operation. Local emergency response personnel will also be invited to the pre-spud meeting. The WV DEP oil and gas inspector will be notified 48 hours in advance of the meeting. All participants will be documented and provided with a copy of the site safety plan to review with their respective employees.

D. WELL SITE SAFETY MEETINGS

Safety Meetings will be held on-site, at the beginning of each shift and prior to any changes in operating conditions/procedures during a shift throughout the course of all operations. Attendance at each safety meeting will be documented.

As a means of safety and maintaining a head count, a check-in and check-out list of personnel will be kept during all drilling, completion, and work over phases of operations. The onsite supervisor will be responsible for maintaining a list of all personnel on location. A sign will be posted at the entrance to the location directing all visitors to the company trailer.


E. DISTRIBUTION OF THE SITE SAFETY PLAN

Copies of this Plan will be located at NNE's corporate office building in Charleston, West Virginia, its field office in Morgantown, West Virginia, with the Designated Response Coordinators and field operation sites when applicable. This Plan may be accessed electronically by all NNE employees on the company's Operations Management System (OMS). All NNE employees are to abide by the provisions of this Plan and are required to ensure its implementation. This Plan will also be shared with external entities such as the Local County Office of Emergency Management within at least seven (7) days prior to earth disturbance and/or well work.

Efforts will be made to familiarize police, fire departments, emergency response teams and the County Emergency Management Coordinator with the layout of the well site, the properties and dangers associated with the equipment and materials that are on site, places where personnel would normally be working, and the possible evacuation routes should an emergency occur.

2

Maps and Diagrams



SCALE BAR, 1"=600'



REVISIONS	
NO.	DATE

LAURITA WELL PAD
GRANT DISTRICT,
MONONGA
COUNTY, WV


DATE:
JUNE 2025

RADIUS PLAN

THIS DOCUMENT WAS PREPARED BY:
BOORD, BENCHEK AND ASSOC., INC.
FOR: MARION NATURAL ENERGY LLC

BOORD, BENCHEK AND ASSOC., INC.
Engineering, Surveying, Construction,
and Mining Services
Southpointe, PA 15317 Phone: 724-746-1865

Structure	Type	Owner	Street Address	City/Zip	District	Tax Map	Parcel
1	Residential	Wolf Christopher	501 Hagens RD	Rivesville, WV 26588	GRANT	17	23.3
2	Inactive Farm	Kennedy Galen Dwight &	108 Kay ST	Morgantown, WV 26501	GRANT	17	23.1
3	Residential	Estle Dale Allen	748 Hagens RD	Rivesville, WV 26588	GRANT	17	24
4	Residential	Shisler Travis James &	773 Hagens RD	Rivesville, WV 26588	GRANT	17	24
5	Mobile Home	Mcardle James F & Elaine	776 Hagens RD	Rivesville, WV 26588	GRANT	17	26.2
6	Residential	McCray Arthur William &	772 Hagens Rd	Rivesville, WV 26588	GRANT	17	26
7	Residential	Estle Dale Allen &	748 Hagens RD	Rivesville, WV 26588	GRANT	17	27.1
8	Residential	Shisler Jimmy L Renita D	222 Ridge Farm RD	Rivesville, WV 26588	GRANT	17	35
9	Active Farm	Shisler Jimmy L Renita D	222 Ridge Farm RD	Rivesville, WV 26588	GRANT	17	35
10	Active Farm	Harris William Carter &	PO Box 44	Kingwood, WV 26537	GRANT	17	21
11	Active Farm	Harris William Carter &	PO Box 44	Kingwood, WV 26537	GRANT	17	21.1
12	Active Farm	Shisler Jimmy L & Renita D	222 Ridge Farm RD	Rivesville, WV 26588	GRANT	17	35.3
13	Active Farm	Zaharko Timothy P	697 Stewarts Run RD	Morgantown, WV 26501	GRANT	17	35.1
14	Active Farm	Rogers James L & ADA D	538 Stewart Run RD	Morgantown, WV 26501	GRANT	17	58.1
15	Mobile Home	Lawson Gordon W & Sheila M	37 Hidden Valley RD	Morgantown, WV 26501	GRANT	17	58
16	Active Farm	Lawson Gordon Wayne & Sheila M	37 Hidden Valley RD	Morgantown, WV 26501	GRANT	17	57
17	Active Farm	Lawson Gordon W & Sheila M	37 Hidden Valley RD	Morgantown, WV 26501	GRANT	17	54.2
18	Active Farm	Lawson Gordon W & Sheila M	362 Stewarts Run RD	Morgantown, WV 26501	GRANT	17	56
19	Residential	Fox Leonard Dale & Rhonda	362 Stewarts Run Rd	Morgantown, WV 26501	GRANT	17	54.1
20	Residential Vacant Land	Fox Leonard Dale & Rhonda	362 Stewarts Run Rd	Morgantown, WV 26501	GRANT	17	54.1
21	Active Farm	Lawson Gordon W & Sheila M	37 Hidden Valley RD	Morgantown, WV 26501	GRANT	17	54
22	Active Farm	Lawson Martina	41 Hidden Valley RD	Morgantown, WV 26501	GRANT	17	63
23	Active Farm	Shisler Jacquelyn Y	3902 Fairmont RD	Morgantown, WV 26501	GRANT	17	78.1
24	Active Farm	Lawson Gordon & Sheila	4235 Fairmont Rd	Morgantown, WV 26501	GRANT	17	53
25	Active Farm	Jackson James & Janet I	37 Hidden Valley RD	Morgantown, WV 26501	GRANT	17	39
26	Active Farm	Lawson Gordon W & Sheila N	362 Stewarts Run RD	Morgantown, WV 26501	GRANT	17	40
27	Auxiliary Improvements	Fox Leonard Dale & Rhonda	714 Venture DR	Morgantown, WV 26508	GRANT	17	38
28	Residential Vacant Land	Kelly Patricia	22 Stewart Run	Morgantown, WV 26501	GRANT	17	36.1
29	Auxiliary Improvements	Glover Alfred Junior	3748 Dents Run BLVD	Morgantown, WV 26501	GRANT	17	37
30	Residential Vacant Land	Ment Development	707 Virginia St East, Suite 1200	Charleston, WV 25301	GRANT	17	36
31	Residential Vacant Land	Marion Natural Energy LLC	707 Virginia St East, Suite 1200	Charleston, WV 25301	GRANT	17	34
32	Residential Vacant Land	Marion Natural Energy LLC	707 Virginia St East, Suite 1200	Charleston, WV 25301	GRANT	17	34
33	Residential Vacant Land	Estle Dale Allen	748 Hagens RD	Rivesville, WV 26588	GRANT	17	29
34	Residential Vacant Land	CNX RCPC LLC	1000 Consol Energy DR	Canonsburg, PA 15317	GRANT	17	30
35	Residential	Church Robert J; Ann L Cortez	N/A	Worthington, WV 26591	GRANT	17	32
36	Residential	Marion Natural Energy LLC	707 Virginia St East, Suite 1200	Charleston, WV 25301	GRANT	17	33.1
37	Residential	Jeffries Matthew & Philip	PO box 909	Belington, WV 26250	GRANT	17	33
38	N/A	Hogues Cemetery	N/A	N/A	GRANT	17	33.3
39	Residential	Sandoval Tom P	716 Lions Gate LN	Odenton, MD 21113	GRANT	17	32.1
40	Residential Vacant Land	Roupe Aaron Michael &	603 Hagens RD	Rivesville, WV 26588	GRANT	17	23.11
41	Residential Vacant Land	Jeffries Matthew & Philip	PO box 909	Belington, WV 26250	GRANT	17	23.7
42	Residential	Coe Crystal	75 Stewarts RUN	Morgantown, WV 26501	GRANT	17	41
43	Residential	Potts Broadbuss H & Marilyn	44 Glasscock HOLW	Rivesville, WV 26588	GRANT	17	23.6
44	Residential	Tucker Jack L	26 Glasscock HOLW	Rivesville, WV 26588	GRANT	17	23.2
45	Auxiliary Improvements	Potts Broadbuss & Marilyn S	44 Glasscock HOLW	Rivesville, WV 26588	GRANT	17	22



NO.	DATE	REVISIONS
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		


LAURITA WELLS, P.D.
GRANT DISTRICT,
MONONGALIA
COUNTY, WV


DATE: JUNE 2025

THIS DOCUMENT WAS PREPARED BY:
BOARD, BENCHMARK AND ASSOC., INC.
FOR: MARION NATURAL ENERGY, LLC

RADIUS CONTACTS

BOARD, BENCHMARK and ASSOC., INC.
Engineering, Surveying, Construction,
and Mining Services
Southpointe, PA 15317 Phone: 724-746-1055





LEGEND
= EVACUATION ROUTE

ACCESS ROAD AT EDGE OF PAD
(NAD83)
LAT: 39° 35' 43.27"
LONG: -80° 06' 33.95"
(UTM NAD 83, METERS, ZONE 17)
N) 131297431.77
E) 254952391.13

SITE ENTRANCE
(NAD83)
LAT: 39° 35' 31.49"
LONG: -80° 06' 49.46"
(UTM NAD 83, METERS, ZONE 17)
N) 131322458.57
E) 254929595.56

EMERGENCY GATHERING AREA
(NAD83)
LAT: 39° 35' 31.27"
LONG: -80° 06' 48.52"
(UTM NAD 83, METERS, ZONE 17)
N) 131323917.77
E) 254932164.42

CENTER OF WELL PAD
(NAD83)
LAT: 39° 35' 40.38"
LONG: -80° 06' 34.06"
FLARE STACK LOCATION

BOORD, BENCHEK and ASSOC., INC.
Engineering, Surveying, Construction,
and Mining Services
Southpointe, PA 15317 Phone: 724-746-1055

THIS DOCUMENT WAS PREPARED BY:
BOORD, BENCHEK AND ASSOC., INC.
FOR: MARION NATURAL ENERGY LLC

DATE:
JUNE 2025
LAURITA WELL PAD
GRANT DISTRICT,
MONONGALIA
COUNTY, WV

NO.	DATE	DESCRIPTION



SCALE BAR: 1" = 600'
SHEET 1 OF 31

10/02/2026

3

Well Work

A. (1.0) Description of Drilling Operations

NNE typically uses an auger rig to set the cellar and conductor. The conductor will then be cemented/grouted to surface. A drilling rig will then be used to drill the surface section on air. Surface casing will be set and cemented to surface. The intermediate section will then be drilled on air, casing will be set, and the casing will be cemented to the surface. NNE will continue drilling on air to the start of the curve or kick off point (KOP). After the KOP the production section of the well will continue to be drilled using synthetic based drilling mud, MWD surveys and geosteering practices to maintain the wellbore in the Marcellus Shale formation. Production casing will be ran to total depth and cemented into the intermediate casing string.

In the event a pilot hole is drilled, it would be drilled to the approved depth after intermediate casing is cemented. At depth wireline logs will be ran and then the hole will be plugged back to the KOP with solid cement. The production section would then be drilled to plan.

A. (1.1) Anticipated Drilling Equipment/Materials

During the drilling of a horizontal Marcellus gas well the following equipment and materials could be on the drilling location:

Equipment / Materials
Drilling Rig Substructure
Drilling Rig Derrick/Mast
Top Drive and Drawworks
Workstations (Driller Cabin, ODS House, etc.)
Shaker Skid and Hopper House
Mud Pumps
Mud Processing Tanks
Gas Buster and Choke Manifold
Hydraulic Power Unit (HPU)
VFD House (Electrical Power System)
Rig Generators
Air Compressors
Boiler System
Hydraulic Catwalk
BOP and Installation System (Wrangler)
Accumulator Skid
Onsite Living Quarters
Forklift

Skid Steer
Manlift
Excavator
Diesel Tank
Light Towers
Frac Tanks (Mud, Cement Additives, Water)

B. (1.0) Description of Completions Operations

Each well will be completed using a multi-stage / high rate slickwater fracture treatment using sand as a proppant. The first stage will be completed by activating a series of toe sleeves which are installed in the casing during the drilling phase. Pressure applied down the wellbore causes the sleeves to open and enables communication with the formation for stimulation. Subsequent stages will be isolated using a composite plug pumped down the wellbore with perforating guns attached. The composite plug is set, the next stage is perforated, and the stage is stimulated. Each individual stage will be isolated via the composite frac plugs.

The maximum pump rate during any stage will be 110 BPM with a maximum allowable surface pressure of 10,800 PSI. Two composite bridge plugs will be set at the end of the last stage to isolate the treated formation. After the fracture treatment, composite frac plugs will be drilled out using a service rig and/or snubbing unit.

B. (1.1) Anticipated Completions Equipment/Materials

During the completion of a horizontal Marcellus gas well the following equipment and materials could be on the drilling location:

Equipment / Materials
Approximately 18 – 22 Pump Trucks
2 Blender Trucks
Wireline Truck
Scale Tanker
Biocide Tanker
Acid Tankers (2)
Friction Reducer Tank
Cranes (2)
Sand Storage
Frac Tanks (500 bbl)

35 MW Turbine
Man Lift
Telehandlers (2)
Forklift
Skid Steer
Vac Truck
Light Towers
Data Van
Generator
NG Compressors (2)
Diesel Tanks (10,000 gallon)

C. (1.0) Description of Production Operations

During the production phase, the gas stream will flow through buried, welded piping to Gas Production Units. The gas will be separated from any water that is produced and sent through a meter to a sales pipeline. The water will be piped and stored in above ground tanks on the well site. Well pressures and flow rates will be monitored and recorded to ensure safe facility operation. All facilities will be installed according to industry standards and will have appropriate safety systems in place.

C. (1.1) Anticipated Production Equipment/Materials

Well Site

Equipment / Materials
Well Head
Buried Flow Line
Sand Separator
Gas Processing Unit
Water Tanks
Natural Gas Generators
Pig Launcher
Air Compressors
Nitrogen Storage Tanks
Combustors
Compressors

M & R Station

Equipment / Materials
Flowline
Pig Receiver
Three Phase Separator
Filter Units
Dehydration Tower
50 – 100 Barrel Water Tank
Meter House
Meter Skid
Nitrogen Storage Tank

4

Safety Data Sheets (“SDS”) & Chemical Inventory

A. Safety Data Sheets ("SDS")

SDS's are stored and can be accessed digitally on NNE's OMS, and hard copies are maintained on location during active operations. Any contractors that bring hazardous materials on site are required to provide SDS for such. The onsite supervisor will be responsible for ensuring that all SDS's are obtained and are easily accessible in case of an emergency.

B. Chemical Inventory

Drilling Operations	NFPA Hazard Classification			
Product	Health	Flammability	Reactivity	Special Hazard
ABS 40 NE	1	1	0	
AES VIS LS	1	1	0	
AES WA II	1	1	0	
Barite	1	0	0	
Calcium Chloride Powder	2	0	0	
Claytone EM	1	1	1	
FLR Plus	0	1	0	
Lime	3	0	0	
TruVis	1	1	0	
WD-40 MULTI-USE PRODUCT AEROSOL	1	2	0	
629 High Temperature White Grease (Bulk)	1	1	0	
Extra Duty Gear Oil	0	1	0	
SPX UNIVERSAL COOLANT	1	1	0	
NO-TOX2	1	2	0	
Dyno Might Rig Wash	2	0	0	
SPX Gear Oil EP	0	1	0	
KOPR KOTE	2	2	1	
293 Supreme Gear Lube	0	1	0	
Lightning Degreaser	3	1	0	
Chain & Wire Rope Lube (aerosol)	2	1	0	
Marvel Mystery Oil	2	2	0	
Brakleen Brake Parts Cleaner	2	4	0	
Atlas Copco CP Airolene + Tool Oil	2	1	0	
Napa RV & Marine -50 °F Burst Antifreeze	2	1	0	
PB Penetrating Catalyst	2	2	0	
EL 2302 Electrical Contact Cleaner Aerosol	3	4	3	

Spray Nine Industrial Cleaner/Degreaser 3.78L	1	1	0	
Diesel Fuel	1	2	0	

Completions Operations	NFPA Hazard Classification			
Product	Health	Flammability	Reactivity	Special Hazard
Diesel Fuel	1	2	0	
80/90 wt gear oil	2	1	0	
50/40 motor oil	2	1	0	
Antifreeze	1	2	0	
Tri-Ethylene Glycol	1	1	1	
Frac Sand	0	0	0	
Hydrochloric Acid (HCl) (5-28%)	3	0	0	
Friction Reducer	1	1	0	
Biocide	3	1	0	
Scale Inhibitor	2	1	0	
Iron Control	0	0	0	
Corrosion Inhibitor	2	1	0	

10/02/2026

Production Operations	NFPA Hazard Classification			
Product	Health	Flammability	Reactivity	Special Hazard
3M High Power Brake Cleaner	2	4	0	
Aqua Clean Degreaser	1	1	1	
Brakleen Brake Cleaner	2	0	0	
ChampionX Foamer	2	3	0	
Desco 955 Valve Lubricant	0	1	0	
Desco Red Bentone Grease	0	1	0	
Engine Oil	0	1	0	
Equa Lube #80	0	1	0	
HDAX PF Antifreeze Coolant Phosphate	2	1	0	
HDAX PF Antifreeze Coolant Premixed	1	1	0	
Hercules MegaBubble Leak Detector	1	1	0	
Lightning Degreaser	2	0	0	
MC SS-5669 Scale Dissolver	4	0	1	
Methanol	2	3	0	
MX 2-1765 Halite Inhibitor	2	3	0	
MX 2-2978 Halite Inhibitor	2	1	0	
MX 4-5353 Foaming Agent	2	1	0	
Norkool Desitherm	1	1	0	
Norkool SLH 50	1	0	0	
PB Blaster	2	4	0	
Rigid Dark Thread Cutting Oil	1	1	0	
Diesel Fuel	1	2	0	
Silicone – Food Grade	0	0	0	
Silikroil Lubricant	1	2	0	
Texas Star Stick	0	1	0	
Turbine Shield – Compressor Oil	1	1	0	
WD-40	1	2	0	

10/02/2026

5

Blow Out Preventer ("BOP") and Well Control

A. (1.0) BOP EQUIPMENT – DRILLING

During drilling operations, all wells will utilize a 13-inch, 5,000 PSI rated BOP equipment as a means of well control. The BOP will mount to a 13-inch, 5,000 PSI well head. The BOP equipment will be used after the surface casing has been cemented in place and will be used for the duration of the well construction. The BOP equipment will include a single ram (pipe ram), kill spool, double ram (one blind and one pipe ram), and a single annular all rated for 5,000 psi.

A. (2.0) BOP EQUIPMENT – SNUBBING

During snubbing operations, all wells will utilize a minimum of a 7-inch, 5,000 PSI rated BOP equipment as a means of well control. The primary BOP equipment will include, from bottom to top, a spacer spool, pipe rams, flow cross, blind rams, and another set of pipe rams. While stripping in and out of the hole for normal operations, a set of stripping BOPs will be used. The stripping BOPs will include (2) sets of stripping/pipe rams and a stripping annular. All equipment listed above will be rated for a minimum of 5,000 PSI.

B. (1.0) PROCEDURE AND SCHEDULE FOR TESTING BOP – DRILLING

The BOP equipment will be pressure tested upon initial installation and every twenty-one (21) days thereafter, should the well not be completed within that time. When swapping wells and within the (21) day threshold, only the connections that were disconnected will be pressure tested. Annular preventers are to be tested to seventy percent (70%) of the rated capacity and ram preventers should be tested to eighty percent (80%) of the rated capacity according to the procedure outlined below. The WV DEP Oil and Gas Inspector will be notified 24 hours in advance of pressure testing the BOP equipment.

The BOP will be function tested upon initial installation. During the bottom and horizontal phase, the BOP will be function tested upon initial installation (if not already complete), as well as weekly and after each trip.

The BOP will be pressure tested with a plug-type tester landed on the load shoulder of the 13-inch casing head or the 9-5/8-inch casing hanger, depending on the phase of the well. All rams, valves, chokes, and annular preventers will be tested with water in the direction of wellbore pressure.

The annular preventer will be pressure tested around the drill pipe, starting with a low-pressure test (up to 300 PSI) for five minutes, followed by a high-pressure test

(2,100 PSI for 3M, 3,500 PSI for 5M) for thirty minutes. All rams, valves, TIWs, and choke components will be pressure tested around the drill pipe, starting with a low-pressure test (up to 300 PSI) for five minutes, followed by a high-pressure test (2,400 PSI for 3M, 4,000 PSI for 5M) for thirty minutes.

Each component must pass its respective test before drilling can commence. A successful test requires bleed-off to be less than 10% after pressure buildup throughout the low/high test duration.

B. (2.0) PROCEDURE AND SCHEDULE FOR TESTING BOP - SNUBBING

The BOP equipment will be pressure tested upon initial installation of each well and every twenty-one (21) days thereafter, should the well not be completed within that time.

The BOP will be pressure tested using the existing 7" master frac valve mounted to the tubing head adapter. All rams, valves, chokes, and annular preventers will be tested with water in the direction of pressure.

C. (1.0) ASSEMBLY INSTALLATION SCHEDULE – DRILLING

A 13-inch 5,000 psi casing head will be installed on the surface casing via tie-down screws. A drilling adapter will then be installed for BOP installation for the duration of the well construction. Each subsequent casing string will land out inside the wellhead using a casing hanger and will be sealed with a seal assembly and lock ring.

The BOP equipment will include a single ram (pipe ram), kill spool, double ram (one blind and one pipe ram), and a single annular all rated for 5,000 psi.

C. (2.0) ASSEMBLY INSTALLATION SCHEDULE - SNUBBING

The BOP equipment will be installed before any well work begins. The BOP equipment will be installed directly to the 7" master frac valve, which was previously installed directly to the tubing head adapter.

D. PERSONNEL WITH WELL CONTROL TRAINING

During drilling and completions operations, any onsite supervisor shall have and maintain IADC well control certification.

E. SYSTEM OF MAINTAINING DETAILED RECORDS

A detailed Driller's Log shall be maintained, including but not limited to, lost circulation, the presence of hydrogen sulfide gas, fluid entry, kicks, and abnormal pressures.

F. NOTIFICATION OF THE OFFICE OF OIL AND GAS

The WV DEP Office of Oil and Gas will be immediately notified of the presence of hydrogen sulfide gas above 10 ppm, significant kicks, or blow-out events.

G. WELL HEAD ASSEMBLY


NNE utilizes two types of wellhead/production configurations, casing flow and tubing flow. Casing flow will utilize either a 3-1/8" or 2-9/16" production tree and tubing flow will utilize 2-9/16" production trees. Both assemblies are rated for 5,000 PSI.


Initial production will occur via casing flow until the wells production decreases to a point where tubing needs to be installed. The casing flow configuration, starting at the tubing spool adapter from bottom to top, will consist of (1) 7" master valve, (1) lower master valve, (1) upper master valve, (1) 4-way tee with (2) wing valves (one on each side), (1) swab valve, and (1) tree cap. All components are rated to a minimum pressure rating of 5,000 PSI.

Once the well has tubing installed, the 7" master valve is removed, and the tree is mounted to the tubing spool adapter. The tubing flow configuration, starting at the tubing spool adapter from bottom to top, will consist of (1) 2-9/16" lower master valve, (1) 2-9/16" upper master valve, (1) 4-way tee with (2) 2-9/16" wing valves (one on each side), (1) 2-9/16" swab valve, and (1) tree cap. All components are rated to a minimum pressure rating of 5,000 PSI.

A schematic of the proposed wellhead and tree assembly for both configurations are shown below for reference.

Casing Flow Configuration





H. WELL CONTROL PLAN

- Surface Section (on air):
 - BOP Equipment: 26" riser with 30" rotating head
 - If a kick occurs:
 - ♣ Pick up off bottom
 - ♣ Bypass air and open to flowline venturi
 - ♣ Pump fresh water down drill string to kill the well
 - If unable to kill the well or manage to evacuate gas away from the rig:
 - ♣ Kill downhole air, venturi should remain active to vent gas from the rig
 - ♣ Evacuate personnel from location and call Wild Well Control (281-784-4700)
 - If non well related evacuation is required (ie. weather):
 - ♣ Pick up off bottom
 - ♣ Continue circulating if possible (2 compressors & 1 booster)
 - If not possible, kill air compressors
 - ♣ Shut down rig and evacuate location
- Intermediate Section (on air):
 - BOP Equipment: 13-5/8" 5k annular & 10k rams
 - If a kick occurs:
 - ♣ Space out (pick up until tool joint is at rig floor)
 - ♣ Bypass air (take air flow off the drill string and divert to flowline), open 2" valve on rig floor bleeding off any stored pressure in the drill string
 - ♣ Close annular or pipe rams (depending on how much gas/psi is present), open HCR valve
 - ♣ Rig will be configured for a Hard Shut In at the choke
 - ♣ Pump fluid down the drill string to kill the well, take returns through the Mud/Gas Separator
 - If unable to kill the well:
 - ♣ Kill pumps, close kelly valve, close in pipe rams, close choke, monitor psi, evacuate personnel from location and call Wild Well Control (281-784-4700)
 - If non well related evacuation is required (ie. weather):
 - ♣ Space out (pick up until tool joint is at rig floor)
 - ♣ Continue circulating if possible (2 compressors & 1 booster)
 - If not possible, kill air compressors

- Close kelly valve, close in pipe rams, close choke
 - ♣ Shut down rig and evacuate location.
- Intermediate or Production Section (on fluid):
 - BOP Equipment: 13-5/8" 5k annular & 10k rams
 - If a kick occurs:
 - ♣ Space out (pick up until tool joint is at rig floor)
 - ♣ Kill pumps, close annular or pipe rams (depending on how much gas/psi is present), open HCR valve
 - ♣ Rig will be configured for a Hard Shut In at the choke
 - ♣ Record pressures, start the Driller's Method to kill the well, take returns to Mud/Gas Separator
 - If unable to kill the well:
 - ♣ Kill pumps, close kelly valve, close in pipe rams, close choke, monitor psi, evacuate personnel from location and call Wild Well Control (281-784-4700)
 - If non well related evacuation is required (ie. weather):
 - ♣ Space out (pick up until tool joint is at rig floor)
 - ♣ Kill pumps, close kelly valve, close in pipe rams, close choke
 - ♣ Shut down rig and evacuate location

6

Hydrogen Sulfide ("H₂S")

A. DETECTION, MONITORING AND WARNING EQUIPMENT

Based upon previous experience and historical data, no H₂S is expected to be encountered during any operations covered by this plan. Detection equipment shall be deployed on or near potential sources of methane or hydrogen sulfide gases on the pad throughout the drilling process. Personnel working in proximity to potential H₂S sources on completions and production operations will be provided with 4-gas monitors.

A windsock and/or flags will be utilized on location to identify wind direction. A safe zone upwind and away from the well will be established.

If H₂S is detected an alarm shall sound and personnel will evacuate to the predetermined safe zone immediately. After personnel are in a safe area, the onsite supervisor will take a head count and make the proper offsite notifications.

If H₂S has been detected, and poses a hazard to the local community, NNE will alert local residents and businesses within a ½ mile radius of the well site (*see attached). Notification may be done in the form of a phone call or a door-to-door visit.

B. NOTIFYING THE OFFICE OF OIL AND GAS

When H₂S is encountered, after all personnel have gathered in the safe zone, the onsite supervisor will take a head count, and then proper offsite notifications shall be made. The DEP Office of Oil and Gas will be notified by phone calls to both the local inspector and the 24-hour emergency reporting service on 800-642-3074.

C. LIST OF PERSONAL PROTECTIVE EQUIPMENT ("PPE")

Operations and the geologic intervals covered in this plan historically have not included the presence of H₂S, for this reason H₂S specific PPE will not be kept on site. Centralized H₂S monitors will be used throughout the drilling process. Personal 4 gas monitors will be used by workers with potential exposure. Personnel on site will be trained to take the necessary steps to safely evacuate and make notifications to public and private third party H₂S trained emergency responders. NNE personnel will work with these parties to assess the hazards and bring in additional resources to mitigate the situation. Operations will not resume until all personnel have specific H₂S certification and are equipped with the proper PPE until the source of H₂S has been eliminated.

D. TRAINING

NNE personnel are trained in H₂S awareness annually.

7

Flaring

A. FLARING POLICY

NNE shall maintain a zero routine flaring policy. The policy pertains to routine flaring and not to flaring for safety reasons or non-routine flaring. Routine flaring of gas shall mean flaring during normal production operations in the absence of sufficient facilities or amenable geology to re-inject the produced gas, utilize it on-site, or dispatch it to a market.

B. NON-ROUTINE FLARING PLAN

(1.0) Drilling

During drilling operations, geologic formations are encountered that can lead to natural gas being brought to the surface by the circulating mud. This gas must be managed at the drilling rig to keep personnel safe. The gas is routed to a flare device which has a non-stop igniter. When the lower explosive limit is reached on the gas content, the flare is automatically ignited, destroying the methane and VOCs in order to maintain a safe operating environment on site. These flaring events, if they occur at all, are of short duration.

The flare placement will be at a height equal or greater to 25' or at a sufficient height taller than the gas separator. It will be located at a minimum 100' from an active well and at a safe location downwind, away from any hazards, and a safe distance from the rig and personnel housing.

(2.0) Completions – Flowback

Flares are not used during NNE's flowback process. Post frac, a system of 2" and 3" Figure 1502 integrated-hammer pup joints will be assembled from the wellhead to a 5,000 PSI plug catcher and choke manifold. The choke manifold shall consist of two parallel adjustable chokes to control the initial flow of the well. Using the same construction iron, from the choke manifold, flow will enter a high-capacity temporary production unit. The liquid fraction from the well will be diverted to gas buster equipped frac- tanks on location. Once the well starts making gas, the gas will be directly diverted through the choke manifold, and temporary production unit, and into the Production Gas Processing Units. Once the gas is accounted for in the GPU, it will then be sent down the sales line.

(3.0) Production

Flares are not used in NNE's production phase. Events that could result in flaring are handled by shutting in the well or routing to a combustor.

8

Collision Avoidance Safeguards, Practices and Standards

Scope of Work:

To ensure that wells are drilled in a safe manner that mitigates the risk of underground collisions on multi-well pads. Key portions of work will be described including roles, responsibilities and steps taken when returning to pads with existing producing or stimulated wells.

Definitions:

- 1) Proposed Wellbore- Involves sections of the vertical top-hole, the KOP, the lateral landing, and the lateral drilling to the total measured depth (TMD).
- 2) Nudge- Technique generally used in the vertical top-hole section. The well path is nudged from vertical to pass areas of possible magnetic interferences and to reduce the risk of collision by maintaining separation with other wellbores.
- 3) KOP- Kick off Point. Diverting a well path from one trajectory to another
- 4) MWD- Measurement While Drilling
- 5) LWD- Logging While Drilling
- 6) EM - Electromagnetic Telemetry
- 7) SF- Separation Factor or Clearance Factor: $SF^* = CC \div [UR_{ref} + UR_{off}]$
 - CC – Well separation distance (center to center of wellbores)
 - UR_{ref} – radius ellipse of uncertainty on reference well
 - UR_{off} – radius ellipse of uncertainty on offset well (Ellipses are half-axes or radii)
 - Calculation options may be considered
- 8) TMD- Total Measured Depth
- 9) Gyro – High accuracy well bore survey instrument unaffected by magnetic interference.
- 10) QC / QA – Quality Control and Quality Assurance
- 11) HSE – Health Safety and the Environment
- 12) UBHO Sub – Universal Bottom Hole Orientation Sub

Established descriptions of risk:

1) $SF \leq 1.0$	Level 1	Extreme collision risk
2) $SF = 1.0$ to 1.5	Level 2	High collision risk
3) $SF = 1.5$ to 2.0	Level 3	Moderate collision risk
4) $SF > 2.0$	Level 4	Low to no collision risk

Well Planning:

Prior to drilling any well, a directional plan will be developed to ensure that the well is properly placed with consideration to permits, lease limitations and future drilling plans. The well will be planned to maintain a SF of ≥ 2.0 whenever possible. If a SF of <2.0 is encountered, additional risk mitigation steps may be required such as increased survey frequency, wellbore steering or installing downhole mechanical barriers.

Survey Protocol:

When drilling wells on a pad without producing or stimulated wells, surveys will be taken every 30' - 500' in the vertical portion of the wellbore depending on wellbore trajectory, hole walk and risk of collision.

When drilling wells on a pad with producing or stimulated wells, surveys will be taken every 30' - 250' in the vertical portion of the wellbore depending on wellbore trajectory, hole walk and risk of collision.

Tool Alignment Procedure:

Tool alignment is critical in eliminating wellbore collision risks. In all wells, north seeking gyro tools, MWD/EM tools and anti-collision processes are utilized to mitigate the risk of downhole collisions. All work groups responsible for the placement of the wellbore share responsibility in ensuring accuracy. The Company Representative, Directional Drilling Supervisor and Gyro Supervisor are all responsible for the alignment of the UBHO Sub and the motor to ensure that azimuthal directional is correct. All parties should visually verify the orientation of the shoe and agree upon a coordinate system and reference point. When possible, MWD tools will be used to minimize risk of incorrect orientation.

Directional Planning and Controls – Vertical Wellbore:

Drilling Without Stimulated Wellbores:

When drilling on pads without producing or stimulated wells, all wells will be planned with a minimum SF ≥ 1.5 , whenever possible. Surveys will be taken at intervals of 500' to record the well path as it is drilled, but the frequency can be increased if needed. Drilling parameters should be held constant for the vertical portions of all wells to ensure the natural drilling path is similar for all wells on the pad. If two wells come within 10' of each other or a SF of ≤ 1.5 is reached, each survey is monitored closely and anti-collision is run after each survey until the wells are clear of a collision risk.

Following the drilling of the vertical section of the wellbore, a gyro survey will be taken. Anti-collision software will be used to analyze this data to ensure safe wellbore spacing. The directional company will utilize their own software to monitor and model wellbores for collision risks.

Drilling With Stimulated Wellbores:

If a rig is returning to a pad with producing or stimulated wellbores, additional steps are required to mitigate risks. Prior to commencing drilling, gyro data from existing wells is analyzed to determine normal hole walk. If a well does not have gyro data, a gyro survey will be run. Once all gyro data is gathered, a preliminary well path is planned to identify collision risks. That plan will be used to identify points of concern where additional risk mitigation steps are needed

When drilling wells on a pad with active production additional well path management practices will be employed. During this scenario, if two wells come within 14' or a SF ≤ 2.0 , each survey is monitored closely and anti-collision re-run after each survey until the wells are clear of a potential collision. The survey frequency can vary from 30'-250' depending on wellbore trajectory, hole walk and risk of collision.

Directional Planning and Controls – Curve and Lateral Wellbore:

While drilling the curve and lateral portions of the wellbores, MWD technology will be used to ensure the well path is drilled according to the drilling plan and the state permit. Azimuth, gamma ray, and other data will be collected and transmitted to the surface. The information will be analyzed by the Directional Drilling Contractor, Company Representative, Drilling Manager and Geologist to ensure the quality of the data and proper interpretation.

Gyro data and/or MWD/EM data will be evaluated in anti-collision software to monitor the path of the well being drilled in relationship to all adjacent wells to ensure an adequate SF is maintained during the vertical, curve and horizontal portions of the wellbore. Survey frequency is to be a minimum of 100' while MWD/EM tools are being utilized. Each survey is analyzed and certified as accurate by the directional company before it can be used for any modeling or directional planning.

Other Data:

Prior to drilling new wells on a pad, a site overview with the wellhead arrangement will be developed. Among the information that will be included is API number, surface footage separation and wellbore status. Additionally, all survey data for each existing well will be compiled for use in well planning.

Contingency Plans:

The wellbore being drilled will be monitored in relation to existing wellbores. Should the active well approach an existing well and the SF be < 1.5 , drilling will be suspended until risks are mitigated by adjusting the directional plan, increasing survey frequency and verifying any necessary mechanical barriers are present in the adjacent wells. If a SF ≤ 1 is experienced or two wellbores are within 5' of one another, the WV DEP Office of Oil and Gas Regional Inspector will be immediately contacted.

If the wellbore trajectories reach a point where a collision is unavoidable, NNE will properly secure each well and evaluate the most prudent path forward while openly communicating with the WV DEP Oil and Gas Regional Inspector.


Should a collision occur, the WV DEP Office of Oil and Gas Regional Inspector will be immediately contacted, drilling will be suspended, and all existing wells will be monitored for integrity. If a loss of pressure control in any well is experienced, Wild Well Control, or another professional well control company, will be contracted for technical support and services. If there is not a loss of pressure control, a separate well work procedure will be developed to repair or plug and abandon the affected wells.



NORTHEAST NATURAL ENERGY, LLC

Area: Monongalia County, WV
Field: Monongalia
Facility: Laurita Pad
Slot: 9H

Well: Laurita 9H
UWI/Legal:
Wellbore: Laurita 9H PWB
Wellpath: Laurita 9H PWP Ex-01



10/02/2026



May 15, 2026

WV Department of Environmental Protection
Office of Oil and Gas Management
601 57th Street, SE
Charleston, WV 25304

RE: Laurita 5H

Dear Permit Reviewer:

Please be advised that Northeast Natural Energy LLC has the right to drill, extract and produce the minerals beneath the following as identified on the included plat:

- Facemine Rd (Route 37/10)
- Stewart Run Rd
- Hagans Rd (Route 37)
- Hawkins Run

Sincerely,

A handwritten signature in black ink that reads 'Justin Moroosse'.

Justin Moroosse
Land Acquisition Manager



TWO WORKING DAYS PRIOR TO EXCAVATION, THE
CONTRACTOR MUST CONTACT THE WV ONE CALL
SYSTEM, INC., 1-800-245-4848
(WV ONE CALL TICKET #24075227904)

OWNER

MARION NATURAL ENERGY LLC
707 VIRGINIA STREET EAST, SUITE 1200,
CHARLESTON, WV 25301

LAURITA WELL PAD GRANT DISTRICT, MONONGALIA COUNTY, WV AUGUST 2025

SHEET INDEX

1. TITLE SHEET
- 2-3. EVAC ROUTE/ PREVAILING WIND
4. E&S CONTROL LAYOUT OVERVIEW
- 5-7. E&S CONTROL LAYOUT
8. E&S CONTROL AND SITE PLAN OVERVIEW
- 9-11. E&S CONTROL AND SITE PLAN
- 12-14. PROFILES
- 15-26. CROSS-SECTIONS
- 27-30. DETAILS
31. RECLAMATION PLAN OVERVIEW
- 32-34. RECLAMATION PLAN

TOTAL DISTURBED AREA: 29.34 AC.
ACCESS ROAD DISTURBED AREA: 12.73 AC.
AST PAD DISTURBED AREA: 3.30 AC.
WELL PAD DISTURBED AREA: 11.85 AC.
COUNTY ROAD RIGHT-OF-WAY AREA: 1.46 AC.

PROPERTY OWNER DISTURBANCE - 27.88 AC.

EXHIBIT B MARION NATURAL ENERGY LLC (TAX MAP AND PARCEL NUMBER 7-17-36) 24.48 AC.
EXHIBIT A PARCEL 1 MARION NATURAL ENERGY LLC (TAX MAP AND PARCEL NUMBER 7-17-34) 1.14 AC.
MATHEW JEFFRIES & PHILIP JEFFRIES (TAX MAP AND PARCEL NUMBER 7-17-33) 2.24 AC.
TOM P SANDOVAL (TAX MAP AND PARCEL NUMBER 7-17-32.1) 0.02 AC.



**APPROVED
WVDEP OOG**
9/10/2025

IN ACCORDANCE WITH WV 35 CSR 8
THE FOLLOWING EROSION & SEDIMENT CONTROL PLAN HAS BEEN
DESIGNED IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES
ESTABLISHED BY THE CHIEF AND PROVIDED IN THE OFFICE'S EROSION AND
SEDIMENT CONTROL FIELD MANUAL. A GENERAL CONSTRUCTION
SEQUENCE, DESCRIPTION OF STABILIZATION METHODS, AND DETAILS &
SPECIFICATIONS FOR EROSION & SEDIMENT BEST MANAGEMENT
PRACTICES HAVE BEEN INCLUDED IN THE PROVIDED DETAIL SHEETS.

TITLE SHEET

LAURITA WELL PAD
GRANT DISTRICT,
MONONGALIA COUNTY, WV
AUGUST 2025

SHEET

1
OF
34

PLANS PREPARED BY:

BOORD BENCHEK & ASSOC., INC.
ENGINEERING, SURVEYING, CONSTRUCTION AND MINING SERVICES
SOUTHPOINTE, PA 15317 PHONE: 724-746-1055




ANDREW BENCHEK
P.E.

DATE

COORDINATES

CENTER OF WELL
(NAD 83)
LAT: 39° 35' 40.38"
LONG: 80° 06' 34.06"
(NAD 83)
LAT: 39.59455
LONG: -80.10946
(NAD 27)
LAT: 39° 35' 40.08"
LONG: 80° 06' 34.80"

SITE ENTRANCE
(NAD 83)
LAT: 39° 35' 31.49"
LONG: 80° 06' 49.46"
(NAD 83)
LAT: 39.59208
LONG: -80.11374
(NAD 27)
LAT: 39° 35' 31.19"
LONG: 80° 06' 50.20"



1"=1000'



