

WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOL MINING COMPANY LLC  
Lease or Property Owner  
275 Technology Drive, Suite 101, Canonsburg, PA 15317  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
HUNDRED, WV 7.5'  
Well Location  
Battelle  
District  
Monongalia  
County  
MD34  
Well No.  
GOODKNIGHT #1  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Robert Hitt


AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 13<sup>th</sup> day of July 2026 and that the well was plugged in the following manner:

| Sand or Zone<br>Record<br>Formation                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Filling Material    | Casing/Tubing Size                                                                                                                                               | Casing<br>Pulled | Casing<br>Left In |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|-------------------|
| Cleaned a 12 1/4" hole from surface to 291'. Reduced hole size to a 9 7/8" and cleaned hole from 291' to 1434'. Cleaned a 9 7/8" hole through the Pittsburgh Coal seam located from 1201.5' to 1208.75'. Left 20' of 16" conductor from surface to 20'.<br><br><b>Cemented the hole from surface to surface as follows:</b><br>From 1434' to 1001' using 315 sacks of Thixotropic Cement with a Green Dye and Gas Blocker additive. From 1001' to surface using 610 sacks of Expandable Cement. Cement did circulate at surface. A total of 925 sacks of cement were used to cement the hole from 1434' to surface. |                     | 16" Conductor                                                                                                                                                    | 0'               | 20'               |
| Coal Seams                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                     | Description of Monument                                                                                                                                          |                  |                   |
| Pittsburgh                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 1201.5' to 1208.75' | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. |                  |                   |

... and that the work of plugging and filling said well was completed on the 28<sup>th</sup> day of July 2026



Matthew A Yearsley  
Matthew A. Yearsley

Delbert Moore  
Delbert Moore

Sworn to and subscribed before me this 24<sup>th</sup> day of August 2026

Notary Public

My commission expires:

August 13, 2029

Permit No. 47-061-02035-00-00  
Well No. MD34  
Latitude: 39° 40' 48.4" N  
Longitude: -80° 23' 22.2" W

09/18/2026

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Goodknight #1 Operator Well No.: MD34

LOCATION: Elevation: 1404.36' Quadrangle: Hundred  
District: Battelle County: Monongalia  
Latitude: 39.6801042 Feet South of 39 Deg. 40 Min. 48.4 Sec.  
Longitude: -80.389495 Feet West of 80 Deg. 23 Min. 22.2 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

|                    |                                         |               |                                         |
|--------------------|-----------------------------------------|---------------|-----------------------------------------|
| Company            | <u>West Virginia Land Resources Inc</u> | Coal Operator | <u>West Virginia Land Resources Inc</u> |
|                    | <u>1 Bridge Street</u>                  | or Owner      | <u>1 Bridge Street</u>                  |
|                    | <u>Monongah, WV 26554</u>               |               | <u>Monongah, WV 26554</u>               |
| Agent              | <u>David Roddy</u>                      | Coal Operator | _____                                   |
| Permit Issued Date | <u>6/5/2026</u>                         | or Owner      | _____                                   |

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:


Matthew A. Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13th day of July, 2026, and the well was plugged and filled in the following manner:

| TYPE                                    | FROM  | TO      | PIPE REMOVED     | LEFT |
|-----------------------------------------|-------|---------|------------------|------|
| Truss-type Cement + Open Dy + Gas Block | 1434' | 1001'   | 16" Conductor 0' | 20'  |
| Expandable Cement                       | 1001  | Surface |                  |      |
|                                         |       |         |                  |      |
|                                         |       |         |                  |      |
|                                         |       |         |                  |      |
|                                         |       |         |                  |      |

RECEIVED  
Office of Oil and Gas  
SEP 08 2026  
WV Department of  
Environmental Protection

Description of monument: 77" of 7" casing w/company name, well number, permit number and date cemented and that the work of plugging and filling said well was completed on the 28th day of July, 2026.

And further deponents saith not. Matthew A Yearsley  
Delbert Moore



Sworn and subscribe before me this 24th day of August, 2026  
My commission expires August 13, 2029  
Kerri A McCormick  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Robert J. Hitt 8-26-26 Title: OG Inspector

09/18/2026