



New Location X
 Drill Deeper
 Abandonment

Company CECIL E. TEDROW
 Address WAYNESBURG, PA.
 Farm S. R. MORROW
 Tract 1 Acres 213.36 Lease No. _____
 Well (Farm) No. 1 Serial No. _____
 Elevation (Spirit Level) 926'
 Quadrangle WHEELING
 County OHIO District RICHLAND
 Engineer WALTER W. STEGMAN
 Engineer's Registration No. 394
 File No. _____ Drawing No. 2025
 Date JULY 30, 1947 Scale 1 inch = 400 Ft.

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. OHIO - 10

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.

- Denotes one inch spaces on border line of original tracing.

5-0 0

WEST VIRGINIA DEPARTMENT OF MINES
OIL & GAS DIVISION
WELL RECORD

Permit No., Ohio 10		Dry Hole
Wheeling Quad,		CASING & TUBING
Company	Cecil E. Tedrow	
Address	R.F.D. #4 Waynesburg, Pa.	10 152
Farm	S.R. Morrow Acres 213.36	8 772
Location	South Fork of Short Creek	6 5/8 1028
Well No.	1	Elev. 926'
District	Richland Ohio County	Coal at 120'
Surface	S.R. Morrow, Wheeling, W.Va.	
Mineral	Same	
Oil	One Half(1/2) bbls, 1st 24 hrs.	
Fresh Water	35'	
Salt Water	778'-800'; 885'-900'; 985'-1000'	

Slate & Shells	0	120
Pittsburgh Coal	120	126
Slate & Shells	126	200
Sand	200	225
Slate	225	500
Sand	500	540
Slate	540	772
Sand	772	865
Slate	865	885
Sand	885	945
Slate	945	985
Sand	985	1070
Slate	1070	1105
Lime	1105	1140
Injun Sand	1140	1416
Slate	1416	1790

APR 18 1948

DRILLED DEEPER		
Slate	1790	2200
Shale	2200	3048
Total Depth		3048
Show of oil	1140-1416	

Dev. Shale - T.D.

No sands were encountered below the Big Injun Sand
Absolutely no chance of production in lower formations.