

State of West Virginia
Department of Environmental Protection
Office of Oil and Gas
Well Operator's Report of Well Work

Farm name: Deborah Craig OHI 3H Operator Well No.: 833806

LOCATION: Elevation: 1331' Quadrangle: Valley Grove

District: Tridelphia County: Ohio
Latitude: 400' Feet South of 40 Deg. 05 Min. 00 Sec.
Longitude 12940' Feet West of 80 Deg. 35 Min. 00 Sec.

Company: Chesapeake Appalachia, L.L.C.

| Address: | Casing & Tubing | Used in drilling | Left in well | Cement fill up Cu. Ft. |
|--|-----------------|------------------|--------------|------------------------|
| P.O. Box 18496 Oklahoma City, OK 73154-0496 | 20" | 126' | 126' | Driven |
| Agent: Eric Gillespie | 13 3/8" | 739' | 739' | 729 Cu. Ft. |
| Inspector: Bill Hendershot | 9 5/8" | 2295' | 2295' | 1021 Cu. Ft. |
| Date Permit Issued: 11-16-2011 | 5 1/2" | 13947' | 13947' | 2851 Cu. Ft. |
| Date Well Work Commenced: 3-23-2012 | | | | |
| Date Well Work Completed: 6-5-2012 | | | | |
| Verbal Plugging: | | | | |
| Date Permission granted on: | | | | |
| Rotary <input checked="" type="checkbox"/> Cable <input type="checkbox"/> Rig <input type="checkbox"/> | | | | |
| Total Vertical Depth (ft): 6537'(cement plug@ 5663' - 6512') | | | | |
| Total Measured Depth (ft): 13950' | | | | |
| Fresh Water Depth (ft.): 82', 350' | | | | |
| Salt Water Depth (ft.): 1520' | | | | |
| Is coal being mined in area (N/Y)? N | | | | |
| Coal Depths (ft.): 683' | | | | |
| Void(s) encountered (N/Y) Depth(s) N | | | | |

OPEN FLOW DATA (If more than two producing formations please include additional data on separate sheet)

Producing formation Marcellus Pay zone depth (ft) 6,950'-13,814'

Gas: Initial open flow _____ MCF/d Oil: Initial open flow _____ Bbl/d

Final open flow Not Tested MCF/d Final open flow _____ Bbl/d

Time of open flow between initial and final tests _____ Hours

Static rock Pressure _____ psig (surface pressure) after _____ Hours

Second producing formation _____ Pay zone depth (ft) _____

Gas: Initial open flow _____ MCF/d Oil: Initial open flow _____ Bbl/d

Final open flow _____ MCF/d Final open flow _____ Bbl/d

Time of open flow between initial and final tests _____ Hours

Static rock Pressure _____ psig (surface pressure) after _____ Hours

RECEIVED
AUG 29 2012
WV GEOLOGICAL SURVEY
MORGANTOWN, WV

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this document and all the attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information I believe that the information is true, accurate, and complete.

Marlene Williams
Signature

8-28-2012
Date

Were core samples taken? Yes _____ No N

Were cuttings caught during drilling? Yes Y No _____

Were Electrical, Mechanical or Geophysical logs recorded on this well? If yes, please list GR, neutron, density, and resistivity
open hole logs run from 0-2318' MD; LWD GR from 5662-13950' MD.

NOTE: IN THE AREA BELOW PUT THE FOLLOWING: 1). DETAILS OF PERFORATED INTERVALS, FRACTURING OR STIMULATING, PHYSICAL CHANGE, ETC. 2). THE WELL LOG WHICH IS A SYSTEMATIC DETAILED GEOLOGICAL RECORD OF THE TOPS AND BOTTOMS OF ALL FORMATIONS, INCLUDING COAL ENCOUNTERED BY THE WELLBORE FROM SURFACE TO TOTAL DEPTH.

Perforated Intervals, Fracturing, or Stimulating:

(See Attached)

Plug Back Details Including Plug Type and Depth(s): Cement plug @ 5663' - 6512'

| <u>Formations Encountered:</u> | <u>Top Depth</u> | <u>/</u> | <u>Bottom Depth</u> |
|--------------------------------|------------------|----------|---------------------|
| <u>Surface:</u> | | | |

(See Attached)

RECEIVED
AUG 29 2012
WV GEOLOGICAL SURVEY
MORGANTOWN, WV

PERFORATION RECORD ATTACHMENT

Well Number and Name: 833806 Deborah Craig OHI 3H

| PERFORATION RECORD | | | STIMULATION RECORD | | | | | | | |
|--------------------|---------------------|--------|--------------------|------------------|--------|---------|--------|----------------|---------|-------------------|
| Date | Interval Perforated | | Date | Interval Treated | Type | Fluid | | Propping Agent | | Average Injection |
| | From | To | | | | Amount | Type | Amount | Type | |
| 5/20/2012 | 13,271 | 13,814 | 6/1/2012 | 13,271 | 13,814 | Slk wtr | 11,450 | Sand | 629,800 | 83 |
| 6/1/2012 | 12,646 | 13,182 | 6/1/2012 | 12,646 | 13,182 | Slk wtr | 12,275 | Sand | 630,780 | 85 |
| 6/1/2012 | 12,012 | 12,550 | 6/2/2012 | 12,012 | 12,550 | Slk wtr | 11,468 | Sand | 630,640 | 84 |
| 6/2/2012 | 11,375 | 11,918 | 6/2/2012 | 11,375 | 11,918 | Slk wtr | 11,695 | Sand | 621,800 | 82 |
| 6/2/2012 | 10,743 | 11,286 | 6/2/2012 | 10,743 | 11,286 | Slk wtr | 11,631 | Sand | 631,300 | 84 |
| 6/2/2012 | 10,110 | 10,654 | 6/3/2012 | 10,110 | 10,654 | Slk wtr | 11,642 | Sand | 631,380 | 85 |
| 6/3/2012 | 9,478 | 10,021 | 6/3/2012 | 9,478 | 10,021 | Slk wtr | 11,189 | Sand | 630,580 | 86 |
| 6/3/2012 | 8,851 | 9,389 | 6/4/2012 | 8,851 | 9,389 | Slk wtr | 12,703 | Sand | 629,080 | 85 |
| 6/4/2012 | 8,219 | 8,757 | 6/4/2012 | 8,219 | 8,757 | Slk wtr | 10,963 | Sand | 630,980 | 86 |
| 6/4/2012 | 7,587 | 8,125 | 6/4/2012 | 7,587 | 8,125 | Slk wtr | 11,341 | Sand | 630,920 | 85 |
| 6/5/2012 | 6,950 | 7,493 | 6/5/2012 | 6,950 | 7,493 | Slk wtr | 11,004 | Sand | 646,780 | 85 |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

RECEIVED
 AUG 29 2012
 WV GEOLOGICAL SURVEY
 MORGANTOWN, WV

LATERAL SIDETRACK WELLBORE (no vertical pilot hole associated with this well)**Maximum TVD of wellbore: 6537 ft TVD @ 6990 ft MD**

| Formation/Lithology | Top Depth, MD (ft) | Top Depth, TVD (ft) | Bottom Depth, MD (ft) | Bottom Depth, TVD (ft) |
|---------------------|-----------------------|------------------------|--------------------------|---------------------------|
| LS/SS | 0 | 0 | 683 | 683 |
| PITTSBURG COAL | 683 | 683 | 690 | 690 |
| LS | 690 | 690 | 840 | 840 |
| SS | 840 | 840 | 990 | 990 |
| SS/SH | 990 | 990 | 1770 | 1770 |
| BIG LIME (LS) | 1770 | 1770 | 1820 | 1820 |
| BIG INJUN (SS) | 1820 | 1820 | 2057 | 2057 |
| SHALE | 2057 | 2057 | 6446 | 6344 |
| GENESEO (SH) | 6446 | 6344 | 6474 | 6362 |
| TULLY (LS) | 6474 | 6362 | 6528 | 6396 |
| HAMILTON (SH) | 6528 | 6396 | 6759 | 6502 |
| MARCELLUS (SH) | 6759 | 6502 | | |
| TD OF LATERAL | | | 13950 | 6443 |

RECEIVED
AUG 29 2012
WV GEOLOGICAL SURVEY
MORGANTOWN, WV