

AMELIA WELSHAN NO. 2 WELL.

30027

Richland District, Ohio County, W. Va.
 Drilled by Treat and Rowland, Pittsburgh, Pa.
 Commenced, March 10, 1911; completed, April 24, 1911.
 Shot April 26, 1911, with 30 qts.
 Results: 3,000,000 cu. ft. gas and 25 bbls. oil.
 Still producing oil and gas (April 1, 1939).
 Conductor, 13"; 10" casing, 142'; 8 $\frac{1}{4}$ ", 830'; 6 $\frac{5}{8}$ ", 1368'.
 Record from Dr. Charles H. Clevis, 33 Walnut Ave., Woodlawn,
 Wheeling, W. Va., April 1, 1939.

	Top.	Bottom.
Coal	120	- ...
Coal, Mapletown (Sewickley)	285	- ...
Coal, Pittsburgh	365	- ...
Coal, Freeport	800	- ...
Cow Run Sand	958	- 978
Salt Sand	1090	- 1135
Lime	1360	-
Big Injun Sand	1440	- 1640
Stray sand	1952	- 1967
Berea Sand (oil and gas, 2005-2014')	2002	- 2016