

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

(REQUIRED BY SECTION 2, CHAPTER 86, ACTS 1929)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS SECTION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

Patton & Wilson Heirs

COAL OPERATOR OR COAL OWNER

G.F. Eagon

NAME OF WELL OPERATOR

Care, B.F. Patton,

ADDRESS

1356 Manchester Rd

COMPLETE ADDRESS

Akron, Ohio

Harrisville, W.Va.,

COAL OPERATOR OR COAL OWNER

Aug. 10

1934

PROPOSED LOCATION

ADDRESS

Murphy

District

COAL OPERATOR OR COAL OWNER

Ritchie

County

ADDRESS

Well No. 6

Patton & Wilson Heirs Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated June 5

1934

, made by Patton & Wilso Heirs, to

G.F. Eagon

, and recorded on the 12 day

of July 1934, in the office of the County Clerk for said County in

Lease Book 62, page 352

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective address.....day.... before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

G.F. Eagon

WELL OPERATOR

Address of Well Operator }

Manchester Rd

STREET

CITY OR TOWN

Akron, Ohio.

STATE

*Section 3 If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

AUG 13 1934

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. Rit-242

Oil or Gas Well.....
(Kind)

| | | | | | |
|--|---|------------------------------|------------------|--------------|---------------------|
| Company..... | <u>Patt- G. F. Eagon</u> | Casing and Tubing | Used in Drilling | Left in Well | Packers |
| Address..... | <u>New Martinsville, W. Va.</u> | Size | | | |
| Farm..... | <u>Patterson & Wilson</u> Acres <u>6.30</u> | 16..... | | | Kind of Packer..... |
| Location (waters)..... | | 13..... | | | Size of..... |
| Well No. <u>6</u> | Elev. <u>975</u> | 10..... | <u>130ft</u> | <u>130ft</u> | Depth set..... |
| District <u>Murphy</u> | County <u>Putnam</u> | 8 1/4..... | <u>1085</u> | <u>11</u> | |
| The surface of tract is owned in fee by..... | Address..... | 6 5/8..... | <u>1583</u> | <u>1583</u> | |
| Mineral rights are owned by..... | Address..... | 5 3/16..... | | | |
| Drilling commenced..... | | 3..... | | | Perf. top..... |
| Drilling completed..... | <u>1935</u> | 2..... | <u>1940</u> | <u>1940</u> | Perf. bottom..... |
| Date shot..... | Depth of shot..... | Liners Used..... | | | Perf. top..... |
| Open Flow /10ths Water in..... | Inch | | | | Perf. bottom..... |
| /10ths Merc. in..... | Inch | | | | |
| Volume..... | Cu. Ft. | CASING CEMENTED..... | SIZE..... | No. FT..... | Date |
| Rock Pressure..... | lbs. hrs. | | | | |
| Oil..... | bbls., 1st 24 hrs. | COAL WAS ENCOUNTERED AT..... | FEET..... | INCHES | |
| Fresh water..... | feet | | FEET..... | INCHES..... | FEET..... |
| Salt water..... | feet | | FEET..... | INCHES..... | FEET..... |

| Formation | Color | Hard or Soft | Top | Bottom | Oil Gas or Water | Depth Found | Remarks |
|----------------|----------|--------------|------|--------|------------------|-------------|---------|
| Soil | Brown | Soft | 0 | 10 | | | |
| Clay | red rock | soft | 10 | 590 | | | |
| sand | white | hard | 590 | 610 | | | |
| | white | soft | 610 | 720 | | | |
| Shale | white | hard | 720 | 745 | | | |
| Sand | white | Soft | 745 | 850 | | | |
| Slate | white | hard | 750 | 875 | | | |
| Sand | white | Soft | 875 | 975 | | | |
| Rock | red | Soft | 975 | 990 | | | |
| little Dunkard | gray | Soft | 990 | 1115 | | | |
| Shale | white | Soft | 1115 | 1145 | | | |
| Big Dunkard | white | Soft | 1145 | 1362 | | | |
| Slate | white | Soft | 1362 | 1505 | | | |
| Salt Sand | white | Hard | 1505 | 1516 | | | |
| Slate | Black | Soft | 1516 | 1683 | | | |
| Shale | white | Soft | 1683 | 1790 | Gas. | | |
| Salt Sand | white | hard | 1790 | 1805 | 1712 | 1714 | |
| Slate | White | Soft | | | | | |



(Title)

By

WEST VIRGINIA DEPARTMENT OF MINES

APPROVED

Owner

WELL RECORD

Date

19

| Formation | Color | Hard or Soft | Top | Bottom | Oil, Gas or Water | Depth Found | Remarks |
|----------------|-------|--------------|------|--------|-------------------|--------------|---------|
| Sand | white | hard | 1805 | 1814 | | | |
| Slate | black | soft | 1814 | 1870 | | | |
| Magnesian Sand | white | stark | 1870 | 1952 | oil | 1920 to 1924 | |
| Big lime | white | stark | 1952 | 2020 | | | |
| Keokuk Sand | white | stark | 2020 | 2105 | | | |

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

INSPECTOR'S WELL REPORT

Permit No. _____

Oil or Gas Well
(KIND) _____

| | | | | |
|---|--|------------------|--------------|---|
| Company _____ Address _____ Farm _____ Well No. _____ District _____ County _____ Drilling commenced _____ Drilling completed _____ Total depth _____ Date shot _____ Depth of shot _____ Initial open flow _____ /10ths Water in _____ Inch Open flow after tubing _____ /10ths Merc. in _____ Inch Volume _____ Cu. Ft. Rock pressure _____ lbs. _____ hrs. Oil _____ bbls., 1st 24 hrs. Fresh water _____ feet _____ feet Salt water _____ feet _____ feet | CASING AND TUBING Size 16 13 10 8 1/4 6 5/8 5 3/16 3 2 Liners Used | USED IN DRILLING | LEFT IN WELL | PACKERS Kind of Packer _____ Size of _____ Depth set _____ Perf. top _____ Perf. bottom _____ Perf. top _____ Perf. bottom _____ |
| CASING CEMENTED _____ SIZE _____ No. FT. _____ Date _____ | | | | |
| COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES | | | | |
| _____ FEET _____ INCHES _____ FEET _____ INCHES | | | | |
| _____ FEET _____ INCHES _____ FEET _____ INCHES | | | | |

Drillers' Names _____

Remarks: _____

DATE _____

DISTRICT WELL INSPECTOR _____





STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

None
COAL OPERATOR OR COAL OWNER

Dan Henthorn
NAME OF WELL OPERATOR

ADDRESS

Route 2, New Martinsville, W. Va.
COMPLETE ADDRESS

None
COAL OPERATOR OR COAL OWNER

Well drilled 19 35
WELL TO BE ABANDONED

None
ADDRESS

Murphy District

Eva Patton
LEASE OR PROPERTY OWNER

Richie County

Harrisonville, W. Va.
ADDRESS

Well No. 6
Patton & Wilson Farm

NOTIFY INSPECTOR O. C. HOWARD - GRANTSVILLE - TELEPHONE 108
24 HOURS IN ADVANCE OF PLUGGING DATE

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence


the work of plugging and abandoning said well on the 1 day of June, 1948,
(which date shall not be less than five days after the day on which this notice so mailed is received,
or in due course should be received by the Department of Mines.)

This notice is given you in order that your respective representatives may be present at the
plugging and filling of said well. You are further notified that whether you are represented or not
represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said
well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the
reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the
above date.

Very truly yours,

Dan Henthorn
Well Operator.



NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent
engineer, showing the district and county in which the tract of land is located, the name and acreage of same,
the names of the owners and adjacent tracts, and the location of the about to be abandoned well, determined
by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall
be submitted with this notice.

(Over)

Rit-242-P

RIT-242-P PERMIT NUMBER

PROPOSED MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY RULES AND REGULATIONS)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

WORK ORDER

Well to be plugged and filled as follows:

fill from 1949 to 1899
1700 " 1660
" " 140 " Top

WORK ORDER INTERPOSED BY THE DEPARTMENT OF MINES

Total Depth 2105'

Pull 2" Tubing

Fill with red clay from bottom to 1900'

Neat Cement 1900' - 1890'

5' crushed stone on cement plug - sealing Big Lime and Keener Sand

SET A PERMANENT BRIDGE AT 1750'

2 sacks neat cement and 5' crushed stone on bridge

Fill with red clay to 1690'

Neat Cement 1690' - 1680'

5' crushed stone on cement plug - sealing off gas in Salt Sands

Continue filling with clay to 1600'

Pull 6-5/8" casing

SET A PERMANENT BRIDGE AT 1085' - casing seat of 8-1/4" casing

2 sacks neat cement and 5' crushed stone on bridge

Fill with clay to 955' - 20' above Little Dunkard

Neat Cement 955' - 945'

SET A PERMANENT BRIDGE AT 600'

Fill with clay and cavings to surface and ERECT MARKER SUCH AS IS DESCRIBED in Rule 18, 1931 Regulations

To the Department of Mines
Coal Owner or Operator,
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

Dan Penton
Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this

8th day of JUNE, 1948, 19

DEPARTMENT OF MINES
Oil and Gas Division

By: _____

NOTE: This "work order" shall be filed in triplicate, one copy for the files of the Department of Mines; one to be approved or corrected and returned to the well operator as his authority for plugging said well; and one for the well inspector.

Handwritten text in blue ink, possibly a signature or date, located in the middle-left section of the page.