

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

(REQUIRED BY SECTION 2, CHAPTER 86, ACTS 1929)

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS SECTION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

none
COAL OPERATOR OR COAL OWNER

ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

John M. Traylor
NAME OF WELL OPERATOR

Enterprise W. Va.
COMPLETE ADDRESS

September 30 1934
PROPOSED LOCATION

Blay District

Ritchie County

Well No. *one*
W.C. Butcher Farm

GENTLEMEN :

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated.....

July 10th 1934, made by *W.C. Butcher & others*, to *John M. Traylor*, and recorded on the..... day of....., in the office of the County Clerk for said County in

Book *62*, page.....

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above

named coal operators or coal owners at their above shown respective address.....day.... before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

John M. Traylor
WELL OPERATOR

Address of Well Operator }

STREET

Enterprise
CITY OR TOWN

W Va
STATE

*Section 3 If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

SEP 15 1934

258

over

W.C. Butcher

Post Office

Highland W. Va

W. T. Butcher

Bremman Ohio

John W. Butcher
NAME OF WELL OPERATOR

Highland W. Va
ADDRESS

Highland W. Va
PROPOSED LOCATION

Highland W. Va
COUNTY

Highland W. Va
TOWN

Highland W. Va
The undersigned well operator is entitled to drill upon the above named land or tract of land for

oil and gas having fee title thereto (or as the case may be) under grant or lease dated

July 10th 1910
made by *W.C. Butcher* and recorded on the

of the office of the County Clerk for said County in

the undersigned well operator is informed and believes there are no coal operators operating here

within the limits of the land on which said well is located, or within 500 feet of the bound-

aries of the same, who have notified their workmen and filed their names as required by law, excepting the

coal operators named above in this application, and that any objections they may

have to make to such proposed location or which they are required to make by Section 3 of said Act, if

the drilling of a well at said proposed location will cause a dangerous condition in or about their respective

premises, they shall file with the Department of Mineral Resources a written statement of such condition

and the reasons therefor, and the Department of Mineral Resources shall cause the same to be

published in the official gazette of the State of West Virginia, and the same shall be

open for a period of thirty days for the filing of objections, and if no such objections are filed or are

John W. Butcher
NAME OF WELL OPERATOR

Highland W. Va
ADDRESS

Highland W. Va
PROPOSED LOCATION

Highland W. Va
COUNTY

Highland W. Va
TOWN

Highland W. Va
The undersigned well operator is entitled to drill upon the above named land or tract of land for

oil and gas having fee title thereto (or as the case may be) under grant or lease dated

July 10th 1910
made by *W.C. Butcher* and recorded on the

of the office of the County Clerk for said County in

the undersigned well operator is informed and believes there are no coal operators operating here

within the limits of the land on which said well is located, or within 500 feet of the bound-

aries of the same, who have notified their workmen and filed their names as required by law, excepting the

coal operators named above in this application, and that any objections they may

have to make to such proposed location or which they are required to make by Section 3 of said Act, if

the drilling of a well at said proposed location will cause a dangerous condition in or about their respective

premises, they shall file with the Department of Mineral Resources a written statement of such condition

and the reasons therefor, and the Department of Mineral Resources shall cause the same to be

published in the official gazette of the State of West Virginia, and the same shall be

open for a period of thirty days for the filing of objections, and if no such objections are filed or are

John W. Butcher
NAME OF WELL OPERATOR

Highland W. Va
ADDRESS

Highland W. Va
PROPOSED LOCATION

Highland W. Va
COUNTY

Highland W. Va
TOWN

Highland W. Va
The undersigned well operator is entitled to drill upon the above named land or tract of land for

oil and gas having fee title thereto (or as the case may be) under grant or lease dated

July 10th 1910
made by *W.C. Butcher* and recorded on the

of the office of the County Clerk for said County in

the undersigned well operator is informed and believes there are no coal operators operating here

within the limits of the land on which said well is located, or within 500 feet of the bound-

aries of the same, who have notified their workmen and filed their names as required by law, excepting the

coal operators named above in this application, and that any objections they may

have to make to such proposed location or which they are required to make by Section 3 of said Act, if

the drilling of a well at said proposed location will cause a dangerous condition in or about their respective

premises, they shall file with the Department of Mineral Resources a written statement of such condition

and the reasons therefor, and the Department of Mineral Resources shall cause the same to be

published in the official gazette of the State of West Virginia, and the same shall be

open for a period of thirty days for the filing of objections, and if no such objections are filed or are



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. RIT-258

Oil or Gas Well Oil
(KIND)


Company Mihlbauer & Tice
Address Box 76, Ellenboro, W. Va.
Farm W. C. Butcher Acres 100
Location (waters) Bonds Creek
Well No. 1 Elev. 848'
District Clay County Ritchie
The surface of tract is owned in fee by W. C. Butcher
Address Highland, W. Va
Mineral rights are owned by same party
Address _____
Drilling commenced no record
Drilling completed no record
Date Shot From _____ To _____
With _____

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10			Size of
8 1/4			
6 5/8	1400'	1400'	Depth set
5 3/16			
3			Perf. top
2		1800'	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water _____ feet _____ feet
Salt water _____ feet _____ feet

CASING CEMENTED no SIZE _____ No. Ft. _____ Date _____
COAL WAS ENCOUNTERED AT none FEET _____ INCHES
FEET _____ INCHES FEET _____ INCHES
FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand			1788'	###1824'			In jun
Sand			1824	1890'			



John M. Traxler, et als Company

COMPLETION DATA SHEET

Enterprise, West Virginia Address

No. 2

FORMATION RECORD

Well No. 1 RIT 258

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Sandstone	gray	hard		848	898	50 ft.	50 ft.	
Redrock	red	soft		898	938	40 "	90"	
Coal Blossom				938	940	2 "	92"	
Slate (grey)	grey	soft		940	970	30 "	122"	
Slate	black	soft		970	1005	35 "	157"	
Slate	grey	soft		1005	1045	40 "	197"	
Red rock		soft		1045	1065	20 "	217"	
Slate	grey	soft		1065	1097	32 "	249"	
State	brown	"		1097	1137	40 "	289"	
Shale	grey	"		1137	1172	35 "	324"	
Red rock		"		1172	1192	20 "	344"	
Shale	grey	"		1192	1222	30 "	374"	
Slate		"		1222	1242	20 "	394"	
Red rock		"		1242	1282	40 "	434"	
Slate (color not given)		"		1282	1332	50 "	484"	
Sand	"	" hard		1332	1366	34 "	518"	
Slate	grey	soft		1366	1432	66 "	584"	
Red rock		"		1432	1444	12 "	596"	
Lime shell		hard		1444	1452	8 "	604"	
White slate		"		1452	1602	150 "	754"	
Pink rock		soft		1602	1616	14 "	768"	
1st cow run		hard		1616	1624	8 "	776"	
Shale				1624	1654	30 "	806"	
Red rock		soft		1654	1762	108 "	914"	
2nd cow run		hard		1762	1792	30 "	944"	
Slate	grey	soft		1792	1852	60 "	1004"	
Slate & shells	"	hard		1852	1997	145 "	1149"	
Coaly slate				1997	2007	10 "	1159"	
Slate				2007	2022	15 "	1174"	
1st salt sand				2022	2026	4 "	1178"	
Slate & shells		hard		2026	2092	66 "	1244"	
2nd salt sand				2092	2127	35 "	1279"	
Coaly slate				2127	2135	8 "	1287"	
shells				2135	2202	67 "	1354"	
3rd salt sand				2202	2262	60 "	1414"	
Shale				2262	2402	140 "	1554"	
Gas sand				2402	2427	25 "	1579"	
Slate				2427	2467	40 "	1619"	
Maxon				2467	2512	45 "	1664"	
Slate				2512	2521	9 "	1673"	
Slate				2521	2590	69 "	1742"	

1-31-35

X Big Lime Well was not shot at 1788 feet; well was shot at _____ feet.

Salt Fresh water at no water salt feet; fresh water at _____ feet.

Well was producing oil hole. dry

January 28th, 1935 Date Approved John M. Traxler et al Owner

NOTE: All bottom formations must be noted as indicated above and all key-rocks and oil and gas sands must be recorded under their proper geological names in the district as well as any local names commonly used in the district for such strata.
 Logs continued Steel line measure 1788 ft. top of Keener sand
 X Keener sand -white hard/ 2590 2626 36ft. 1778 Ft.
 Injun sand 2626 2692 66" 1844-bottom
 of hole - the driller's log does not correspond with the steel line measure which was 1890 feet at bottom of hole.

JAN 31 1935

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

PRELIMINARY DATA SHEET NO. 1

File No. _____

Well No. 1

John M. Traxler, et als Company of Enterprise,

_____ on the W. C. Butcher Farm

containing 100 acres. Location _____

Clay District, in Ritchie County, West Virginia

The surface of the above tract is owned in fee by W. C. Butcher

of Highland, West Virginia address, and the mineral rights are owned by

W. C. Butcher & W. P. Butcher of Highland, W.Va. & Bremen, Ohio

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit No. Rit-258 issued by the West Virginia Department of Mines, Oil and Gas Division

September 25th, 1934.

Elevation of surface at top of well, 848 feet Spirit Barometric.

The number of feet of the different sized casings used in the well.

10 feet _____ feet 13 inch size. Wood conductor.

1400 feet 6-5/8 size, csg. _____ feet _____ sized csg.

_____ feet _____ size, csg. _____ feet _____ sized csg.

_____ feet _____ size, csg. _____ feet _____ sized csg.

_____ packer of _____ size, set at _____

_____ packer of _____ size, set at _____

_____, in casing perforated at _____ feet to _____ feet.

_____, in casing perforated at _____ feet to _____ feet.

and slate

Coal was encountered at 1195 to 1205 feet, thick ness _____ inches, and at 1325 to 1333

feet; thickness _____ inches; and at _____ feet; thickness _____ inches.

Liners were used as follows: (Give details) none

January 28th, 1935 Date.

Approved John M. Traxler et al, Owner.

By John M. Traxler atty (TITLE)

JAN 31 1935



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

No Coal Operators

Mihlbauer & Tice

COAL OPERATOR OR COAL OWNER

NAME OF WELL OPERATOR

Box 76, Ellenboro, W. Va.

ADDRESS

COMPLETE ADDRESS

June 16, 19 52

COAL OPERATOR OR COAL OWNER

WELL TO BE ABANDONED

ADDRESS

CLAY District

Mihlbauer & Tice

RITCHIE

County

LEASE OR PROPERTY OWNER

Well No. 1

Box 76, Ellenboro, W. Va.

ADDRESS

W. C. Butcher

Farm

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence
**Will notify Inspector Harry Maze, 24 hours previous to the start
of operations.**

the work of plugging and abandoning said well on the _____ day of _____, 19 ____,
(which date shall not be less than five days after the day on which this notice so mailed is received,
or in due course should be received by the Department of Mines.)

This notice is given you in order that your respective representatives may be present at the
plugging and filling of said well. You are further notified that whether you are represented or not
represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said
well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the
reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the
above date.

Very truly yours,

Mihlbauer and Tice
B. E. Tice

Well Operator.



NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent
engineer, showing the district and county in which the tract of land is located, the name and acreage of same,
the names of the owners and adjacent tracts, and the location of the about to be abandoned well, determined
by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall
be submitted with this notice.

(Over)

RIT-258

PERMIT NUMBER

RIT-258-P

PROPOSED MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY RULES AND REGULATIONS)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

WORK ORDER

Well to be plugged and filled as follows:

- Total depth 1890'
- Fill with Red Clay from Bottom to 1785'
- Neat Cement 1785' to 1775'
- Crushed Stone 1775' to 1765' sealing off oil & Gas in Kenner Sand.
- Continue to fill with Red Clay to 1440' 40' below 6-5/8" casing.
- Neat Cement 1840' to 1830'
- Crushed Stone 1830' to 1820'
- Start to pull 6-5/8" casing.
- Continue to fill with Red Clay from 1820' to 1000'
- Neat Cement 1000' to 990'
- Crushed Stone 990' to 980'
- Red Clay 980' to 500'
- Neat Cement 500' to 490'
- Crushed Stone 490' to 480' sealing off Pittsburgh Coal Horizon
- Continue to fill with Red Clay to surface.
- Erect Monument or Marker, such as prescribed in Rules and Regulations

To the Department of Mines
Coal Owner or Operator,
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

W. G. Ditcher
W. G. Ditcher
Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this

30th day of June, 1952, 19

DEPARTMENT OF MINES
Oil and Gas Division

By: *C. H. Hall*

NOTE: This "work order" shall be filed in triplicate, one copy for the files of the Department of Mines; one to be approved or corrected and returned to the well operator as his authority for plugging said well; and one for the well inspector.