

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Corliss Ball No. 7 Operator Well No.: R3 - 4708500338

LOCATION: Elevation: 854' Quadrangle: Ellenboro 7.5

District: Clay County: Ritchie

Latitude: 278362.5 Feet South of _____ Deg. _____ Min. _____ Sec.

Longitude: 1524122.9 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

RECEIVED
Office Of Oil and Gas

JUL 28

WV Department of
Environmental Protection

Company Unknown - WVDEP Paid Plugging Contract Coal Operator None
601 57th St., SE or Owner _____
Charleston, WV 26304 _____

Agent Jason Harmon Coal Operator None
or Owner _____

Permit Issued Date 1/24/23

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Ritchie ss:

Tim Simmons and Tim Hicks being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of April, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
72 SKS of Class L CMT	2280'	1650'		
9 SKS of Class L CMT	1588'	1504'		
24 SKS of Class L CMT	1254'	1100'	830' of 5-3/16" csg	744' of 5-3/16" csg
55 SKS of Class L CMT	957'	600'		
150 SKS of Class L CMT	420'	unknown	490' of 6-5/8" csg	unknown
199 SKS of Class L CMT	190'	surface		

Description of monument: Monument was a piece of casing removed from well that had a 7" OD, 21' feet long and protrudes from surface 54" and that the work of plugging and filling said well was completed on the 21st day of April, 2023.

And further deponents saith not. Chris Veazey



Sworn and subscribe before me this 25th day of May, 2023

My commission expires: Sept. 18, 2021
Sandra L. Messer
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: OOG Inspector

09/08/2023