

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL  
(REQUIRED BY SECTION 2, CHAPTER 86, ACTS 1929)  
WEST VIRGINIA DEPARTMENT OF MINES  
OIL AND GAS SECTION

To THE DEPARTMENT OF MINES,  
Charleston, W. Va.

Same ✓  
COAL OPERATOR OR COAL OWNER  
Same ✓  
ADDRESS  
Same ✓  
COAL OPERATOR OR COAL OWNER  
Same ✓  
ADDRESS  
Same ✓  
COAL OPERATOR OR COAL OWNER  
Same ✓  
ADDRESS

*notice not required*

H.R. & W.G. Busch  
NAME OF WELL OPERATOR  
Brohard West Virginia  
COMPLETE ADDRESS  
August 20 1935  
PROPOSED LOCATION  
Murphy District  
Ritchie County  
Well No. One  
G.G. Goff Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated April 15, 1935, made by G.G. Goff and wife, to H.R. & W.G. Busch, and recorded on the 27 day of June 1935, in the office of the County Clerk for said County in Book 63, page 483.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten\* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above

named coal operators or coal owners at their above shown respective address.....day.... before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

H.R. & W.G. Busch  
WELL OPERATOR



Address of Well Operator }

Brohard Ritchie County  
West Virginia  
STREET  
CITY OR TOWN  
STATE

\*Section 3 . . . . . If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

375



WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

PRELIMINARY DATA SHEET NO. 1

File No. RIT 375

Well No. One

Dry Run Oil & Gas Co Company of Brohard

West Virginia on the C. G. Goff & Wife Farm

containing 1.85 acres. Location Water of Dry Run

Murphy District, in Ritchie County, West Virginia

The surface of the above tract is owned in fee by C. G. Goff and Wife

of Burnt House Trg. address, and the mineral rights are owned by

C. G. Goff & Wife of Burnt House Trg.

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit No. Rit 375 issued by the West Virginia Department of Mines, Oil and Gas Division

September 7th 1935

Elevation of surface at top of well, 1096 Spirit Barometric.

The number of feet of the different sized casings used in the well.

\_\_\_\_\_ feet 7ft conductor 13" size. Wood conductor.

137 feet 10" inch size, csg. \_\_\_\_\_ feet \_\_\_\_\_ sized csg.

920 feet 8 1/4" inch size, csg. \_\_\_\_\_ feet \_\_\_\_\_ sized csg.

\_\_\_\_\_ feet \_\_\_\_\_ size, csg. \_\_\_\_\_ feet \_\_\_\_\_ sized csg.

\_\_\_\_\_ packer of \_\_\_\_\_ size, set at \_\_\_\_\_

\_\_\_\_\_ packer of \_\_\_\_\_ size, set at \_\_\_\_\_

\_\_\_\_\_, in casing perforated at \_\_\_\_\_ feet to \_\_\_\_\_ feet.

\_\_\_\_\_, in casing perforated at \_\_\_\_\_ feet to \_\_\_\_\_ feet.

Coal was encountered at no coal found feet, thickness \_\_\_\_\_ inches, and at \_\_\_\_\_

feet; thickness \_\_\_\_\_ inches; and at \_\_\_\_\_ feet; thickness \_\_\_\_\_ inches.

Liners were used as follows: (Give details) Hole reduced for 6 7/8" pipe

at 1774 ft. No pipe run after

8 1/4" pipe was set

Mar. 26 1936

Date. \_\_\_\_\_ Approved H. R. Busch, Owner.

By H. R. Busch (TITLE)





Rt - 375

OIL OR GAS WELL Dry Hole

Dry Run Oil & Gas Co. Company  
Brohard Hoq. Address

COMPLETION DATA SHEET  
No. 2  
FORMATION RECORD

WELL No. One FARM B. G. Goff's wife

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Soil	Red			0	7	7		
Sand	White			7	40	33		
Slate	Black			40	60	20		
Sand	White			60	137	77		
White slate	White			137	160	23	137	-10"
Red Rock	Red		137 Water	160	250	90		
Sand shell	White			250	275	25		
Red Rock	Red			275	605	330		
Lim shell	White			605	715	110		
Slate	White			715	740	25		
Red Rock	Red			740	880	140		
Blue shale	Blue			880	920	40		-920'-8 1/4"
Big Dunkard	White			920	940	20		
White slate	White			940	950	10		
Sand	White			950	1155	200		
White slate	White			1155	1160	5		
Slate black	Black			1160	1245	85		
W. salt sand	White			1245	1280	35		
Slate black	Black			1280	1325	45		
Large	White			1325	1326	1		
White slate	White			1326	1455	129		
Shale	Black			1455	1475	20		
Mason	White			1475	1534	59		
Black slate	Black			1534	1580	46		
Lim shell	White & Red			1580	1600	20		
Black slate	Black			1600	1648	48		
Sand shell	White			1648	1685	37		
Little lime	White			1685	1720	35		
Genev. cone	Black			1720	1728	8		
Big Lim	Black			1728	1732	4		
Kemper sand	White		light show	1732	1735	3		
Trin sand	Dark		Gas	1735	1800	65		
Trin sand	Black		No other	1800	1830	30		
Shale	Black		oil or	1830	1863	33		
Shale	Black		Gas found	1863	1880	17		
Black lime	Black			1880	1932	52		
Black lime	Black			1932	2000	68		
Black lime	Black			2000	2080	80		
Black lime	Black			2080	2215	135		
Black lime	Black			2215	2218	3		

shot  
Well was not shot at Not shot feet; well was shot at Same feet.


Salt  
Fresh water at fresh water 137 feet; fresh water at Same feet.

producing  
Well was dry hole. dry hole.

Mar 26 1936  
Date

Approved H. G. Busch  
Owner

NOTE: All bottom formations must be noted as indicated above and all key-rocks and oil and gas sands must be recorded under their proper geological names in the district as well as any local names commonly used in the district for such strata.









NO affidavit

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

Rit-375

To THE DEPARTMENT OF MINES,  
Charleston, W. Va.

COAL OPERATOR OR COAL OWNER

W. R. and W. G. Busch

NAME OF WELL OPERATOR

ADDRESS

Brohard, West Virginia

COMPLETE ADDRESS

COAL OPERATOR OR COAL OWNER

March 30, 19.36

19.36

WELL TO BE ABANDONED

ADDRESS

Murphy

District

LEASE OR PROPERTY OWNER

Ritchie

County

ADDRESS

Well No. 1

C. G. Goff

Farm

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence the work of plugging and abandoning said well on the 6th day of April, 19.36, (which date shall not be less than five days after the day on which this notice so mailed is received, or in due course should be received by the Department of Mines).

This notice is given you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,

W. R. and W. G. Busch

Well Operator.

NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent engineer, showing the district and county in which the tract of land is located, the name and acreage of same, the names of the owners of adjacent tracts, and the location of the about to be abandoned well, determined by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted with this notice.

(Over)



**PROPOSED MANNER OF PLUGGING AND FILLING WELL,**

(REQUIRED BY RULES AND REGULATIONS)

**WEST VIRGINIA DEPARTMENT OF MINES**

**OIL AND GAS DIVISION**

**WORK ORDER**

Well to be plugged and filled as follows:

WORK ORDER SUPPLIED BY THE DEPARTMENT OF MINES:

Bottom of hole 2250'

Fill with clay from bottom 2250' to 1843' - 20' above the Squaw Sand.

Drive wood plug from 1843' to 1840'

Continue to fill with clay from 1840' to 1708' a point 20' above the pencil cave in the Little Lime.

Drive wood plug 1708' to 1705'

Cement from 1705' to 1695' sealing the hole completely.

SET A PERMANENT BRIDGE AT 1610' - 30' below the Maxon Sand.

1 sack of cement on top of bridge

Fill with red clay from 1610' to 1140' - 20' above the First Salt Sand.

Drive wood plug from 1140' to 1137'

Cement from 1137' to 1127' sealing the hole above the Salt Sand.

SET A PERMANENT BRIDGE AT 950' - 30' below the Big Dunkard Sand and 8-1/4" casing

1 sack of cement on top of bridge

Fill with red clay from 950' to 920' and PULL 8-1/4" casing

Continue to fill with red clay from 920' to 860' - 20' above the Big Dunkard

Drive wood plug from 860' to 857'

Cement from 857' to 847' sealing the hole completely.

SET A PERMANENT BRIDGE AT 170' - 33' below the 10" casing

1 sack of cement on top of bridge

Fill with red clay from 170' to 137' and PULL 10" casing

Continue to fill with red clay from 137' to the surface and

Erect a marker such as is described in Rule 18, 1931 Regulations.

To the Department of Mines,  
Coal Owner or Operator,  
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this 30th day

of March 6, 1931

DEPARTMENT OF MINES  
Oil and Gas Division

By: \_\_\_\_\_

NOTE: This "work order" must be filed in duplicate, one copy for the files of the Department of Mines and the other to be approved or corrected and returned to the well operator as his authority for plugging said well.