

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

(REQUIRED BY SECTION 2, CHAPTER 86, ACTS 1929)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS SECTION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

COAL OPERATOR OR COAL OWNER

ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

OWNER OF MINERAL RIGHTS

ADDRESS

NAME OF WELL OPERATOR

COMPLETE ADDRESS

PROPOSED LOCATION

District

County

Well No.

Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated.....

August 13, 1934, made by Ida E. Jones, hrs, to

S. M. Summers & G. L. Conrad, and recorded on the 9 day

of January 1935, in the office of the County Clerk for said County in

Book 63, page 156.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above

named coal operators or coal owners at their above shown respective address.....day before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

S. M. Summers
WELL OPERATOR

G. L. Conrad.
STREET

Berea.
CITY OR TOWN

W. Va.
STATE

Address of Well Operator }



*Section 3 If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

THE NATIONAL BUREAU OF FIRE UNDERWRITERS
1917

Wm. Summers

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

Wm. Summers

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

1917

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

PRELIMINARY DATA SHEET NO. 1

File No. _____

Well No. 2

Company of S. M. Summers &

G. L. Conrad on the Ida Jones Heirs Farm

containing 18-147rds acres. Location _____

Union District, in Ritchie County, West Virginia

The surface of the above tract is owned in fee by Ida Jones Heirs

of Freed, W. Va. address, and the mineral rights are owned by Ida Jones Heir of Freed, W. Va. and of S. A. Smith of Clarksburg, W. Va.

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit No. 392 issued by the West Virginia Department of Mines, Oil and Gas Division October 31, 1935.

Elevation of surface at top of well, 977.9 ^{Spirit} Barometric.

The number of feet of the different sized casings used in the well.

<u>13"</u>	feet	<u>16</u>	size.	<u>Wood</u>	conductor.
<u>350</u>	feet	<u>10"</u>	size, csg.	<u>feet</u>	sized csg.
<u>1147</u>	feet	<u>8 1/4</u>	size, csg.	<u>feet</u>	sized csg.
<u>1722</u>	feet	<u>6 5/8</u>	size, csg.	<u>feet</u>	sized csg.

_____ packer of _____ size, set at _____

_____ packer of _____ size, set at _____

_____, in casing perforated at _____ feet to _____ feet.

_____, in casing perforated at _____ feet to _____ feet.

Coal was encountered at none feet, thickness _____ inches, and at _____ feet; thickness _____ inches; and at _____ feet; thickness _____ inches.

Liners were used as follows: (Give details) _____

December 17, 1935

Date.

Approved S. M. Summers & G. L. Conrad, Owner.

By S. M. Summers & G. L. Conrad
(TITLE)



085-392

S. M. Summers & G. L. Conrad Company

COMPLETION DATA SHEET

No. 2

Berea, W. Va. Address

FORMATION RECORD

Well No. 2

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Big Dunkard	Blue	Hard		1140	1175	35		
Gas Sand	White	"		1210	1302	92		
First Salt Sand	White	"		1355	1490	135		
Second Salt Sand	White	"		1505	1546	41		
Third Salt Sand	White	"		1714	1785	71		
Maxon Sand	White	"		1792	1884	92		
Big Lime	Gray	"		1930	2000	70		
Injun Sand	Dark	"		2000	2084	84		
			Smell Gas 1841					
			Smell Gas 2074					
			Show Oil 1987					
							2125	

Well was ~~not~~ shot at 1888 to 1898 feet; well was shot at _____ feet.

Salt Fresh water at none feet; salt fresh water at none feet.


Well was ~~producing~~ hole. dry

December 17, 1935 Date

Approved S. M. Summers & G. L. Conrad

S. M. Summers & G. L. Conrad Owner

NOTE: All bottom formations must be noted as indicated above and all key-rocks and oil and gas sands must be recorded under their proper geological names in the district as well as any local names commonly used in the district for such strata.



Rit-392-B

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

.....
COAL OPERATOR OR COAL OWNER

W. A. Bickerstaff
NAME OF WELL OPERATOR

.....
ADDRESS

Harrisville, West Virginia
COMPLETE ADDRESS

.....
COAL OPERATOR OR COAL OWNER

February 19, 1936

WELL TO BE ABANDONED

.....
ADDRESS

Union District

Ida E. Jones
LEASE OR PROPERTY OWNER

Ritchie County

Berea, West Virginia
ADDRESS

Well No. 2

Ida E. Jones Heirs Farm

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence the work of plugging and abandoning said well on the 24th day of February, 1936, (which date shall not be less than five days after the day on which this notice so mailed is received, or in due course should be received by the Department of Mines).

This notice is given you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,

W. A. BICKERSTAFF
Well Operator.

NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent engineer, showing the district and county in which the tract of land is located, the name and acreage of same, the names of the owners of adjacent tracts, and the location of the about to be abandoned well, determined by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted with this notice.

(Over)

PROPOSED MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY RULES AND REGULATIONS)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

WORK ORDER

Well to be plugged and filled as follows:

WORK ORDER SUPPLIED BY THE DEPARTMENT OF MINES:

Bottom of well 2125'

Fill with red clay from bottom 2125' to 1980' - 20' above the Big Injun
Drive wood plug from 1980' to 1977'
Cement from 1977' to 1967' sealing the Big Injun

Continue to fill with red clay from 1967' to 1772' - 20' above the Maxton
(OR SET A PERMANENT BRIDGE AT 1868' - 20' above the SHOT HOLE) and
Fill with clay to 1772'

Drive wood plug from 1772' to 1769'

Cement from 1769' to 1759' sealing the Maxton Sand, and bottom of Third Salt Sand

PULL 6-5/8" casing

SET A PERMANENT BRIDGE AT 1520' - 30' below the First Salt Sand.

1 sack of cement (mixed with water only) on top of bridge

Fill with red clay from 1520' to 1335' - 20' above the First Salt Sand.

Drive wood plug from 1335' to 1332'

Cement from 1332' to 1322' sealing the Salt Sands.

SET A PERMANENT BRIDGE AT 1205' - 30' below the Big Dunkard Sand.

1 sack of neat cement on top of bridge

Fill with red clay from 1205' to 1147' PULL 8-1/4" casing and

Continue to fill with red clay to 1120' - 20' above the Big Dunkard Sand.

Drive wood plug from 1120' to 1117'

Cement from 1117' to 1107' sealing the hole completely

SET A PERMANENT BRIDGE AT 380' - 30' below the 10" casing

1 sack of neat cement on top of bridge

Fill with red clay from 380' to surface and

Erect a marker such as is described in Rule 18, 1931 Regulations

To the Department of Mines,
Coal Owner or Operator,
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this 19th day

of February, 1936

DEPARTMENT OF MINES
Oil and Gas Division

By: _____

NOTE: This "work order" must be filed in duplicate, one copy for the files of the Department of Mines and the other to be approved or corrected and returned to the well operator as his authority for plugging said well.

COPY TO INSPECTOR COURTNEY.

AFFIDAVIT IN TRIPLICATE TO TIME AND MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY SECTION 9, CHAPTER 86, ACTS 1929)

WEST VIRGINIA DEPARTMENT OF MINES OIL AND GAS SECTION

W A Bickerstaff

Ida E. Jones Heirs

COAL OPERATOR

Berea, W. Va.

ADDRESS

S. M. Summers & G. L. Conrad

NAME OF WELL OPERATOR

Berea, W. Va.

COMPLETE ADDRESS

June 24, 1936

WELL AND LOCATION

Union District

Ritchie County

Well No. 2

Ida E. Jones heirs Farm

AFFIDAVIT TO BE MADE IN TRIPLICATE. ONE COPY TO BE MAILED BY REGISTERED MAIL TO THE DEPARTMENT, ONE COPY TO BE RETAINED BY THE WELL OPERATOR AND THE THIRD COPY (AND EXTRA COPIES IF REQUIRED) TO BE MAILED TO EACH COAL OPERATOR ABOVE NAMED AT THEIR RESPECTIVE ADDRESSES.

AFFIDAVIT

STATE OF WEST VIRGINIA,

COUNTY OF Ritchie

} ss:

W. A. Bickerstaff, Driller and Leland Summers, Tool Dresser

being first duly sworn according to law depose and say that they are experienced in the work of plugging

and filling oil and gas wells and were employed by S. M. Summers & G. L. Conrad, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the

day of June, 1936, and that the well was plugged and filled in the following manner:

Manner in which sand was plugged: Filled with red clay to 1980', wood plug drove 1980, cement 1977 to 1967, filled with clay to 1772', drove wood plug 1769, cement from 1769 to 1759', permanent bridge 1520, 1 sack cement filled with clay to 1335, wood plug 1332, cement 1332-1322, bridge 1205, 1 sack cement filled with clay to 1147, pulled 8 1/2" casing, filled with clay to 1120, wood plug 1117 cement to 1107, bridge 380, 1 sack cement filled with clay to surface.

Manner in which coal was plugged: No coal found.

Description of monument: 6" casing cemented in hole and filled with cement.

(THE ABOVE DESCRIPTIONS MUST BE IN DETAIL AND IN ACCORDANCE WITH THE PROVISIONS OF SECTION 10, OIL AND GAS ACT OF 1929.)


and that the work of plugging and filling said well was completed on the day of June, 1936

And further deponents saith not.

Sworn to and subscribed before me this 21st day of July, 1936

WA Bickerstaff
Leland Summers
John E. Lawther
Notary Public.

My Commission expires: April 7, 1937



Ritchie 392-P

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS SECTION
AFFIDAVIT IN TRIPPLICATE TO TIME AND MANNER OF
PLUGGING AND FILLING WELL
(REQUIRED BY SECTION 5, CHAPTER 20, ACTS 1920)

NAME OF WELL OPERATOR _____
 COMPLETE ADDRESS _____
 WELL AND LOCATION _____
 DISTRICT _____
 COUNTY _____
 WELL NO. _____
 FARM _____

THE ABOVE INFORMATION WAS OBTAINED FROM THE RECORDS OF THE DEPARTMENT OF MINES AND GEOLOGY AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

AFFIDAVIT

STATE OF WEST VIRGINIA

ss:

_____ and _____ being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by _____ well operator and participated in the work of plugging and filling the above well, that said work was commenced on the _____ day of _____, 19____, and that the well was plugged and filled in the following manner:

_____ manner in which coal was plugged: _____

Description of monument:

_____ and that the work of plugging and filling said well was completed on the _____ day of _____, 19____.

And further deponents said not _____

Sworn to and subscribed before me this _____ day of _____, 19____.

Notary Public _____

My Commission expires: _____