

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

(REQUIRED BY SECTION 2, CHAPTER 86, ACTS 1929)

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS SECTION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

none
COAL OPERATOR OR COAL OWNER

ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

J.R. Hayhurst & B.F. Gilmore
NAME OF WELL OPERATOR

Pennsboro W. Va
COMPLETE ADDRESS

October 31st 193*5*
PROPOSED LOCATION

Clay District

Ritchie County

Well No. *1*

Warren S. Hayhurst & Florence Hayhurst
Farm
Pennsboro, W. Va

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for

oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated *May 10th 1935*

made by Belle Hayhurst & husband Warren S. Hayhurst & wife
Florence Hayhurst to J.R. Hayhurst & B.F. Gilmore
and recorded on the.....day

of....., in the office of the County Clerk for said County in

Book....., page.....

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above

named coal operators or coal owners at their above shown respective address.....day.... before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

J.R. Hayhurst
B.F. Gilmore
WELL OPERATOR

Address
of
Well Operator }

Pennsboro
STREET
CITY OR TOWN

W. Va
STATE



*Section 3 If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

PRELIMINARY DATA SHEET NO. 1

File No. _____

Well No. 1

J. R. Hayhurst & B. F. Gilmore Company of Pennsboro, W. Va.

on the Warren S. & Florence Hayhurst farm

containing 63 acres. Location _____

Clay District, in Ritchie County, West Virginia

The surface of the above tract is owned in fee by Warren S. & Florence Hayhurst,

of Pennsboro, RFD. #3, W. Va. address, and the mineral rights are owned by

same parties, of same address,

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit

No. 396-B issued by the West Virginia Department of Mines, Oil and Gas Division

Nov. 14, 1935

Elevation of surface at top of well, 865 ^{Spirit} Barometric.

The number of feet of the different sized casings used in the well.

300 feet 10" size. Wood conductor.

300 feet 10" size, csg. 101 feet sized csg.

1012 feet 8-1/4" size, csg. _____ feet sized csg.

_____ feet _____ size, csg. _____ feet sized csg.

_____ packer of _____ size, set at _____

_____ packer of _____ size, set at _____

_____, in casing perforated at _____ feet to _____ feet.

_____, in casing perforated at _____ feet to _____ feet.

Coal was encountered at No feet, thick ness _____ inches, and at _____

feet; thickness _____ inches; and at _____ feet; thickness _____ inches.

Liners were used as follows: (Give details) No

Jan. 16, 1936

Date.

Approved J. R. Hayhurst & B. F. Gilmore, Owner.

By B. F. Gilmore

(TITLE)

1-17-36



OIL OR GAS WELL

Dry

J. R. Hayhurst and B. F. Gilmore

COMPLETION DATA SHEET

No. 2

FORMATION RECORD

Pennsboro, W. Va. Address

WELL No. 1 *Rit-396* FARM *Warren S. & Florence Hayhurst.*

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks	
Little Dunkard,				820	830	10		<i>306' - 10"</i>	
Slate & Shell,	<i>pink</i>			830	935	105			
Big Dunkard,				935	950	15			
Slate & Shell				950	1120	170		<i>1012' - 8 1/4"</i>	
1st Salt				1120	1220	100			
Slate & Shell				1220	1300	80			
2nd salt				1300	1350	50			
Slate break,				1350	1370	30			
3d salt				1370	1605	235			
Slate				1605	1660	55			
Little Lime				1660	1690	30			
Pencil Cave				1690	1692	2			
Big Lime,				1692	1766	74			
Keener Sand,				1766	1778	12			
Lime & Slate,				1778	1784	6			
Injun				1784	1890	106			
Squaw				1890	1907	17			
Gas at				1844	1859	15			
Gas tested 4/10 water in 1" opening=							23,640 ft.	1932	

Well was ~~not~~ shot at *1844 to 1859* feet; well was shot at _____ feet.


Salt ~~fresh~~ water at *1200* feet; salt fresh water at _____ feet.

Well was ~~productive~~ hole.
 dry

January 16 - 36
Date

Approved *J. R. Hayhurst and B. F. Gilmore*
Owner

NOTE: All bottom formations must be noted as indicated above and all key-rocks and oil and gas sands must be recorded under their proper geological names in the district as well as any local names commonly used in the district for such strata.



396-B

no affidavit

FORM G-9

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

J. R. Hayhurst & B. F. Gilmore,

NAME OF WELL OPERATOR

Pennsboro, W. Va.

COMPLETE ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

Soon as possible, 19

WELL TO BE ABANDONED

Clay District

Ritchie County

COAL OPERATOR OR COAL OWNER

ADDRESS

LEASE OR PROPERTY OWNER

ADDRESS

Well No. 1

Warren S. & Florence, Hayhurst Farm

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence the work of plugging and abandoning said well on the 27th day of Jan., 1936, (which date shall not be less than five days after the day on which this notice so mailed is received, or in due course should be received by the Department of Mines).

This notice is given you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,

Well Operator.

NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent engineer, showing the district and county in which the tract of land is located, the name and acreage of same, the names of the owners of adjacent tracts, and the location of the about to be abandoned well, determined by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted with this notice.

(Over)



1-17-36

PROPOSED MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY RULES AND REGULATIONS)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

WORK ORDER

Well to be plugged and filled as follows:

According to the requirements of the Dept. of Mines.

WORK ORDER SUPPLIED BY THE DEPARTMENT OF MINES:

Bottom of well 1932'

Fill with clay from 1932' to 1764' - 20' above the Big Injun

Drive wood plug from 1764' to 1761'

Cement from 1761' to 1751' sealing the Squaw and Big Injun

Continue to fill with clay from 1751' to 1100' - 20' above the Salt Sands.

Drive wood plug from 1100' to 1097'

Cement from 1097' to 1087'

PULL 8-1/4" casing set at 1012' and

SET A PERMANENT BRIDGE AT 980' - 30' below the Big Dunkard

~~Drive wood plug from 980' to 977'~~

~~Cement from 977' to 967' sealing the Big Dunkard Sand~~

Continue to fill with clay from 980' to 915' - 20' above the Big Dunkard

Drive wood plug from 915' to 912'

Cement from 912' to 902' sealing the Big Dunkard Sand.

Continue to fill with clay from 902' to 800' - 20' above the Little Dunkard

Cement from 800' to 790' sealing the hole completely

SET A PERMANENT BRIDGE AT 330' - 30' below the 10" casing

Fill with clay from 330' to 320'

Drive wood plug from 320' to 317'

PULL 10" casing and

Fill with clay to the surface

Erect a marker such as is described in Rule 18, 1931 Regulations.

To the Department of Mines,
Coal Owner or Operator,
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

J. R. Hayhurst
Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this 18th day of January, 1936.

DEPARTMENT OF MINES
Oil and Gas Division

By: _____

NOTE: This "work order" must be filed in duplicate, one copy for the files of the Department of Mines and the other to be approved or corrected and returned to the well operator as his authority for plugging said well.