

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PARKS, JOE Operator Well No.: 23

LOCATION: Elevation: 936' Quadrangle: Schultz
District: Grant County: Ritchie
Latitude: 7633' Feet South of 39 Deg. 17 Min. 30 Sec.
Longitude: 5220' Feet West of 81 Deg. 12 Min. 30 Sec.

Well Type: OIL GAS

Company UNKNOWN - DEP PAID PLUGGING CONTRACT WVDEP
601 57TH STREET
CHARLESTON WV 25304

Coal Operator Haessly Land & Timber, LLC
or **Owner** 25 Sheets Run Road, Marietta OH 45750
EIGG Land Limited

RECEIVED
Office of Oil and Gas

Agent H. JASON HARMON
Permit Issued Date 05-08-2023

Coal Operator P.O. Box 31, New Philadelphia OH 44663
or **Owner** Orma M. Wilson Johnson Trust
3315 Higley Road, Rocky River OH 44116

JUN 29 2023

WV Department of
Environmental Protection

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of LEWIS ss:

MICHAEL D. GOODWIN, JR. and KEVIN QUESENBERRY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18TH day of MAY, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
PULL RODS	1875	SURFACE	5/8" RODS	0
PULL TBG	1900	SURFACE	2" TBG	0
BH PLUG CEMENT	1900	1700	0	1779'; 5 3/16" CSG
BOND LOG	1700	SURFACE	0	1779'; 5 3/16" CSG
PERF 5 3/16" CSG	1485	426'	*10 SHOTS @ 1485; 4 SHOTS AT ALL OTHER INTERVALS	1485 1357; 1250; 1140; 1032; 923; 838; 734; 620; 538; 426
CEMENT	1700	400	PULL 390'; 5 3/16" CSG	1389'
SURFACE PLUG CEMENT	400	0		

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 21ST day of JUNE, 2023.


And further deponents saith not. [Signatures]

Sworn and subscribe before me this 22ND day of JUNE, 2023

My commission expires: OCTOBER 10, 2024

[Signature]
Notary Public

Stephen Mccoy Digitally signed by Stephen Mccoy
Date: 2023.06.23 07:53:30 -04'00'



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

06/30/2023