

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

~~OFFER~~
~~6/23~~

6/23

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Vanhoesen Operator Well No.: R3 - 4708501554

LOCATION: Elevation: 793' Quadrangle: Shultz 7.5'
District: Grant County: Ritchie
Latitude: 4347615 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: 484958 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company Unknown - WVDEP Paid Plugging Contract Coal Operator None
601 57th St., SE or Owner _____
Charleston, WV 26304 _____

Agent Jason Harmon Coal Operator None
or Owner _____
Permit Issued Date 3/6/2023 _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Ritchie ss:

Tim Simmons and Chaz Simmons being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 5th day of May, 2023, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
25.5 SKS of Class L CMT	1450'	1723'	1,469' of 2 3/8"	0' of 2 3/8"
14 SKS of Class L CMT	1318'	1450'	255' of 1 1/2"	0' of 1 1/2"
26 SKS of Class L CMT	1112'	1318'	367' of 5 3/16"	Unknown amount of 5 3/16"
74 SKS of Class L CMT	562'	1112'		
160 SKS of Class L CMT	80'	375'		
50 SKS of Class L CMT	Surface	80'		

Description of monument: 7" OD casing anchored 16' below surface and protruding 72" above surface with API welded on the monument. and that the work of plugging and filling said well was completed on the 12th day of June, 2023.

And further deponents saith not. Austin Sutler

Justin Smith

Sworn and subscribe before me this 21st day of June, 2023



My commission expires: Sept. 18, 2027 Sandra L. Messer
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: OOG Inspector 09/08/2023