

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J. L. Mullenax Operator Well No.: 5

LOCATION: Elevation: 886' Quadrangle: Cairo  
District: Grant County: Ritchie  
Latitude: 39.1357520 Feet South of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.  
Longitude: -81.2022570 Feet West of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company VIRCO Coal Operator N/A  
1300 Fort Pierpont Drive. Suite 201 or Owner \_\_\_\_\_  
Morgantown, WV. 26508 \_\_\_\_\_  
Agent Brittany Woody Coal Operator N/A  
or Owner \_\_\_\_\_  
Permit Issued Date 06/29/2021 \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Ritchie ss:

Next LVL Energy and \_\_\_\_\_ being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 8th day of August, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Collapsed Hole / Fill	1950	1550	N/A	Tagged at 1463' & spud to 1550' .DEP Insp good to set plugs from 1550'.
Class A CMT	1540	975	N/A	6-5/8" - 1386'
Class A CMT	680	554	N/A	Perf 6-5/8" @ 600'-590',500'-490',400'-390',300'-290',200'-190',125'-115'
Class A CMT	400	300	N/A	Above perfs are 10', 10 shot - 3/8" shot as per direction of WV DEP Insp
Class A CMT	150	0	N/A	
Class A CMT Grout 6-5/8" x Wellbore Ann	20	0		
*6" Gel Spacer set between CMT plugs*				

Description of monument: 6" OD pipe raised 36" above ground with well info posted and that the work of plugging and filling said well was completed on the 27th day of August, 2021.

And further deponents saith not. Theresa N. Comisso



Sworn and subscribe before me this 18 day of May, 2022

My commission expires: 6/17/2026  
Laura A Cade  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Douglas Newlon Title: Oil and Gas Inspector Supervisor 06/03/2022