

WR-38
DATE 01 - 16 - 2013

API # 47-085-3941 P

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Ann Exline Revocable Trust
LOCATION: Elevation: 839'
District: Union
Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.
Operator Well No.: WV 652821
Quadrangle: Pullman
County: Ritchie

Well Type: OIL X GAS XXXX

Company: EQT Production Company
1710 Pennsylvania Ave
Charleston, WV 26302
Coal Operator or owner NA

Agent: Rex C. Ray

Coal Lessee NA
With declaration JUL 29 2013

Permit Issued Date: 08/24/2011

AFFIDAVIT

WV Department of
Environmental Protection


STATE OF WEST VIRGINIA,
County of Ritchie ss:

Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and David Cowan Oil and Gas Inspector representing the Director, say that said work was commenced on the 9th day of January, 2013 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED		LEFT
Cement	1500'	1300'	Rods	0	0
Cement	1160'	950'	2 3/8"	1506'	474
Cement	850'	650'	5 1/2"	84'	0
Cement	650'	500'	7"	506'	1257'
Cement	495'	400'			
Cement	285'	0'	8" & 10" Pulled in		drilling operations
Cement	50'	0'			
Cement					

6 % Gel between each plug.
Tagged Plug @ 1277'; 942'; 650'; 495'; 50'; Shot 2 3/8" @ 1506"; Shot 7" @ 1004"; 1 time; Shot 7" @ 806"; 1 time; Shot 7" @ 701"; 1 time; Shot 7" @ 609"; 1 time; Shot 7" @ 506"; Free.

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 17th day of January, 2013.



David Cowan
24th day of January, 2013

David Cowan

Notary Public

Oil and Gas Inspector

David Cowan

08/02/2013