

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Goff, FP – Estate & Martha Operator Well No.: WV 655356 (Bird 1266)
 LOCATION: Elevation: 807' Quadrangle: Burnt House
 District: Union County: Ritchie
 Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
 Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Well Type: OIL X GAS XXXX

Company: EQT Production Company Coal Operator NA
1710 Pennsylvania Avenue or owner
Charleston, WV 25302

Agent: John Damato Coal Lessee NA RECEIVED
 With declaration Office of Oil & Gas

Permit Issued Date: 10/14/2011

AFFIDAVIT

OCT 22 2013

STATE OF WEST VIRGINIA,
County of Ritchie ss:


WV Department of
Environmental Protection

Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and David Cowan Oil and Gas Inspector representing the Director, say that said work was commenced on the 29 day of July and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	2089'	1980'	2 3/8 2119'	0'
Cement	1726'	1590'	5 1/2" 1676'	410'
Cement	1053'	950'	7" 876'	764'
Cement	950'	814'	8" 0	874'
Cement	495'	392'		
Cement	250'	0'		
Cement				
Cement				
6 % Gel Between Each Plug				
Shot 5 1/2" @ 1676' ; 1 time; Free; Shot 7" @ 1003'; 1 Time; 876'; 1 time; Free. Shot 8" @ 798'; 1 time; 204'; 1 Time; Tagged plug @ 1985'; 950'; 798;				

Description of monument: 7 inch casing – 8 ft long with API# welded on it and that the work of plugging and filling said well was completed on the 6th day of August, 2013.
And further deponents saith not.

Sworn and subscribe before me this 6th day of August, 2013



Jason Meadows
Mildred L. Casto
 Notary Public
8-19-13
 10/25/2013