

Rit - 315-A

Union District, Ritchie County, W. Va.

By Hope Construction &amp; Refining Co., Clarksburg, W. Va.

On 454 $\frac{1}{2}$  acres, on South Fork of Hughes River.

Elevation, 972' L.

Drilling completed April 13, 1907.

Shot in Big Injun Sand in 1907, 1913, and 1916.

10" casing, 554' (pulled); 8 $\frac{1}{2}$ ", 1107'; 6 $\frac{3}{8}$ ", 1871'; 2" tubing, 1966'.

Coal was encountered at 600'.

Oil well. Abandonment reported to Dept. of Mines June 29, 1937.

Record to RCT from D. G. Courtney 2-1-38.

	Top.	Bottom.
Coal	600	
Little Dunkard Sand	900	940
Big Dunkard Sand	1040	1060
First Salt Sand	1200	1280
Second Salt Sand	1320	1350
Third Salt Sand	1625	1655
Maxton Sand	1765	1805
Big Lime	1875	1922
Big Injun Sand (gas, 1943-1958'; oil, 1950-1958')	1922	
Total depth		1966

Union District, Fitchie County, W. Va.

By Hope Construction & Refining Co., Clarksburg, W. Va.

On 454½ acres, on South Fork of Hughes River.

Elevation, 972' L.

Drilling completed April 13, 1907.

Shot in Big Injun Sand in 1907, 1913, and 1916.

10" casing, 554' (pulled); 8½", 1107'; 6½", 1871'; 2" tubing, 1966'.

Coal was encountered at 600'.

Oil well. Abandonment reported to Dept. of Mines June 29, 1937.

Record to RCT from D. G. Courtney 2-1-38.

	Top.	Bottom.
Coal	600	
Little Dunkard Sand	900 -	940
Big Dunkard Sand	1040 -	1060
First Salt Sand	1200 -	1280
Second Salt Sand	1320 -	1350
Third Salt Sand	1625 -	1655
Marion Sand	1765 -	1805
Big Line	1875 -	1922
Big Injun Sand (gas, 1943-1958'; oil, 1950-1958')	1922	
Total depth		1966

WEST VIRGINIA DEPARTMENT OF MINES  
OIL AND GAS DIVISION

(1107) **407**

WELL RECORD

Oil

Permit No. **RIF-315-A**


Oil or Gas Well (Kind)

Company **Rope Construction & Refining Company**  
 Address **Clarksburg, W. Va.,**  
**G. M. Ireland** Acres **454 1/2**  
 Location (waters) **South Fork Hughes River**  
 Well No. **5046** Elev. **972**  
 District **Union** County **Ritchie**  
 The surface of tract is owned in fee by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Mineral rights are owned by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Drilling commenced **No record**  
 Drilling completed **April 13, 1907**  
 Date shot **1907-1913, 1916** Depth of shot **In Injun**  
 Open Flow /10ths Water in \_\_\_\_\_ Inch  
 /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
 Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	<b>554</b>	<b>None</b>	Size of
8 1/4	<b>1107</b>	<b>1107</b>	
6 5/8	<b>1871</b>	<b>1871</b>	Depth set
5 3/16			
3			Perf. top
2	<b>1966</b>	<b>1966</b>	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. FT. \_\_\_\_\_ Date \_\_\_\_\_  
 COAL WAS ENCOUNTERED AT **600** FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Coal			600				
Little Dunkard Sand			900	940			
Big Dunkard Sand			1040	1060			
First Salt Sand			1200	1250			
Second Salt Sand			1380	1360			
Third Salt Sand			1625	1655			
Maxon Sand			1765	1805			
Big Lime			1875	1922			
Big Injun			1922		Gas Oil	1943-1958 1950-1958	
Total Depth			1966				



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date 6/29/37, 19...

APPROVED *W.C.B.C.*, Owner

By *C.A. Reed*  
(Title) asst. General Supt