



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

New Martinsville SC

WELL RECORD

Permit No. TYL 218.-

Oil or Gas Well Both
(KIND)

Company Glenn F. McBurney
Address Box 114-Sistersville, W.Va.
Farm Daisy W. Mercer Acres 126
Location (waters) Ten Mile
Well No. 1 Elev. 800
District Ellsworth County Tyler
The surface of tract is owned in fee by Daisy W. Mercer
R.F.D # 2. New Martinsville, W.Va.
Mineral rights are owned by Glenn F. McBurney
Box 114-Sistersville, West Virginia.
Drilling commenced February 7th, 1954
Drilling completed November 23rd, 1954
Date Shot From To
With

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13		20'	
10	62		Size of
8 1/4	226		Depth set
6 1/2		827	Perf. top
5 3/16			Perf. bottom
3			Perf. top
2			Perf. bottom
Liners Used			

Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume 80,000 Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil Very good showing 20 bbls., 1st 24 hrs.
Fresh water 31-58' feet
Salt water NONE feet


CASING CEMENTED NONE No. Ft. _____ Date _____
COAL WAS ENCOUNTERED AT NONE FEET _____ INCHES
FEET INCHES FEET INCHES
FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Red Rock			Surface	31			
Red Rock							
Lime and sand	Brown	Hard	31	580		1600	
Lime	Black	"	580	626			
Slate	Grey	"	626	645			
Shale & Lime	Black	Soft	645	780			
Red Rock	Red	Hard	780	805			
Slate-Lime	Black	"	805	980	SHELLS		
Sand	White	W	980	1010			
Break	Black	"	1010	1012			
Lime-Slate	Brown	"	1012	1170	Shells		
Sand	White	"	1170	1240	1st, salt		
Break	Black	soft	1240	1300	Slate & Lime shells		
Sand	Brown	Hard	1300	1410	2nd, salt		
Lime shells	Black	"	1410	1570			
Sand	Brown	"	1570	1600	Maxton Sand		
Big Lime	White	"	1600	1668			
Keener Sand	White	"	1668	1702	Oil & gas	1668 to 1672	
B. Injun S	Brown	"	1702	1840	Bottom hole		

Well to be hydraulically fractured and possibly deepened

*1.5 mi. S of 390 35' of
1.26 mi. W of 6048' SC -
New Martinsville Prod*

*1668
800
800*



Fract 1955



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Quadrangle New Martinsville
Permit No. Dye-218-D

WELL RECORD

Oil or Gas Well Dye
(KIND)

Company Glenn F. McBurney
Address Box 114-Sistersville, W. Va.
Farm Daisy W. Mercer Acres 50 3/4
Location (waters) Ten Mile
Well No. 1 Elev. 800'
District Ellsworth County Tyler
The surface of tract is owned in fee by Daisy W. Mercer
Address R.F.D # 2 New Martinsville, W. Va.
Mineral rights are owned by Glenn F. McBurney LEASED
Address Box 114-Sistersville, W. Va.
Drilling commenced February 7-1954.
Drilling completed November 23rd, 1954. Have been fishing until July 15, 1958.
Date Shot From To
With _____
Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure ~~xxxxxxx~~ lbs. _____ hrs.
Oil Tested around 20 bbls., 1st 24 hrs.
WELL ACIDIZED No
WELL FRACTURED No

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16 "	Conductor		
13 "	NONE	xxxxx	
10 "	67 ft		Size of
8 1/4 "	288'		Depth set
6 5/8 "	827 also drilling nipple of around 13'		
3 "			Perf. top
2 "			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
COAL WAS ENCOUNTERED AT NONE FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES

RESULT AFTER TREATMENT _____
ROCK PRESSURE AFTER TREATMENT _____
Fresh Water 31-58-120-288 Feet _____ Salt Water _____ Feet _____

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
In addition to log filed to bottom of Squaw Sand at 1840 feet.							
Black slate		hard	1840	2065			
White lime		hard	2065	2105			
Slate & Lime	Brown	soft	2103	2197			
Lime Shells	Gray	Soft	2197	2348			Tools stuck, cannot recover. Top of tools 2300 feet.

