

WR-38
Date: 05.14.2014

API# 047-095-1022 P

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Spencer Alva D. Operator Well No: M.W. Spencer No.22
LOCATION: Elevation: 757' Quadrangle: Shirley 7.5'
District: McElroy County: Tyler
Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Well Type: OIL _____ GAS XXXX

Company: Gastar Exploration, LTD Coal Operator N/A
229 W. Main Street or owner _____
Clarksburg, WV 26301 _____

Agent: Mike McCown Coal Lessee N/A
With declaration _____

Permit Issued Date: 10/21/2013

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Tyler

ss:


Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Michael Goff Oil and Gas Inspector representing the Director, say that said work was commenced on the 5th day of May 2014 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1790'	1640'	Rods 1844'	0
Cement	Reset 1790'	1640'	2 3/8" 1852'	0
Cement	1050'	950'	5 1/2" 747'	949'
Cement	800'	700'		
Cement	550'	350"		
Cement	100'	Surface	8 5/8" cement to surface in drilling operation	

Tag Plug @ 1580'; 948', 345'.
Shot 5 1/2" @ 999' ; 747', Free.

Description of monument: 7 inch casing - 8 ft long with API# welded on it and that the work of plugging and filling said well was completed on the 14th day of May 2014.
And further deponents saith not.

Sworn and subscribe before me this 20th day of May 2014



June 3, 2020

Notary Public
Michael A. Goff

RECEIVED
Office of Oil and Gas

SEP 10 2014

WV Department of
Environmental Protection
09/19/2014