

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PM Furbee
 LOCATION: Elevation: 984'
 District: McElroy
 Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
 Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Operator Well No.: No. 7
 Quadrangle: Shirley 7.5'
 County: Tyler

Well Type: OIL X GAS XXXX


Company: Gastar Exploration, Ltd.
229 W. Main Street
Clarksburg, WV 26301

Coal Operator or owner: NA

Coal Lessee With declaration: NA

Agent: Mike McCown

Permit Issued Date: 12/09/2011



AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Tyler ss:


Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 8th day of February 2012 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1904'	1800'	Rods 2000'	0'
Cement	1260'	1160'	2 3/8" 2000'	0'
Cement	860'	750'		
Cement	650'	550'	5 1/2" 322'	No Records
Cement	450'	300'		
Cement	298'	0'	7" 0'	2025'
Cement				
6% Gel between each plug				
Shot 5 1/2" @ 1203"; 1 time; 809'; 1 time; 599'; 1 time; 391'; 1 time; 322'; Free; Shot 7" @ 297'; 1 time; 209'; 1 time; 106'; 1 time; Not Free; Tagged plug @ 1150'; 289'; reset plug 1904' - 1800'; 1260' - 1160'; Tried to back off and could not back 7" off.				

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 16th day of February 2012.

And further deponents saith not. Jason Meadows
 Sworn and subscribe before me this 19 day of March, 2012
 My commission expires: May 24, 2016

Suzann Bryant
 Notary Public
3-19-12



03/30/2012