

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Thomas Smith Operator Well No.: No. 1
 LOCATION: Elevation: 940' Quadrangle: Shirley 7.5'
 District: McElroy County: Tyler
 Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
 Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Well Type: OIL X GAS XXXX

Company: Gastar Exploration, Ltd. Coal Operator NA
229 W. Main Street or owner
Clarksburg, WV 26301

Agent: Mike McCown Coal Lessee RECEIVED
 With declaration SEP 10 2012

Permit Issued Date: 04/30/2012

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Tyler ss:


SEP 10 2012
Department of
Environmental Protection

Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 7th day of July 2012 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1950'	1800'		
Cement	1238'	1138'	2 3/8" 2000'	0'
Cement	860'	760'		
Cement	545'	250'	5" 0'	1188'
Cement	250'	100'		
Cement	99'	0'		
Cement				
6% Gel between each plug				
Shot 5" @ 1188'; 1 time; 809'; 1 time; 495'; 1 time; 386'; 1 time; 297'; 1 time; 194'; 1 time; 109'; 1 time ; tried to back off; Tagged plug @ 1802'; 756'; 99';				

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 12th day of July 2012.

And further deponents saith not. Jessie Meadows
 Sworn and subscribe before me this 30 day of August, 2012
 My commission expires: December 24, 2017



Zelma Meadows
Notary Public

09/14/2012