

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL & GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: Wadsworth, Frances & C.I. Operator Well No.: J. Lemasters H-11
 Location: Elevation: 967' Quadrangle: Centerpoint
 District: McElroy County: Tyler
 Latitude: 11,950 Feet South of: 39 Deg. 30 Min. Sec.
 Longitude: 6500 Feet West of: 80 Deg. 40 Min. Sec.

Well Type: Oil Gas WIW

Company: HG Energy, LLC Coal Operator
5260 Dupont Road or Owner
Parkersburg, WV 26101

Agent: Diane White Coal Operator
 or Owner

Permit Issued: 10/9/15

AFFIDAVIT

State of West Virginia, County of Wood ss:

Jared Stemple and Kenneth Dotson being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of June, 20 16 and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Class A Cement	2900'	2750'	4 1/2" 620'	2357'
Class A Cement	1800'	1700'	2 3/8" 2940'	0'
Class A Cement	1025'	925'		
Class A Cement	300'	Surface		
Set CIB plug @ 2900', Pulled 620' of 4 1/2" and got casing hung.				
Perforated one shot every ten feet - 1020' to 720', 300' to 100'. One shot per foot 980' - 970'.				
6% gel between all cement plugs				

Received
Office of Oil & Gas
JUL 05 2016


Description of monument: 7" Cemented Pipe and that the work of plugging and filling said well was completed on the 14th day of June, 20 16

And further deponents saith not.

Kenneth Dotson

Sworn and subscribed before me this 1st day of July, 20 16
 My commission expires: 7-11-2022

Notary Public Diane White



Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught

Title: Oil & Gas Inspector

07/15/2016