

**STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL & GAS**

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

| | | | |
|----------------|--------------------------------------|------------------------|--|
| Farm Name: | <u>Wadsworth, Randy & Terry</u> | Operator Well No.: | <u>F. Lemasters 13</u> |
| Location: | Elevation: <u>931'</u> | Quadrangle: | <u>Centerpoint 7.5'</u> |
| | District: <u>McElroy</u> | County: | <u>Tyler</u> |
| | Latitude: <u>3,575</u> | Feet South of: | <u>39</u> Deg. <u>27</u> Min. <u>30</u> Sec. |
| | Longitude: <u>9750</u> | Feet West of: | <u>80</u> Deg. <u>40</u> Min. <u></u> Sec. |
| Well Type: | Oil <u>X</u> Gas <u></u> WIW <u></u> | | |
| Company: | <u>HG Energy, LLC</u> | Coal Operator or Owner | <u></u> |
| | <u>5260 Dupont Road</u> | | <u></u> |
| | <u>Parkersburg, WV 26101</u> | | <u></u> |
| Agent: | <u>Diane White</u> | Coal Operator or Owner | <u></u> |
| Permit Issued: | <u>9/8/16</u> | | <u></u> |

AFFIDAVIT

State of West Virginia, County of Wood ss:

Jared Stemple and Ken Dotson being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19th day of October, 20 16 and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--|-------|-------|--------------|-------|
| CIB Plug | 2765' | | | |
| Class A Cement | 2765' | 2650' | 41/2" 886' | 2053' |
| Class A Cement | 1850' | 1750' | 7" | 580' |
| Class A Cement | 980' | 830' | | |
| Class A Cement | 625' | 525' | | |
| Class A Cement | 100' | 0' | | |
| Set CIB plug below bottom hole cement plug. Perforated 980' - 880' (one shot every 10'). | | | | |
| 6% gel between all cement plugs | | | | |
| RECEIVED Office of Oil and Gas | | | | |

Description of monument: 7" Cemented Pipe and that the work of plugging and filling said well was completed on the 26th day of October, 20 16

And further deponents saith not.


Sworn and subscribed before me this 12TH day of DECEMBER, 20 16

My commission expires: 11-2-2021

Notary Public [Signature]

Affidavit reviewed by the Office of Oil and Gas: [Signature]

Title: Oil & Gas Inspector



12/16/2016