



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

324

WELL RECORD

Permit No. Drilled in 1912


Oil or Gas Well Gas  
(KIND)

Company The Mfrs. Light & Heat Co.  
Address 800 Union Trust Bldg., Pittsburgh, Pa.  
Farm Marion McIntire Acres 93  
Location (waters) \_\_\_\_\_  
Well No. 1 - 1527 Elev. 945 ft.  
District McElroy County Tyler  
The surface of tract is owned in fee by Estella Spencer  
Middlebourne Address W. Va.  
Mineral rights are owned by The Mfrs Light & Heat Co.  
800 Union Trust Bldg., Address Pittsburgh, Pa.  
Drilling commenced ?  
Drilling completed 10/26/12  
Date shot \_\_\_\_\_ Depth of shot \_\_\_\_\_  
Open Flow /10ths Water in \_\_\_\_\_ Inch  
/10ths Merc. in \_\_\_\_\_ Inch  
Volume \_\_\_\_\_ Cu. Ft.  
Rock Pressure 335 lbs \_\_\_\_\_ hrs.  
Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
Fresh water \_\_\_\_\_ feet  
Salt water \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	<u>130 ft.</u>		Size of
8 1/4	<u>1105 ft.</u>		<u>3 x 6 5/8"</u>
6 3/8	<u>1833 ft.</u>		Depth set
5 3/16			<u>2369 ft.</u>
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_  
COAL WAS ENCOUNTERED AT 135 FEET 24 INCHES  
591 FEET 48 INCHES FEET INCHES  
FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Native Coal			135	137			
Pittsburgh Coal			591	595			
Sand & Shells			655	685			
Little Dunkard			957	1080			
Big Dunkard			1100	1150			
Gas Sand			1218	1248			
1st Salt Sand			1302	1350			
2nd Salt Sand			1420	1525			
3rd Salt Sand			1526	1560			
Maxon Sand			1712	1732			
Little Lime			1794	1807			
Pencil Cave			1807	1820			
Big Lime			1821	1891			
Big Injun			1891	2110			
Gants Sand			2445	2490			
Garden Sand			2677	2702			
Total depth				2770			
							1st Pay 2681 - 2682 Pay 2690 - 2695



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date..... May 22nd, ..... 1941

APPROVED..... THE MANUFACTURERS LIGHT & HEAT CO., ..... Owner

By..... Harry H. Fowler .....  
 Land Dept. (Title) Office Manager.

