

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: S.M. Shriver Operator Well No.: 8273

LOCATION: Elevation: 1486' Quadrangle: Hundred WV, PA
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 39 Min. 25.92 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 51.04 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 04/06/2022 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18th day of July, 2022, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--|-------|---------|---|---------|
| Thixotropic w/ Green Dye and Gas Block | 1593' | 1093' | | |
| Expandable Cement | 1093' | Surface | | |
| 7" Casing | | | 371' | None |
| 8 5/8" Casing | 829' | Unknown | 0' (multiple cuts, perforations and rips) | Unknown |
| | | | | |

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 5th day of August, 2022.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 26 day of August, 2022

My commission expires: June 8, 2027 Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ALBERT E. & BRENDA S. REYNOLDS
Lease or Property Owner
81 POGUE RUN RD. BURTON, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED W.VA, PA
Well Location
CHURCH
District
WETZEL
County
8273
Well No.
S.M. SHRIVER
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18th day of July, 2022 and that the well was plugged in the following manner:

| Sand or Zone Record Formation | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|-------------------------------|--|--|---------------|----------------|
| | Cleaned out existing 7" casing from the surface to 647'. Removed 371' of 7" casing from the surface to 371'. Cleaned a 12 1/4" hole from the surface to 327'. Reduced the hole to 9 7/8" at 371'. Cleaned a 9 7/8" hole from 371' to the top of the existing 8 5/8" casing at 829'. Reduced the hole to 7 7/8" at 829'. Cleaned out existing 8 5/8" casing from 829' to 1593'. Attempted to remove the 8 5/8" casing from 829' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 829' to an unknown depth. Cut the remaining 8 5/8" casing below, through and above the Pittsburgh Coal Seam (1293.8 - 1300.9') at 1499.5', 1449', 1398.9', 1348.5', 1308.7', 1304.7', 1299', 1297', 1295.1', 1293.8', 1291.9', 1287', 1242', 1195, 1193' and 1191.8'. Perforated the remaining 8 5/8" casing with 4 shots at each of the following depths: 1310.8', 1305.8', 1300.9' and 1283.8'. The 8 5/8" casing was previously ripped from 1263' to 1254', 1146' to 1141' and from 864' to 860'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1293.8' - 1300.9'). Left 20' of 16" conductor in the hole from the surface to 20'. Cemented the hole from 1593' to the surface as follows: From 1593' to 1093' with 155 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 1093'. Cemented the hole from 1093' to the surface with 560 sacks of Expandable Cement. Cement did circulate at the surface. A total of 715 sacks of cement were used to fill the hole from 1593' to the surface. | 8 5/8" Casing 16" Conductor | 0' 0' | Unknown 20' |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | <u>1293.8' - 1300.9'</u> | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |

... and that the work of plugging and filling said well was completed on the 5th day of August, 2022

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright


Kevin S. Wright

Sworn to and subscribed before me this 26 day of August, 2022

Christopher Andrew Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-00275
Well No. 8273
Latitude: 39° 39' 25.92"N
Longitude: -80° 24' 51.04"W