

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7332

LOCATION: Elevation: 1191 Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: 39.51198 Feet South of 39 Deg. 30 Min. 43.1119 Sec.
Longitude: -80.51898 Feet West of -80 Deg. 31 Min. 08.328 Sec.

Well Type: OIL GAS

Company West Virginia Land Resources, Inc Coal Operator West Virginia Land Resources, Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 08/28/2023 _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 9th day of September, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thix w/ Green Dye and Gas Blocker	1214'	801'	16" Conductor Casing - 0'	14'
Expandable	801'	Surface		

Description of monument: 77" of 7" casing with Company Name, Well #, API #, and Date Completed and that the work of plugging and filling said well was completed on the 25th day of September, 2024.

And further deponents saith not. Matthew A. Yearsley
Thomas Thrasher



Sworn and subscribe before me this 8th day of October, 2024

My commission expires: June 8, 2027
Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JOHN DALE COEN
Lease or Property Owner
666 S LINDEN AVE, ALLIANCE, OH 44601
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Big Run, W.Va
Well Location
GRANT
District
WETZEL
County
7332
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by WEST VIRGINIA LAND RESOURCES, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10th day of September, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from surface to 475'. Reduced to 9 7/8" bit and cleaned 9 7/8" hole from 475' to 1214'. Cleaned 9 7/8" hole through the Pittsburgh Coal (1001' - 1007'). <u>Cemented Hole from 1214' to surface as follows:</u> Cemented hole from 1214' to 801' using 215 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 801' to surface using 450 sacks of Expandable Cement. Cement did circulate at the surface. A total of 665 sacks of cement were used to fill the hole from 1214' to the surface. Left 14' of 16" conductor from surface to 14'.	16" Conductor Casing	0'	14'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1001' - 1007'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 25th day of September, 2024

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Thomas Thrasher


Thomas Thrasher

Sworn to and subscribed before me this 8th day of October, 2024

[Signature]
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-00292
Well No. 7332
Latitude: 39° 30' 43.11"N
Longitude: -80° 31' 08.33"W