

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554

WALTER B. & ROSIA LEE SMITH
Lease or Property Owner
1478 PICKENPAW RD. SMITHFIELD, WV 26437

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address
Glover Gap W.VA

Well Location

GRANT

District

WETZEL

County

7498

Well No.

SMITH, WALTER B.

Farm

RECEIVED
Office of Oil and Gas

JUN 29 2026

WV Department of
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT


Stephen Mccoy Digitally signed by Stephen Mccoy
Date: 2026.06.22 08:49:39 -04'00'

STATE OF WEST VIRGINIA,
County of MARSHALL ss:

MATTHEW A. YEARSLEY and **CODY WEAVER** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6th day of March, 2026 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned a 4 ¾ hole through existing 5 ½" casing from surface to bottom of 5 ½" casing at 1,548'. Continued cleaning a 4 ¾" hole from 1,548' to bottom of well at 1,980'. Attempted to remove 5 ½" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left 1,548' of 5 ½" casing from surface to 1,548'. Well was a coal research well drilled laterally through the Pittsburgh Coal Seam. Cleaned a 4 ¾" hole through the Pittsburgh Coal Seam from 883' to 1980'. Left 39' of 8 3/8" surface casing from surface to 39'. Cement hole from 1,980' to surface as follows: Cemented hole from 1,980' to 1,250' using 170 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 1250' to surface using 130 sacks of Thixotropic Cement. Cement did circulate at the surface. A total of 300 sacks of Cement were used to fill the hole from 1,980' to the surface.	5 ½" Casing	0'	1548'	
		8 5/8" Casing	0'	39'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	883.03' – 1980'	77" of 7" casing w/ company name, well number,		
	(Note: Well was a coal research Well	permit number and date cemented stated on 7"		
	Drilled laterally through the Pittsburgh	casing. Well marker will be attached to cement		
	Seam)	plug at ground level.		

... and that the work of plugging and filling said well was completed on the 17th day of April, 2026

And further deponents said that

NOTARY PUBLIC
STATE OF WEST VIRGINIA
KERRI A MCCORMICK
421 Rolling Hills Vlg, Morgantown, WV 26508
My Commission Expires August 13, 2029

Sworn to and subscribed before me this 11th day of June 2026

My commission expires:

August 13, 2029

Matthew A. Yearsley

Matthew A. Yearsley

Cody Weaver

Cody Weaver


Notary Public

Permit No. 47-103-00598
Well No. 7498
Latitude: 39° 31' 24.15"N
Longitude: 80° 29' 29.43"W

07/10/2026

AFFIDAVIT OF PLUGGING AND FILLING WELL

07/10/2026