

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL & GAS

MAR 30 2015

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: Alfred Efaw  
 Location: Elevation: 1294'  
 District: Center  
 Latitude: \_\_\_\_\_ Feet South of: \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.  
 Longitude: \_\_\_\_\_ Feet West of: \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Operator Well No.: 4  
 Quadrangle: Littleton 7.5'  
 County: Wetzel

Well Type: Oil X Gas \_\_\_\_\_ WIW \_\_\_\_\_

Company: HG Energy, LLC  
5260 Dupont Road  
Parkersburg, WV 26101  
 Agent: Diane White

Coal Operator or Owner: Murray Coal  
46226 National Road  
St. Clairsville, OH 43950  
 Coal Operator or Owner: NA

Permit Issued: 11/24/14

AFFIDAVIT

State of West Virginia, County of Wood ss:

Roger Heldman and Ken Dotson being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20th day of January, 20 15 and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED		LEFT
Cement	2550	2404			
Cement	2350	2175			
Cement	1600	1450	5-3/16"	1700'	902'
Cement	1250	820	6-5/8"	1545'	745'
Cement	770	650	8-1/4"	720'	854'
Cement	304	0	10"	0	317'
Perforated casing 2250'-2350' (1 shot/10'), 1500'-1600' (1 shot/10'), 1150'-1250' (1 shot/10'), 1020'-1070' (1 shot/10'), 1071'-1079' (1 shot/1'), 1080'-1120' (1 shot/10') - Ripped 10" casing @ 175' - Unable to pull					
6% gel between cement plugs					


Description of monument: 10" x 20" and that the work of plugging and filling said well was completed on the 24th day of March, 20 15

And further deponents saith not.

Roger Heldman  
Ken Dotson

Sworn and subscribed before me this 13th day of April, 20 15  
 My commission expires: Oct. 4, 2016

Notary Public S. Dianne Dulaney  
 Affidavit reviewed by the Office of Oil and Gas: [Signature]  
 Title: Inspector



Received  
Office of Oil &  
APR 09 2015

04/17/2015