

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Chas Gilbert Operator Well No.: 7309

LOCATION: Elevation: 1246.21' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: 39.5069232 Feet South of 39 Deg. 30 Min. 24.924 Sec.
Longitude: -80.529766 Feet West of 80 Deg. 31 Min. 47.157 Sec.

Well Type: OIL GAS

Company West Virginia Land Resources, INC Coal Operator West Virginia Land Resources, INC
1 Bridge Street or Owner 1 Bridge Street
Monongah. Wv 26554 Monongah. Wv 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 6/28/2024 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Mathew A. Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of June, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ green dye, gas block	1200'	790	8 5/8" Casing - 0'	UNKNOWN
Expanding	790'	Surface	10 3/4" Casing - 0'	320'
			16" Conductor Casing - 0'	30'

Description of monument: 77' of 7' Casing with company name, Well #, API #, and date completed. and that the work of plugging and filling said well was completed on the 6th day of September, 2024.

And further deponents saith not. Matthew A. Yearsley
Thomas Thrasher



Sworn and subscribe before me this 25 day of September, 2024

My commission expires August 17, 2025 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES
Lease or Property Owner
PO BOX 1023 Havana, FL 32333
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7309
Well No.
CHAS GILBERT
Farm

STATE INSPECTOR SUPERVISING PLUGGING Stephen McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by WEST VIRGINIA LAND RESOURCES, INC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 26th day of June, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 14 3/4" hole from surface to 124'. Reduced hole to 7 7/8". Cleaned a 7 7/8" hole from 124' to 351'. Tagged top of existing 10 3/4" casing at 351'. Reduced hole to 6 1/4". Cleaned a 6 1/4" hole from 351' to 835'. Tagged top of existing 8 5/8" casing at 835'. Cleaned a 6 1/4" hole from 835' to 1200'. Attempted to pull 8 5/8" casing by pulling 150% of string weight. All attempts were unsuccessful. Perforated 8 5/8" casing with 6 shots each at the following depths: 1197', 1147', 1097', 1047', 1007', 1002', 997', 995.3', 993.6', 991.9', 990.5', 985.5', 980.5', 940.5', 890.5'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (990.5' to 997'). <u>Cemented hole from 1200' to surface as follows:</u> Cemented hole from 1200' to 790' with 115 sacks of Thixotropic cement with Green Dye and a Gas Blocker additive. Cemented hole from 790' to surface with 410 sacks of Expanding Cement. Cement did circulate at surface.	8 5/8" Casing	0'	UNKNOWN	
		10 3/4" Casing	0'	320'
		16" Conductor Casing	0'	30'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	990.5'-997'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 6th day of September, 2024

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Thomas Thrasher


Thomas Thrasher

Sworn to and subscribed before me this 25th day of September, 2024.

Christopher Andrew Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-00980
Well No. 7309
Latitude: 39° 30' 24.924"N
Longitude: -80° 31' 31.157"W