

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: H A Riggs 1 Operator Well No.: 7369

LOCATION: Elevation: 1472.05' Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.52582 Feet South of 39 Deg. 31 Min. 32.99 Sec.
Longitude: -80.5131 Feet West of 80 Deg. 30 Min. 47.12 Sec.

Well Type: OIL GAS

Company: West Virginia Land Resources, LLC. Coal Operator West Virginia Land Resources, LLC.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
Permit Issued Date 8/1/2025 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Brad Thrasher and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of December, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expanding Cement	2624'	1455'	2 3/8" Tubing 2624'	0'
Thixotropic Cement	1455'	1047'	5 1/2" Casing 1950'	665'
Expanding Cement	1047'	Surface	7" Casing 0'	Unknown
			16" Conductor 0'	15'

RECEIVED
Office of Oil and Gas

FEB 17 2026

WV Department of
Environmental Protection

Description of monument: 96" of 7" casing with company name, well#, API#, and date cemented and that the work of plugging and filling said well was completed on the 29th day of December, 2025.

And further deponents saith not. Matthew A. Yearsley

Brad Thrasher

Sworn and subscribe before me this 27th day of January, 2026

My commission expires: August 13, 2029 Stephen Mccoy

Notary Public
Digitally signed by Stephen
Mccoy

Affidavit reviewed by the Office of Oil and Gas: Stephen Mccoy Date: 2026.02.05 12:39:38 -05'00' Title: _____

02/20/2026

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
TALL TIMBER INC
Lease or Property Owner
4464 Mannington Rd., Smithfield, WV 26437
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7369
Well No.
H A RIGGS 1
Farm

STATE INSPECTOR SUPERVISING PLUGGING Stephen McCory

Stephen McCory

Digitally signed by Stephen
McCory
Date: 2026.02.05 12:38:55
-05'00'

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

MATTHEW A. YEARSLEY and Brad Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4th day of December 2025 and that the well was plugged in the following manner:


Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 2580' of 5/8" sucker rod. Removed 2624' of 2 3/8" tubing. Perforated 5 1/2" casing at 2515', 2415', 2315', and 2215' using 6 shots at each location for a total of 24 shots. Cemented hole from 2624' to 2061' using 50 sacks of Expanding Cement with Gas Blocker additive. Cut 5 1/2" casing at 2050'. Made a diligent effort to remove casing by pulling 150% of string weight. All attempts were unsuccessful. Removed 1950' of 5 1/2" casing from surface to 1950'. Cut 7" casing at 1454.5' and 1254.5'. Made a diligent effort to remove casing at both cuts by pulling 150% of the string weight. All attempts were unsuccessful. Perforated 7" casing at 1900', 1800', 1700', 1600', 1500', 1404.5', 1354.5', 1304.5', 1259.5', 1254.5', 1252.6', 1250.7', 1248.8', 1247', 1242', 1237', 1197', 1147' using 6 shots at each location for a total of 108 shots. All attempts to remove remaining casing were unsuccessful. Cleaned a 6 1/4" hole through the Pillsburg Coal Seam from 1247' to 1254.5'. Left 15' of 16" conductor from surface to 15'. Cemented Hole from 2051' to Surface as Follows: From 2624' to 1455' using 95sks of Expanding Cement. From 1455' to 1047' using 75 sacks of Thixotropic Cement with Green Dye and a Gas Block additive. From 1047' to surface using 220 sacks of Expanding Cement. A total of 440 sacks of cement were used to cement the hole from 2624' to surface. Cement did circulate at surface.	2 3/8" Tubing	2624'	0'	
	5 1/2" Casing	1950'	685'	
	7"	0'	Unknown	
	16" Conductor	0'	15'	
Coal Seams		Description of Monument		
Pittsburgh	1247' to 1254.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil and Gas

FEB 17 2026

WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 29th day of December 2025



Matthew A Yearsley
Matthew A. Yearsley

Brad Thrasher
Brad Thrasher

Sworn to and subscribed before me this

27th day of January 2026

Kerri McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-01092
Well No. 7369
Latitude: 39° 31' 32.99"W
Longitude: -80° 30' 47.12"W

02/20/2026