

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Levi Shuman Heirs Operator Well No.: 7196

LOCATION: Elevation: 1154.58 Quadrangle: Folsom, WV  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 52.29 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 04.11 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 06/24/21

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:


Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 24th day of June, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1210'	786'		
Expandable Cement	786'	Surface		
8 5/8" Casing	298'	Unknown	0' (multiple cuts)	Unknown
10 3/4" Casing	14'	325'	0'	311'
16" Conductor	Surface	20'	0'	20'

Description of monument: 77' of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 6th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright



Sworn and subscribe before me this 8th day of July, 2021

My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 7/12/21

08/13/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
BERNARD R. ELLIOTT SR.  
Lease or Property Owner  
104 WHITE RD. WELLSBURG, WV 26070  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7196  
Well No.  
LEVI SHUMAN HEIRS  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 7/12/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24<sup>th</sup> day of June, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 9 7/8" hole through the existing 10 3/4" casing from 14' to 298'. Tagged top of existing 8 5/8" casing at 298'. Reduced the hole to 7 7/8" at 298'. Cleaned the hole with a 7 7/8" bit from 298' to 1210'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (998' - 1005'). Attempted to pull existing 8 5/8" casing from 298' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 298' to an unknown depth. Cut remaining 8 5/8" casing at 1205', 1152', 1105', 1055', 1014', 1010', 1005', 1003', 1001', 998', 993', 988', 946' and 895'. Left 311' of 10 3/4" casing in the hole from 14' to 325'. Left 20' of 16" conductor in the hole from 20' to surface.		8 5/8" Casing	0'	Unknown
		10 3/4" Casing	0'	311'
		16" Conductor	0'	20'
<b>Cemented the hole from 1210' to surface as follows:</b> From 1210' to 786' with 120 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 786'. Cemented to hole from 786' to surface with 280 sacks of Expandable Cement. Cement did circulate at surface. A total of 400 sacks of cement were used to fill the hole from 1210' to surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>998' - 1005'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 6<sup>th</sup> day of July, 2021

And further deponents saith not.



*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright

Sworn to and subscribed before me this 9<sup>th</sup> day of July, 2021

*[Signature]* 08/13/2021  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-01106  
Well No. 7196  
Latitude: 39° 29' 52.29"N  
Longitude: -80° 31' 04.11"W