

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7254

LOCATION: Elevation: 958.29' Quadrangle: Big Run, WV
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 19.57 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 05.1828 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 06/22/2021

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 19th day of November, 2021, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic Cement w/ Green Dye and Gas	1027'	655'		
Thixotropic Cement	655'	571'		
Expandable Cement	571'	Surface		
8 5/8" Casing	33'	856'	0' (multiple cuts installed)	823'
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 8th day of December, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 6th day of Jan, 2022



My commission expires: 09/15/22

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

04/15/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

SOUTHERN COUNTRY FARMS INC.
Lease or Property Owner
P.O. BOX 40 SINKS GROVE, WV 24976
Address

WEST VIRGINIA LAND RESOURCES, INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

BIG RUN, WV
Well Location
GRANT
District
WETZEL
County
7254
Well No.
I.D. MORGAN
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Bryan Harris

Inspector

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19th day of November, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to the top of the existing 8 5/8" casing at 33'. Reduced hole to 7 7/8" at 33'. Cleaned a 7 7/8" hole from 33' to 1027'. Attempted to remove existing 8 5/8" casing by pulling 150% of string weight but all attempts were unsuccessful. Left 823' of 8 5/8" casing in the hole from 33' to 856'. Cut remaining 8 5/8" casing at the following depths, 829' 789', 784', 779', 776', 773', 771', 766', 761', 721', 671' and 485'. Cleaned a 7 7/8" hole through Pittsburgh Coal Seam (771.5 - 778.5'). Left 20' of 16" conductor in the hole from the surface to 20'.		8 5/8" Casing	0'	823'
		16" Conductor	0'	20'
Cemented hole from 1027' back to the surface as follows:				
From 1027' to 571' with 135 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic Cement plug at 655'. From 655' to 571' with 25 sacks of Thixotropic Cement. From 571' to surface with 140 sacks of Expandable Cement. Cement did circulate at the surface. A total of 300 sacks of cement were used to fill the hole from 1027' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>771.5 - 778.5</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 8th day of December, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 6th day of Jan, 2022

[Signature]

04/15/2022

Notary Public

My commission expires: 09/15/22

Permit No. 47-103-01170
Well No. 7254
Latitude: 39° 30' 19.57"N
Longitude: -80° 32' 05.17"W