

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Big Run, WV 7.5'
Well Location
Grant
District
Wetzel
County
7328
Well No.
LD 47-103-01427

Digitally signed by Stephen Mccoy
Mccoy
Date: 2025.10.30 22:20:49 -04'00'

Stephen Mccoy

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel :

Bruce Chisler and Kenneth Gump being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21st day of June, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
3Formation				
Clean out hole to 1252', shot off 5-1/2" casing and pulled it out. Shot off 7" at 1202' - made diligent effort to pull 7" - it would not pull. Perforated 7". Trip in tubing to 1152 and cemented back to 845', top of cement is drilled down to 845'. Hole is converted to a degas hole Perforated 7" 1152', 1102', 1052', 1002', 962', 957', 952', 950', 948', 945', 940', 935', 895', 845', every 5' from 845' to 545' Cemented well from 845' to surface on 8-27-25 using 695 sacks		5.5"	1252'	N/A
		7"	0	N/A
Coal Seams		Description of Monument		
Pittsburgh	945' - 952'	6" pipe with information welded on to it		

RECEIVED
Office Of Oil and Gas
NOV 6 2025
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 12th day of July, 2024

And further deponents saith not.


Bruce G. Chisler

Kenneth Gump

Sworn to and subscribed before me this 21 day of Oct, 26

Lisa d. Raber
Notary Public

My commission expires



Permit No. 47-103-01427
Well No. 7328
Latitude:
Longitude:

11/14/2025